## **TECHNICAL MEMORANDUM**

DATA GAP INVESTIGATION REPORT - 2020 International Paper Company Closed Former Wood Treating Site Units Wiggins, Mississippi MSD 980 600 084

PREPARED FOR:

International Paper Company

6400 Poplar Avenue Memphis, Tennessee

US EPA Region 4

COPY TO:

Mississippi Department of Environmental Quality

PREPARED BY:

EarthCon Consultants, Inc.

DATE:

August 10, 2020

## REGISTERED PROFESSIONAL GEOLOGIST STATEMENT

I have reviewed this document in sufficient depth to accept full responsibility for its contents related to the geologic discussion/data/information contained herein.



August 10, 2020

Norman D. Kennel, RPG #0681 EarthCon Consultants, Inc.

Date

## **INTRODUCTION**

This report presents the results of additional investigation activities conducted in June 2020 at the International Paper Company (IP) Closed Former Wood Treating Site in Wiggins, Mississippi (Wiggins facility).

A meeting and site tour were held at the Wiggins facility on December 10, 2019. Meeting attendees included US Environmental Protection Agency (EPA), Mississippi Department of Environmental Quality (MDEQ), IP and EarthCon Consultants, Inc. (EarthCon) personnel. The discussion during the meeting included EPA's concern that elevated concentrations of dissolved wood treating chemical constituents or dense non-aqueous phase liquids (DNAPL) may exist hydraulically downgradient from the closed units/treatment areas at the bottom of the Citronelle/top of the Pascagoula formations. The top of the

Pascagoula formation is an aquitard, consisting of clay; therefore, DNAPL, if present may collect in this zone. Although such conditions have previously been investigated and shown not to be present, several activities were discussed with EPA to further evaluate the potential for DNAPL, and IP agreed to prepare a Data Gap Investigation Work Plan (Work Plan) for EPA review following the meeting.

On January 29, 2020 IP submitted a Work Plan to EPA (**Attachment 1**). The Work Plan elements included the following activities:

- Installation of a "well cluster" in the area between wells WC-40 and WC-44
  - One well to be screened similarly to WC-40
  - The second, deeper well to be screened at the bottom of the Citronelle/top of Pascagoula formations
- Redevelop, purge, and sample existing "deep wells":
  - o WC-43
  - o WC-08A
  - o WCP-8
  - o WP-01
  - o WP-02
- Abandon three shallow wells which were observed inside the closed treatment impoundment area (SWMUs 8, 9 and 10) during the site tour. The wells were examined during the site visit and were found to be approximately 40 feet deep. IP searched available records regarding well installation/construction, functionality and/or intended use of the wells and was unable to locate any information regarding these three wells. Given the location of these wells within the closed units, these wells did not appear to be useful for monitoring the groundwater plume and migration/plume stability and thus they were proposed for abandonment.

The Work Plan was approved by EPA on February 26, 2020. Due to restrictions, and concerns surrounding the COVID-19 pandemic, the field work could not be implemented until the week of June 15, 2020.

The location of the Wiggins facility is shown on **Figure 1**. **Figure 2** shows site features and groundwater monitoring well locations. The results of the June 2020 field activities are summarized in this report as well as documented in the following attachments:

Table 1. Monitoring Well Completion Data

Table 2. MDEQ Permit Monitoring Parameters/GWPS

Table 3. Laboratory Analytical Results Summary – Permit Wells - June 2020

Table 4. Laboratory Analytical Results Summary – Work Plan Wells - June 2020

Table 5. Water Level Data - June 2020

Figure 1. Site Location Map

Figure 2. Wiggins Facility Site Map

Figure 3. Potentiometric Surface Map (June 2020)
Figure 4. Naphthalene Iso-contour lines near WC-40

Attachment 1. Data Gap Work Plan

Attachment 2. Photolog

Attachment 3. Soil Boring/Well Construction Logs/Well Abandonment Reports

Attachment 4. June 2020 Laboratory Analytical Reports

Attachment 5. June 2020 Laboratory Data Quality Assurance Review Memoranda

Attachment 6. Plume Stability Analysis Update Summary

## MONITORING WELL INSTALLATION, DEVELOPMENT AND WELL ABANDONMENT

A monitoring well cluster, consisting of two wells designated WC-56 and WC-57 was installed in an area between monitoring wells WC-40 and WC-44 as shown on **Figure 2**. The purpose of the two new monitoring wells was to assess potential concentrations of creosote constituents and pentachlorophenol (PCP) in and at the bottom of the Citronelle aguifer downgradient from monitoring well WC-40.

The boreholes were drilled using rotary sonic drilling methods by advancing 10-foot long sections of 4.5-inch outer diameter (OD) inner casing and 6.5-inch OD outer casing sonic rods. The 4.5-inch OD rods were advanced 10 feet, then the 6.5-inch OD rods were advanced over the smaller rods to the same depth. The 4.5-inch OD rod was then retrieved to collect the recovered soil core sample. This process was repeated at 10-feet intervals until the desired depth was reached. The larger-diameter sonic rods remained in the borehole and acted as an outer casing until the monitoring well was constructed.

The initial borehole, designated WC-57 was advanced to the contact of the Citronelle and Pascagoula formations (the top of the latter formation is referred to as the Pascagoula clay), at a depth of 142 feet below ground surface (bgs). Soil sample cores were retrieved from the borehole at 10-feet intervals and the samples were placed in a polyethylene sleeve which was placed on a plastic sheet and then cut open. The sample cores were observed, classified, and logged by the on-site geologist. Representative photos of the soil cores are contained in the photolog in **Attachment 2**. The second borehole, designated WC-56 and located approximately 15 feet north of WC-57 was advanced to a total depth of 105' bgs, to match the well construction of WC-40. Soil sample cores were not retrieved from the second boring, as the soil cores from WC-57 were used for logging and well placement purposes.

After reaching the terminal depth of each borehole, groundwater monitoring wells were constructed in each borehole as the larger-diameter sonic rods were retrieved. The monitoring wells were constructed of rigid poly-vinyl chloride (PVC), each with a 10-foot section of screen with 0.010-inch slots. A 20-40 sand filter pack was installed around the screened section to approximately two to three feet above the top of the screen, followed by approximately two to three feet of bentonite pellets. The remainder of the annular space surrounding the riser in each well was filled with grout after the bentonite had hydrated. Each well was completed at the surface with a load-rated monitoring well vault. Soil boring/well construction logs are contained in **Attachment 3**.

After a minimum of 24 hours following well installation, each well was developed with a submersible pump to remove residual materials remaining in the wells and to attempt to re-establish the natural hydraulic flow conditions of the formation around the wells. The wells were developed until the column of water in the well was reasonably free of visible sediment.

The three monitoring wells observed inside the closed treatment impoundment area were abandoned. In addition, two monitoring wells (WC-49I and WC-50I) which were installed in 2007 and were used for chemical injection during the 2008 *In Situ* Chemical Oxidation (ISCO) pilot study were also abandoned 1. (see **Attachment 3** for well abandonment forms).

The location and casing elevation for WC-56, WC-57 as well as several other wells lacking complete survey information were surveyed by a Mississippi-registered surveyor, and the information was added to the site's well network database (summarized in **Table 1**).

<sup>1</sup> Note WC-49I and WC-50I were wells installed during the 2007/2008 ISCO Pilot Study. Groundwater monitoring wells WC-49i and WC-50i, which were installed during the 2011 CAP, remain at the site.

## **GROUNDWATER SAMPLING**

Groundwater samples were collected from the MDEQ Permit-required semi-annual monitoring event wells (WC-8, WC-11, WC-26, WC-39, WC-41, and WC-44), from WC-56, WC-57, and from five additional existing "deep" wells in the vicinity of the closed impoundments (WC-43, WC-08A, WCP-8, WP-01 and WP-02).

Existing monitoring wells WC-43, WC-08A, WCP-8, WP-1, and WP-2 and the new wells WC-56 and WC-57 were developed with a submersible pump until sediment accumulated in the bottom of each well, if any, had been removed and the recovered water was reasonably free of sediment. Prior to development and again prior to sampling, an oil/water interface probe was used to measure the depth to water, the potential presence of light and dense non-aqueous phase-separated layers (LNPAL and DNAPL), and the total depth of each well. Neither LNAPL nor DNAPL was observed in any of the wells accessed during the June 2020 field activities. A potentiometric surface map for the Citronelle Formation (using data from the MDEQ Permit-required wells) is included as **Figure 3**.

The monitoring wells were purged and sampled using the low-flow method described in the EPA Region 4, Science and Ecosystem Support Division, Operating Procedure SESDPROC-301-R4, Groundwater Sampling. Field parameter data including pH, specific conductance, temperature, dissolved oxygen, turbidity, and oxidation-reduction potential were measured during purging and samples were collected after measurements stabilized.

The Work Plan contemplated that a packer would be installed in monitoring wells with screen lengths greater than 10 feet (i.e. WCP-8, WC-08A and WP-2) prior to purging/sampling activities in an attempt to isolate the bottom of the screened interval during sampling.

- Upon review of well construction information, it was determined that WCP-8 was constructed with 25 feet of 6-inch diameter PVC well screen. EarthCon was advised by equipment suppliers contacted that there would be a risk of well screen damage with inflatable packer usage (i.e. due to the larger diameter of the well, increased pressure would be required which may result in damage to the PVC well screen). WCP-8 was therefore sampled using low-flow methods with the intake of the bladder pump deployed at a depth of 5 feet above the bottom of the well (i.e. half-way within the bottom 10-foot screen interval).
- An inflatable packer was placed and inflated approximately 10 feet above the bottom of the screened interval in monitoring wells WC-08A and WP-2 with the intake of the bladder pump deployed at a depth of 5 feet above the bottom of the well (i.e. half-way within the bottom 10 foot screen interval).
  - WC-08A was successfully sampled using the packer assembly (see representative photo in **Attachment 2**). The packer held an air pressure of 30 pounds per square inch (psi) throughout sampling and no drawdown was observed.
  - o WP-2 could not successfully be sampled with the packer assembly due to the well depth and the inability of the bladder pump to successfully deploy at this depth. WP-2 was therefore sampled using low-flow methods with the intake of a variable speed submersible pump deployed at a depth of 5 feet above the bottom of the well (i.e. half-way within the bottom 10-foot screen interval).

## LABORATORY RESULTS

The collected groundwater samples were submitted to Pace Analytical National Laboratory in Mt. Juliet, Tennessee for analysis of the following analytes:

• For the MDEQ Permit required wells; 3&4-methylphenol, fluorene, naphthalene, pentachlorophenol, and phenanthrene using Method 8270C SIM.

For existing monitoring wells WC-43, WC-08A, WCP-8, WP-1, and WP-2 and the new wells (WC-56 and WC-57); the Ground Water Protection Standards (GWPS) constituents listed in the MDEQ permit using EPA Methods 8260B and 8270C.

Quality control (QC) samples consisted of equipment blanks, duplicate samples, and matric spike/matrix spike duplicates. The laboratory analytical reports are contained in **Attachment 4**.

The laboratory results were reviewed and validated (**Attachment 5**), and the validated results were compared to the GWPS. The groundwater sampling results are summarized in **Table 3**, (Permit Required Wells) and **Table 4** (Work Plan Wells).

The analytical results for the groundwater samples collected from the MDEQ Permit Required Wells were all non-detect except for PCP in WC-26 where it was detected at a concentration of 1.45 ug/L (see **Table 3**).

Several constituents were detected in the Work Plan Wells as summarized in Table 4. Several the detections were reported as "J" flagged results due to their estimated low detection below the Reporting Detection Limit (RDL). Two constituents; PCP and Naphthalene were detected at concentrations above their respective MDEQ Groundwater Protection Standard (GWPS).

- The constituents in the sample collected from well WP-1<sup>2</sup> were either estimated concentrations below the RDL or non-detected. A low level of PCP was detected in sample WP-1, however, following Functional Guidelines protocols, the concentration, which equaled that of the associated equipment blank (EB-2), was assumed to be a field artifact and was qualified as non-detected.
- Naphthalene was detected in the sample collected from the newly installed WC-57 (and the duplicate sample collected from WC-57) at a concentration of 59.1 ug/L and 41.7 ug/L respectively (the GWPS for naphthalene is 6.2 ug/L).
- All constituents in the samples collected from WP-2 and WC-43 were non-detect.
- All constituents in the sample collected from WC-56 were non-detect except for estimated concentrations below the RDL for Fluoranthene and Phenanthrene.
- All constituents in the sample collected from WC-8A were non-detect except for estimated concentrations below the RDL for PCP and Phenanthrene.

The Groundwater Plume Analytics® evaluation, including a Ricker Method® Plume Stability Analysis (PSA), was updated utilizing site groundwater data through December 2019. The following is provided as a limited summary of the results. The full graphical display and analyses, including plume map videos, center-of-mass (COM) evaluation maps, and the Spatial Change Indicator™ (SCI) results are included in **Attachment** 6.

The plume stability analysis update indicates that from 2011 through 2019 both the naphthalene and PCP plumes are decreasing with strong statistical confidence. The COM evaluation maps depict very little net movement in both constituents over that same time-period indicating that the plumes are not migrating. This is confirmed by the SCI. The SCI for naphthalene, comparing 2011 to 2019, shows attenuation

<sup>&</sup>lt;sup>2</sup> A review of the soil/boring well log indicates that WP-1 is likely not screened within the Pascagoula Formation, rather it appears as if it also a well completed within the Citronelle Formation. The top of the Pascagoula formation (as described in other site well logs (i.e. WP-2) and encountered in the soil cores recovered during the drilling of WC-57 is a blue-gray stiff Clay. This material was not noted in the WP-1 well log.

(depicted by blue shading) throughout all parts of the plume except proximal to WC-5. The small portion of pink shading depicted in the SCI is because naphthalene was non-detect in WC-5 in 2011 and was measured at 8.23 µg/L in 2019. However, a plot of the naphthalene trend in WC-5 reveals a strongly decreasing trend in this well that is currently very near the GWPS. The SCI for PCP, comparing 2011 to 2019, depicts attenuation throughout most of the plume with small areas of increase proximal to WC-5, WC-23, WC-29 and WC-30. Individual PCP trend charts are provided for these wells for further context. The WC-5 PCP plot depicts a decreasing trend since approximately 1998 with a brief spike following the 2007 injections. The 2011 date appears to be an uncharacteristically low value similar to what was observed for naphthalene in this well. The WC-23 PCP plot has a similar pattern to WC-5 in that 2011 was the only non-detect event but still depicts a strong decreasing trend. The WC-29 PCP plot also shows a strong decreasing trend over time with a relatively recent increase starting in 2017. This increase appears similar to what occurred in 2002 through 2004 which later returned non-detect values in 2010 and 2011. If further monitoring does not result in a return to low levels, this may be an indication of a localized concentration increase or sourcing in this area. The PCP plot in WC-30, which is proximal to WC-29, depicts a similar increase in concentration starting in 2017 that has currently peaked in 2018. Further sampling of these wells will help reveal if this trend will be sustained or short-term as observed in 2002-2004.

Investigative Derived Waste (IDW) generated during field activities was addressed in accordance with USEPA Operating Procedure SESDPROC-202-R3 "Management of Investigative Derived Waste" (<a href="https://www.epa.gov/sites/production/files/2015-06/documents/Management-of-IDW.pdf">https://www.epa.gov/sites/production/files/2015-06/documents/Management-of-IDW.pdf</a>). IDW (i.e., drill cuttings, development/purge water, etc.) was containerized, and the ultimate disposition of the IDW is being evaluated utilizing USEPA Operating Procedure SESDPROC-202-R3.

# **DISCUSSION**

Neither LNAPL nor DNAPL were observed in any of the wells accessed during the June 2020 field activities. Based on potentiometric surface data collected during the June 2020 field activities the Citronelle potentiometric surface continues to indicate a south-southwesterly flow direction. A review of the soil/boring well log indicates that WP-1 is likely not screened within the Pascagoula Formation, rather it appears as if it also a well completed within the Citronelle Formation.

Both the 2019 PSA Update and the 2020 PSA Update evaluated Naphthalene iso-contours nearby, and down-gradient of, WC-40 (see **Figure 4**). The iso-contours are closely aligned with the actual sampling results obtained from WC-57 in June 2020 (i.e. double-digit concentrations). A concentration gradient calculation utilizing the WC-40 December 2018, WC-40 December 2019 and the WC-57 June 2020 naphthalene concentrations (also shown on **Figure 4**), indicates that a concentration equal to or below the GWPS for naphthalene (6.2 ug/L), is expected to be achieved within approximately 15 feet down-gradient of WC-57. This information provides further credence that the naphthalene plume is well defined on the Wiggins facility and near WC-57. The PSA analyses indicate that both the naphthalene and PCP plumes are attenuating. The SCI for PCP reveals that the trends in WC-29 and WC-30 should be monitored closely to assess the occurrence of short-term variability or the development of a possible new trend in these wells.

The results of the recent groundwater sampling event, the newly installed monitoring wells and 2020 PSA Update indicate that the naphthalene and pentachlorophenol plumes are stable and/or decreasing and have been delineated within the bounds of the Wiggins facility itself. We look forward to discussing the results of this Data Gap Investigation with EPA following your review.

**Table 1. Monitoring Well Completion Data** 

Well	Coord	inates <sup>8</sup>	Well Ins	tallation	Eleva	ntion <sup>1</sup>	Scre	en Top	Screer	Bottom	Screen Length
Number	East	North	Ву	Date	Ground	TOC <sup>2</sup>	Depth	Elevation	Depth	Elevation	(feet)
MONITORING	WELLS										
WC-05	892440.09	486293.02	HET <sup>3</sup>	Sep-81	204.71	204.73	15.00	187.90	25.00	177.90	10.00
WC-07 <sup>7</sup>	892491.57	485728.29	LAW <sup>4</sup>	May-83	239.10	241.20	41.00	198.10	60.20	178.90	19.20
WC-08	892560.82	486080.80	LAW	May-83	223.52	224.86	28.20	195.50	47.00	176.70	18.80
WC-08A	892554.92	486076.02	JLGA	Aug-84	223.24	224.43	29.00	194.24	109.00	114.24	20.00
WC-09P	892660.64	486263.69	JLGA	Dec-85	205.76	207.50	83.00	124.50	93.00	114.50	10.00
WC-11	892535.70	486330.19	LAW	May-83	201.18	202.58	6.20	195.00	25.00	176.20	18.80
WC-13	891218.52	486107.59	LAW	Apr-83	239.39	241.17	41.00	198.50	60.20	179.30	19.20
WC-14	892330.47	485826.81	LAW	Aug-83	236.04	238.04	40.90	195.20	60.30	175.80	19.40
WC-19	891355.76	485804.03	JLGA⁵	Jul-84	244.51	247.27	55.00	189.50	65.00	179.50	10.00
WC-21 <sup>7</sup>	892351.28	485578.68	JLGA	Jun-87	240.80	243.30	49.20	191.70	69.30	171.60	20.10
WC-22	891876.60	485885.79	JLGA	Dec-85	243.13	244.68	48.90	194.40	63.90	179.40	15.00
WC-23	891886.89	485693.26	JLGA	Dec-85	246.33	248.10	48.70	197.70	63.70	182.70	15.00
WC-24	891988.82	485536.83	JLGA	Dec-85	246.57	248.91	50.00	197.00	65.00	182.00	15.00
WC-25	892224.04	485542.50	JLGA	Dec-85	242.85	245.75	49.70	193.10	64.70	178.10	15.00
WC-26	891377.37	485532.31	JLGA	Dec-85	245.90	247.80	48.90	197.00	63.90	182.00	15.00
WC-28	892523.73	485528.18	JLGA	Jun-87	236.23	238.22	50.90	185.60	70.90	165.60	20.00
WC-29	892450.77	485615.96	JLGA	Jun-87	240.95	241.59	46.30	192.70	66.30	172.70	20.00
WC-30	892399.26	485683.20	JLGA	Jun-87	242.02	243.27	42.80	198.10	62.80	178.10	20.00
WC-31	892085.94	485915.25	JLGA	Jun-87	236.08	237.70	35.70	200.70	55.80	180.60	20.10
WC-33	891353.23	485855.78	JLGA	Jun-87	244.60	247.03	41.10	203.40	61.10	183.40	20.00
WC-34	891239.29	485863.29	JLGA	Jun-87	242.70	243.83	49.60	191.70	69.60	171.70	20.00
WC-35	891183.41	485949.10	JLGA	Jun-87	241.44	242.69	50.20	189.00	70.20	169.00	20.00
WC-36	891380.16	486427.42	JLGA	Jun-87	232.50	234.38	40.00	194.38	60.00	174.38	20.00
WC-39	892441.54	485230.69	WCC <sub>e</sub>	Sep-91	239.94	242.10	95.00	144.52	105.00	134.52	10.00
WC-40	891916.00	485210.40	WCC	Sep-91	248.42	250.71	95.00	153.42	105.00	143.42	10.00
WC-41	892230.54	484611.18	WCC	Feb-93	248.92	251.43	122.50	126.56	132.50	116.56	10.00
WC-42	892574.90	483999.50	WCC	Feb-93	249.04	252.21	117.00	132.36	127.00	122.36	10.00
WC-43	892235.75	485831.53	WCC	Feb-93	235.81	238.33	106.00	129.23	116.00	119.23	10.00
WC-44	891613.66	484593.86	Premier	Jun-05	240.18	240.03	44.00	196.13	64.00	176.30	20.00
WC-45	891901.46	485234.61	Premier	Oct-06	248.48	248.15	98.00	150.48	108.00	141.48	10.00
WC-46	891924.27	485191.41	Premier	Oct-06	248.30	247.93	65.00	183.30	75.00	173.30	10.00
WC-47	891928.02	485181.15	Premier	Oct-06	248.21	247.77	95.00	153.21	105.00	143.21	10.00

**Table 1. Monitoring Well Completion Data** 

Well	Coord	inates <sup>8</sup>	Well Inst	allation	Eleva	ıtion <sup>1</sup>	Scre	en Top	Screer	Bottom	Screen Length	
Number	East	North	Ву	Date	Ground	TOC <sup>2</sup>	Depth	Elevation	Depth	Elevation	(feet)	
WC-48	892538.87	484869.94	Premier	Oct-06	241.32	240.79	55.00	186.32	65.00	176.32	10.00	
WC-56	891758.32	484923.09	EarthCon	Jun-20	245.84	245.09	95.00	150.09	105.00	140.09	10.00	
WC-57	891769.51	484909.07	EarthCon	Jun-20	245.82	245.11	132.00	113.11	142.00	103.11	10.00	
ILOT STIDY	WELLS											
WC-48i	892433.67	486188.63	EarthCon	Oct-11	214.84	217.84	15.00	202.84	50.00	187.84	15.00	
WC-49s	892428.82	486190.91	EarthCon	Oct-11	214.41	217.71	15.00	202.71	30.00	187.71	15.00	
WC-49i	892433.67	486188.63	EarthCon	Oct-11	214.84	217.84	35.00	182.84	50.00	167.84	15.00	
WC-50i	892458.70	486156.64	EarthCon	Oct-11	218.40	221.41	10.00	211.41	50.00	171.41	10.00	
WC-50s	892454.71	486161.68	EarthCon	Oct-11	217.60	221.10	20.00	201.10	35.00	186.10	15.00	
WC-51i	892490.22	486128.34	EarthCon	Oct-11	220.79	223.64	45.00	178.64	55.00	168.64	10.00	
WC-51s	892485.81	486132.99	EarthCon	Oct-11	219.17	222.97	25.00	197.97	40.00	182.97	15.00	
WC-52i	892338.52	486063.92	EarthCon	Oct-11	221.41	224.76	55.00	169.76	65.00	159.76	10.00	
WC-52s	892332.92	486066.83	EarthCon	Oct-11	221.43	224.93	30.00	194.93	40.00	184.93	10.00	
WC-53i	892406.53	4865051.28	EarthCon	Oct-11	225.21	228.21	55.00	173.21	65.00	163.21	10.00	
WC-53s	892403.78	486057.38	EarthCon	Oct-11	224.81	228.01	35.00	193.01	50.00	178.01	15.00	
WC-54s	892197.81	485908.37	EarthCon	Oct-11	228.92	232.52	35.00	197.52	50.00	182.52	15.00	
WC-55i	892361.63	485902.31	EarthCon	Oct-11	230.80	234.23	55.00	179.23	65.00	169.23	10.00	
WC-55s	892354.82	485908.45	EarthCon	Oct-11	230.84	234.09	35.00	199.09	50.00	180.84	15.00	
ECOVERY \	VELLS											
WCP-1	892489.05	486255.65	JLGA	Nov-88	205.47	208.35	15.50	189.70	40.50	164.70	25.00	
WCP-2	892356.81	486076.48	JLGA	Nov-88	223.14	225.67	32.80	190.00	57.90	165.00	25.10	
WCP-3	892236.87	485928.84	JLGA	Nov-88	229.59	231.85	45.70	183.30	70.70	158.30	25.00	
WCP-4	892040.90	485841.92	JLGA	Nov-88	239.43	242.26	50.00	189.10	75.00	164.10	25.00	
WCP-5	892464.48	485919.85	JLGA	Nov-88	230.57	233.36	35.00	195.30	60.00	170.30	25.00	
WCP-6	892181.51	485784.28	JLGA	Nov-88	238.25	241.38	45.60	193.10	70.60	168.10	25.00	
WCP-7	892043.36	486272.25	JLGA	Nov-88	240.65	244.21	52.00	188.70	77.00	163.70	25.00	
WCP-8	892125.64	485602.41	JLGA	Nov-88	244.09	247.24	56.50	187.50	81.50	162.50	25.00	
WCP-9	891307.75	485835.72	JLGA	Nov-88	243.32	245.62	57.00	186.40	82.00	161.40	25.00	
ASCAGOUL	A WELLS											
WP-1 <sup>9</sup>	892666.23	486260.10	LAW	May-83	205.79	207.52	135.00	N/A	144.40	N/A	9.40	
WP-2	892135.70	485799.89	JLGA	Aug-84	238.60	239.39	169.00	N/A	189.00	N/A	20.00	

**Table 1. Monitoring Well Completion Data** 

Well	Coord	inates <sup>8</sup>	Well Installation		Eleva	ıtion <sup>1</sup>	Scre	en Top	Screen	Bottom	Screen Length
Number	East	North	Ву	Date	Ground	TOC <sup>2</sup>	Depth	Elevation	Depth	Elevation	(feet)
WP-3	892848.43	484755.97	JLGA	Aug-84	239.54	242.59	159.00	N/A	169.00	N/A	10.00
WP-4P	892680.20	486161.95	JLGA	Dec-85	205.40	207.55	167.00	N/A	217.00	N/A	50.00
RECHARGE V	VELLS										
WCR-17	892199.23	486349.48	JLGA	Nov-88	219.90	222.89	30.00	189.90	45.00	174.90	15.00
WCR-2 <sup>7</sup>	892117.96	486306.24	JLGA	Nov-88	221.20	224.19	30.00	191.20	45.00	176.20	15.00
WCR-3 <sup>7</sup>	892028.91	486263.01	JLGA	Nov-88	224.20	226.36	35.00	189.20	50.00	174.20	15.00
WCR-4 <sup>7</sup>	891935.53	486219.77	JLGA	Nov-88	227.30	230.22	35.00	192.30	50.00	177.30	15.00
WCR-5 <sup>7</sup>	892245.91	486368.50	JLGA	Apr-89	218.20	221.02	18.50	199.70	110.50	107.70	92.00
WCR-6 <sup>7</sup>	892159.46	486328.72	JLGA	Apr-89	220.80	223.16	20.00	200.80	110.50	110.30	90.00
WCR-7 <sup>7</sup>	892075.59	486294.13	JLGA	Apr-89	222.80	225.16	16.50	206.30	108.00	114.80	91.50
WCR-8 <sup>7</sup>	891970.98	486235.34	JLGA	Apr-89	226.00	228.83	25.00	201.00	105.00	121.00	80.00

#### Notes:

- 1 All Depths and elevation are in feet, screen depth is measured below ground surface.
- 2 **TOC** = Top of Casing
- 3 HET = Harmon Engineering and Testing Company
- 4 **LAW** = Law Engineering Testing Company
- 5 **JLGA** = James L. Grant and Associates
- 6 **WCC** = Woodward-Clyde Consultants
- Well was abandoned in June 2005.
- 8 Wells were resurveyed in 2020. Coordinate system shown is Mississippi East State Plane (feet).
- A review of the soil/boring well log indicates that WP-1 is likely not screened within the Pascagoula Formation, rather it appears as if it also a well completed within the Citronelle Formation. The top of the Pascagoula formation (as described in other site well logs (i.e. WP-2) and encountered in the soil cores recovered during the drilling of WC-57 is a blue-gray stiff Clay. This material was not noted in the WP-1 well log.
- N/A Information not avaliable.

Prepared by: JB 7/2/2020 Reviewed by: NDK 7/2/2020

Table 2. MDEQ Permit Monitoring Parameters/GWPS

Constituent	GWPS (ug/L)
GWPS	
2,3,4,6-Tetrachlorophenol	1100
2,4,6-Trichlorophenol	3.6
2,4-Dichlorophenol	110
2,4-Dimethylphenol	730
2-Methylnaphthalene	122
2-Methylphenol (o Cresol)	1800
Acenaphthene	370
Acenaphthylene	2190
Anthracene	1800
Benzo(b)fluoranthene	0.092
Benzo(k)fluoranthene	0.92
Carbazole	3.4
Chrysene	9.2
Dibenzofuran	12
Fluoranthene	1500
Phenol	11000
Pyrene	180
Ethylbenzene	700
Xylene	10000
Modified GWPS	
Fluorene	240
Naphthalene	6.2
Pentachlorophenol	1.0
Phenanthrene	1100
3 and 4-Methylphenol (m and p Cresol)*	180*

Prepared by: MAB 02/03/12 Checked by: AGL 02/06/12

## Notes:

\*3- and 4-methylphenol coelute and are reported as a combined result. The 4-methylphenol GWPS is used to compare to the combined results as it is the lower GWPS.

Table 3. Laboratory Analytical Results Summary – Permit Wells - June 2020

		Station	WC-08	WC-39	WC-41	WC-44	Equip. Blank	WC-11	DUP-1	WC-26
		Sample	WC-8	WC-39	WC-41	WC-44	EB-01	WC-11	WC-11	WC-26
		Date	06/15/20	06/15/20	06/15/20	06/15/20	06/15/20	06/15/20	06/15/20	06/16/20
Analyte	Units	GWPS								
3- & 4-Methylphenol	ug/L	180	10.0 U	10.0 U	10.0 U	10.0 U				
Fluorene	ug/L	240	1.0 U	1.0 U	1.0 U	1.0 U				
Naphthalene	ug/L	6.2	1.0 U	1.0 U	1.0 U	1.0 U				
Phenanthrene	ug/L	1100	1.0 U	1.0 U	1.0 U	1.0 U				
Sum of the above	creosote c	onstituents	ND	ND	ND	ND	ND	ND	ND	ND
Pentachlorophenol (PCP)	ug/L	1.0	1.0 U	1.0 U	1.0 U	1.45				

6/23/2020

7/30/2020

Prepared By: NDK Checked By: CAC

Notes:
J - Estimated concentration

**U** - Not detected at the method detection limit shown

ND - Not detected

NA - Not analyzed

DUP - Field duplicate sample
Shaded values exceed the GWPS

Table 4. Laboratory Analytical Results Summary – Work Plan Wells - June 2020

	;	Station	WP-1	WP-2	DUP-02	WC-8A	WC-43	WCP-8	WC-56	DUP-03	WC-57	DUP-4	Equip. Blank
		Sample	WP-1	WP-2	WP-2	WC-8A	WC-43	WCP-8	WC-56	WC-56	WC-57	WC-57	EB-2
		Date	06/17/20	06/17/20	06/17/20	06/17/20	06/17/20	06/17/20	06/18/20	06/18/20	06/18/20	06/18/20	06/17/20
Analyte	Units	<b>GWPS</b>											
Ethylbenzene	ug/L	700	1.0 U										
Xylenes (total)	ug/L	10000	3.0 U										
Sum of the above	VOC para	meters											
Carbazole	ug/L	3.4	0.112 J	10.0 U	10.0 U	10.0 U	10.0 U	5.03 J	10.0 U	10.0 U	10.0 U	0.144 J	10.0 U
Dibenzofuran	ug/L	12	0.252 J	10.0 U	10.0 U	10.0 U	10.0 U	1.64 J	10.0 U	10.0 U	1.16 J	1.52 J	10.0 U
2,4-Dichlorophenol	ug/L	110	10.0 U										
2,4-Dimethylphenol	ug/L	730	10.0 U										
3&4-Methylphenol	ug/L	180	10.0 U										
Phenol	ug/L	11000	4.870 J	10.0 U									
Pentachlorophenol	ug/L	1.0	1.82 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.82
2,4,6-Trichlorophenol	ug/L	3.6	10.0 U										
2,3,4,6-Tetrachlorophenol	ug/L	1100	0.391 J	10.0 U									
Sum of the above S	VOC para	meters	7.445	ND	ND	0.889	ND	6.67	ND	ND	1.16		
Anthracene	ug/L	1800	0.05 UJ	0.05 U	0.05 U	0.05 U	0.05 U	0.0325 J	0.05 U				
Acenaphthene	ug/L	370	0.0354 J	0.05 U	0.05 U	0.05 U	0.05 U	0.509	0.05 U	0.05 U	1.99	1.65	0.05 U
Acenaphtylene	ug/L	2190	0.05 UJ	0.05 U	0.0256 J	0.0206 J	0.05 U						
Benzo(b)fluoranthene	ug/L	0.092	0.05 UJ	0.05 U	0.0170 J	0.05 U							
Benzo(k)fluoranthene	ug/L	0.92	0.0330 J	0.05 U	0.25 U	0.05 U	0.05 U	0.05 U	0.05 U				
Chrysene	ug/L	9.2	0.05 UJ	0.05 U									
Fluoranthene	ug/L	1500	0.1 UJ	0.1 U	0.1 U	0.1 U	0.1 U	0.028 J	0.0213 J	0.0324 J	0.0340 J	0.0371 J	0.1 U
Fluorene	ug/L	240	0.0337 J	0.05 U	0.05 U	0.05 U	0.05 U	4.40	0.05 U	0.05 U	1.05	0.888	0.05 U
Naphthalene	ug/L	6.2	2.48 J	0.25 U	0.25 U	0.25 U	0.25 U	6.09	0.5 U	0.25 U	59.1	41.7	0.25 U
Phenanthrene	ug/L	1100	0.0286 J	0.05 U	0.05 U	0.0183 J	0.05 U	0.937	0.0814 J	0.05 U	0.566	0.400	0.05 U
Pyrene	ug/L	180	0.0209 J	0.05 U	0.0397 J	0.05 U							
2-Methylnaphthalene	ug/L	122	0.1000 J	0.25 U	0.25 U	0.25 U	0.25 U	1.38	0.5 U	0.25 U	5.21 J	3.23 J	0.25 U
Sum of the above SVOC	SIM para	meters	2.7316	ND	ND	0.183	ND	13.38	0.1027	0.0324	67.9416	47.926	

Prepared By:

Checked By:

NDK

CAC

6/29/2020

7/30/2020

# Notes:

U - Not detected at the method detection limit / reporting limit shown or qualifed based on data validation J- Value is an estimate of concetration below the Reported Detection Limit (RDL) or qualifed based on data validation

ND - Not detected

NA - Not Analyzed

FD - Field duplicate sample Shaded values exceed the GWPS

EarthCon Project No. 02.20000006 Copyright © 2020 EarthCon Consultants, Inc. All Rights Reserved


# Table 5 Water Level Data - June 2020


Well Number	Top of Casing Elevation (feet)	Water Depth (feet)	Water Elevation (feet)
WC-8	224.86	32.20	192.66
WC-8A	224.43	32.26	192.17
WC-11	202.58	9.25	193.33
WC-26	247.80	59.40	188.40
WC-39	242.10	54.28	187.82
WC-41	251.43	65.18	186.25
WC-43	238.33	48.14	190.19
WC-44	240.03	53.90	186.13
WP-1	207.52	15.05	192.47
WP-2	239.39	51.14	188.25
WC-56	245.09	62.94	182.15
WC-57	245.11	64.89	180.22
WCP-8	247.24	57.71	189.53


 Prepared By:
 NDK
 7/2/2020


 Checked By:
 HP
 7/2/2020

\_











Emily W. Lee, P.G. (AR, IL, MS, TN) Remediation Project Manager Environment, Health, & Safety 6400 Poplar Avenue Memphis, TN 38197

**T** 901 419 7725 **M** 901 304 4022 emily.lee@ipaper.com

January 29, 2020

Maher Budeir RCRA Corrective Action Section U.S. EPA – Region 4 Sam Nunn Atlanta Federal Center 61 Forsyth Street, SW Atlanta, GA 30303-8960

Subject: Data Gap Investigation Work Plan

International Paper Company

Wood Treating Site, EPA ID # MSD 980 600 084

Wiggins, Mississippi

Dear Mr. Budeir:

International Paper Company submits herein a Data Gap Investigation Work Plan (Work Plan) that includes the elements agreed to in a meeting with EPA, MDEQ, IP and EarthCon representatives during a site visit on December 10, 2019. IP is prepared to begin implementing the Work Plan upon receipt of your approval.

Please do not hesitate to call me at (901) 419-7725 if you need any additional information or have any questions or comments.

Sincerely,

Emily W. Lee, P.G.

Emily W. Lu

Attachments:

cc: Noman Ahsanuzzaman, EPA Region 4

Steve Ginski, IP

Trudy D. Fisher, Butler Snow

Krista Caron, MDEQ Robert Huckaby, MDEQ Norman Kennel, EarthCon Doug Seely, EarthCon

.



# DATA GAP INVESTIGATION WORK PLAN

# INTERNATIONAL PAPER COMPANY CLOSED FORMER WOOD TREATING SITE UNITS WIGGINS, MS 39577 MSD 980 600 084

# PREPARED FOR:

INTERNATIONAL PAPER COMPANY 6400 POPLAR AVENUE MEMPHIS, TN 38197-0001

PREPARED BY:

EARTHCON CONSULTANTS, INC. 1880 WEST OAK PARKWAY BUILDING 100, SUITE 106 MARIETTA, GA 30062

PROJECT NO. 02.20000006

**JANUARY 29, 2020** 



## REGISTERED PROFESSIONAL GEOLOGIST STATEMENT

# DATA GAP INVESTIGATION WORK PLAN INTERNATIONAL PAPER CLOSED FORMER WOOD TREATING SITE UNITS WIGGINS, MS HAZARDOUS WASTE MANAGEMENT FACILITY MSD 980 600 084

I have reviewed this document in sufficient depth to accept full responsibility for its contents related to the geologic discussion/data/information contained herein.

Darrell C. Adkins, RPG #0709

EarthCon Consultants, Inc.

January 29, 2020 Date



# **Table of Contents**

1.0	INTRODUCTION	1
2.0	MONITORING WELL INSTALLATION AND ABANDONMENT	2
2.1	Utility Locating	2
2.2	2 Soil Borings	2
2.3	B Monitoring Well Installation	3
2.3	B Monitoring Well Abandonment	3
2.4	Surveying	3
3.0	MONITORING WELL REDEVELOPMENT	
4.0	GROUND WATER SAMPLING	3
4.1	Laboratory Analyses	4
4.2	2 Quality Assurance and Quality Control	4
5.0	INVESTIGATIVE-DERIVED WASTE MANAGEMENT	4
6.0	REPORT PREPARATION	5



# **List of Tables**

Table 1. Monitoring Well Completion Data Table 2. Monitoring Parameters and GWPS

# **List of Figures**

Figure 1.	Site Location Map
Figure 2.	Wiggins Facility Site Map
Figure 3.	Citronelle Aquifer Potentiometric Surface Map December 9, 2019
Figure 4.	Pascagoula Aquifer Potentiometric Surface Map December 9, 2019
Figure 5.	Proposed Well Locations Map

# **List of Appendices**

Appendix A	Soil Boring and Well Construction Logs for Select Wells
Appendix B	Photographs
Appendix C	Fieldwork Documentation Forms



#### 1.0 INTRODUCTION

International Paper Company (IP) is conducting corrective action and groundwater monitoring at the Closed Former Wood Treating Site Units in Wiggins, Mississippi (Wiggins facility) according to the State of Mississippi Hazardous Waste Management Permit HW-980-600-084 that was issued on May 4, 2010 and the HSWA portion of the permit that became effective January 4, 1993.

In a meeting held on December 10, 2019, attended by US Environmental Protection Agency (EPA), Mississippi Department of Environmental Quality (MDEQ), IP and EarthCon Consultants, Inc. (EarthCon) personnel, it was agreed the IP would prepare a Data Gap Investigation Work Plan (Work Plan) for EPA review to include the elements summarized in the following meeting summary:

- Installation of a "well cluster" in the area between wells WC-40 and WC-44 (actual location to be based upon a review of the potentiometric surface data collected on December 9, 2019)
  - o One well is to be screened similarly to WC-40 (~135-145' msl).
  - o The second, deeper well will be screened at the bottom of the Citronelle/top of Pascagoula formations (~115-125' msl).
  - The wells will be purged and sampled per methods used for other routine site well sampling.
- The following wells will be redeveloped, purged, and sampled:
  - o WC-43
  - o WC-08A
  - o WCP-8
  - o WP-01
  - o WP-02
- Wells with greater than 10' of well screen (i.e. WC-08A, WCP-8 and WP-02) will utilize a "packer" to isolate the bottom 10' of the screen length during sampling.

The discussion during the meeting included EPA's concern that elevated concentrations of dissolved wood treating chemical constituents or dense non-aqueous phase liquids (DNAPL) may exist hydraulically downgradient from the closed units at the bottom of the Citronelle/top of the Pascagoula formations. The top of the Pascagoula formation is an aquitard, consisting of clay; therefore, DNAPL, if present may collect in this zone.

EPA, MDEQ, IP and EarthCon representatives also conducted a site visit on December 10, 2019. During the site visit, three shallow wells were observed inside the closed treatment impoundment area (see attached example photograph in Appendix B). The wells were examined during the site visit and were found to be approximately 40 feet deep. IP searched available records regarding well installation/construction, functionality and/or intended use of the wells and was unable to locate any information regarding these three wells.

Included in this Work Plan are a site location map (**Figure 1**), a site map showing features at the Wiggins facility and existing monitoring well locations (**Figure 2**), and potentiometric surface maps for the Citronelle and Pascagoula formation wells based on data collected in December 2019

**BUSINESS SOLUTIONS** ®



(**Figures 3 and 4**). A summary of monitoring well construction data is also attached for reference (**Table 1**). Drilling and well construction logs for WC-08A, WC-40, WC-43, WC-44, WCP-8, WP-1 and WP-2 are included in **Appendix A**.

## 2.0 MONITORING WELL INSTALLATION AND ABANDONMENT

A monitoring well cluster, consisting of two wells designated WC-56 and WC-57 will be installed in an area between monitoring wells WC-40 and WC-44 as shown on **Figure 5**. The location of the well cluster is hydraulically downgradient of WC-40 based on December 2019 potentiometric surface data (**Figure 3**). The purpose of the two new monitoring wells is to assess potential concentrations of creosote constituents and pentachlorophenol (PCP) in the Citronelle aquifer downgradient from monitoring well WC-40:

- At a similar screen depth as WC-40; and
- At a greater depth; i.e. the at the bottom of the Citronelle/top of Pascagoula formation.

During the same mobilization to install the monitoring well cluster, the three existing monitoring wells identified inside the closed treatment impoundment area will be abandoned.

Monitoring well installation and abandonment will be conducted by a Mississippi-licensed Water Well Contractor and in accordance with applicable guidance included in EPA Region 4 SESDGUID-1-1-R0, Design and Installation of Monitoring Wells (<a href="https://www.epa.gov/sites/production/files/2014-">https://www.epa.gov/sites/production/files/2014-</a>

<u>O3/documents/appendix m monitor well installation.pdf) and MDEQ Administrative Procedures Act Rules Title 11, Part 7, Surface Water and Groundwater Use and Protection, Licensing of Water Well Contractors and Dam Safety Regulations (https://www.mdeq.ms.gov/wp-content/uploads/2017/10/WellDrillerRegs..pdf).</u>

## 2.1 Utility Locating

Prior to drilling the boreholes for WC-56 and WC-57, Mississippi 811 will be contacted to identify the locations of public underground utilities in the vicinity of the work. In addition, facility utility information will be requested from Baldwin Pole Mississippi, and a private utility locating service will be contacted to identify potential conflicts with private underground utilities at the proposed boring locations.

## 2.2 Soil Borings

The boreholes will be drilled using the rotary sonic drilling method. The drilling will involve advancing 10-feet long sections of 4.5-inch outer diameter (OD) and 6.5-inch OD sonic rods. The 4.5-inch OD rod will be advanced 10 feet, then the 6.5-inch OD rod will be advanced over the smaller rod to the same depth. The 4.5-inch rod will then be retrieved to collect the soil sample. This process will be repeated at 10-feet intervals until the desired depth is reached.

The initial borehole, designated WC-56 will be advanced to the contact of the Citronelle and Pascagoula formations (the top of the latter formation is referred to as the Pascagoula clay), this contact has been identified at the Wiggins site as being a yellow to bluish-gray stiff silty clay. The



second borehole, designated WC-57 will be placed within approximately ten feet from WC-56 and to a depth of approximately 20 feet above the top of the Pascagoula clay. Soil samples will be retrieved from each borehole at 10-feet intervals and the samples will be placed in a polyethylene sleeve. The samples will be observed, classified and logged by the on-site geologist. The larger-diameter sonic rods remain in the borehole and act as an outer casing until the monitoring well is constructed.

# 2.3 Monitoring Well Installation

After reaching the terminal depth of each borehole, a groundwater monitoring well will be constructed in each borehole as the larger-diameter sonic rods are retrieved. The monitoring wells will be constructed of rigid poly-vinyl chloride (PVC), each with a 10-feet section of screen with 0.010-inch slots. A 20-40 sand filter pack will be installed around the screened section to approximately two feet above the top of the screen, followed by approximately two feet of bentonite pellets. The remainder of the annular space surrounding the riser will be filled with grout after the bentonite is hydrated. Each well will be completed at the surface with a load-rated locking monitoring well vault. After a minimum of 24 hours following well installation and surface completion, each well will be developed to remove residual materials remaining in the wells and to attempt to re-establish the natural hydraulic flow conditions of the formation around the wells. Well development methods used will include pumping with a submersible pump and/or an air-lift pump. The wells will be developed until the column of water in the well is reasonably free of visible sediment.

# 2.3 Monitoring Well Abandonment

The three monitoring wells observed inside the closed treatment impoundment area will be abandoned in a manner consistent with EPA and MDEQ guidance.

# 2.4 Surveying

The location and casing elevation for each newly installed well will be surveyed by a Mississippiregistered surveyor, and the information will be added to the site's well network database.

## 3.0 MONITORING WELL REDEVELOPMENT

Monitoring wells WC-43, WC-08A, WCP-8, WP-1, and WP-2 will be redeveloped prior to sampling. Prior to redevelopment, the depth of each well will be measured and compared to the constructed depth to identify the effort and methods needed for redevelopment. The wells will be redeveloped using a submersible and/or air-lift pump until sediment accumulated in the bottom of each well, if any, has been removed and the recovered water is reasonably free of sediment.

## 4.0 GROUND WATER SAMPLING

Groundwater samples will be collected during the Spring 2020 semi-annual monitoring event. Prior to sampling, an oil/water interface probe will be used to measure the depth to water, the

**BUSINESS SOLUTIONS** ®



potential presence of separate-phase product, and the total depth of each well. Samples will be collected from:

- The permit required site wells,
- The newly installed monitoring wells (WC-56 and WC-57), and
- Wells WC-43, WC-08A, WCP-8, WP01, and WP-2.

Each well will be purged and sampled using the low-flow method described in the EPA Region 4, Science and Ecosystem Support Division, Operating Procedure SESDPROC-301-R4, Groundwater Sampling (<a href="https://www.epa.gov/sites/production/files/2015-06/documents/Groundwater-Sampling.pdf">https://www.epa.gov/sites/production/files/2015-06/documents/Groundwater-Sampling.pdf</a>). Field parameter data including pH, specific conductance, temperature, dissolved oxygen, turbidity, and oxidation-reduction potential will be measured during purging and samples will be collected after measurements have stabilized. The data collected during sampling will be recorded Groundwater Sampling Record. A blank Groundwater Sampling Record form is included in **Appendix C**.

A packer will be installed in monitoring wells with screen lengths greater than 10 feet (i.e. WC-08A, WCP-8 and WP-2) prior to purging/sampling activities in an attempt to isolate the bottom of the screened interval during sampling. An inflatable packer will be installed and inflated approximately 10 feet above the bottom of the screened interval. The depth to water in the casing above the packer will be measured during purging and sampling and the purge/sampling rate will be adjusted to minimize drawdown.

## 4.1 Laboratory Analyses

The samples will be submitted to Pace analytical laboratory in Mt. Juliet, Tennessee for analyses for the Ground Water Protection Standards (GWPS) constituents listed in the MDEQ permit (**Table 2**) using EPA Methods 8260B and 8270C. The laboratory results will be reviewed and validated, and the validated results will be compared to the GWPS.

## 4.2 Quality Assurance and Quality Control

Quality control (QC) samples will consist of one equipment blank, one duplicate sample, a trip blank for each cooler (VOCs only), and a matrix spike/matrix spike duplicate.

## 5.0 INVESTIGATIVE-DERIVED WASTE MANAGEMENT

Investigative Derived Waste (IDW) generated during field activities will be addressed in accordance with USEPA Operating Procedure SESDPROC-202-R3 "Management of Investigative Derived Waste" (<a href="https://www.epa.gov/sites/production/files/2015-06/documents/Management-of-IDW.pdf">https://www.epa.gov/sites/production/files/2015-06/documents/Management-of-IDW.pdf</a>). IDW (i.e. drill cuttings, development/purge water, etc.) will be containerized, and the ultimate disposition of the IDW will be determined once analytical results are received utilizing USEPA Operating Procedure SESDPROC-202-R3.

**BUSINESS SOLUTIONS** ®



## 6.0 REPORT PREPARATION

Upon completion of the fieldwork, receipt of laboratory analyses and data validation, a report will be prepared that will include the following:

- · A narrative summary of fieldwork and findings;
- Soil boring logs and well completion diagrams for each newly installed well;
- Well abandonment documentation;
- Groundwater sampling forms;
- Summary tables of field and laboratory data, including water levels and NAPL measurements;
- A site figure showing the locations of monitoring wells, including the newly installed wells; and,
- Laboratory analytical and data validation reports.



**Table 1. Monitoring Well Completion Data** 

Well	Coord	inates <sup>8</sup>	Well Inst	tallation	Eleva	ation <sup>1</sup>	Scre	en Top	Screen	n Bottom	Screen Length	
Number	East	North	Ву	Date	Ground	TOC <sup>2</sup>	Depth	Elevation	Depth	Elevation	(feet)	
MONITORIN	G WELLS											
WC-05	51798.58	9782.7	HET <sup>3</sup>	Sep-81	204.71	204.73	15	187.9	25	177.9	10	
WC-07 <sup>7</sup>	51871	9216	LAW <sup>4</sup>	May-83	239.1	241.2	41	198.1	60.2	178.9	19.2	
WC-08	51919.91	9570.82	LAW	May-83	223.52	224.86	28.2	195.5	47	176.7	18.8	
WC-11	51894.09	9820.14	LAW	May-83	201.18	202.58	6.2	195	25	176.2	18.8	
WC-13	50577.54	9593.83	LAW	Apr-83	239.39	241.17	41	198.5	60.2	179.3	19.2	
WC-14	51690.28	9316.19	LAW	Aug-83	236.04	238.04	40.9	195.2	60.3	175.8	19.4	
WC-19	50715.63	9290.66	JLGA⁵	Jul-84	244.51	247.27	55	189.5	65	179.5	10	
WC-21 <sup>7</sup>	51734	9044	JLGA	Jun-87	240.8	243.3	49.2	191.7	69.3	171.6	20.1	
WC-22	51236.24	9373.88	JLGA	Dec-85	243.13	244.68	48.9	194.4	63.9	179.4	15	
WC-23	51247.08	9181.39	JLGA	Dec-85	246.33	248.1	48.7	197.7	63.7	182.7	15	
WC-24	51349.14	9025.66	JLGA	Dec-85	247.08	249.64	50	197	65	182	15	
WC-25	51584.65	9031.57	JLGA	Dec-85	242.85	245.75	49.7	193.1	64.7	178.1	15	
WC-28	51884.38	9018.1	JLGA	Jun-87	236.23	238.22	50.9	185.6	70.9	165.6	20	
WC-29	51811.17	9105.67	JLGA	Jun-87	240.95	241.59	46.3	192.7	66.3	172.7	20	
WC-30	51759.47	9172.77	JLGA	Jun-87	242.02	243.27	42.8	198.1	62.8	178.1	20	
WC-31	51445.5	9403.94	JLGA	Jun-87	236.08	237.7	35.7	200.7	55.8	180.6	20.1	
WC-33	50712.96	9342.4	JLGA	Jun-87	244.6	247.03	41.1	203.4	61.1	183.4	20	
WC-34	50599	9349.59	JLGA	Jun-87	242.7	243.83	49.6	191.7	69.6	171.7	20	
WC-35	50542.87	9435.24	JLGA	Jun-87	241.44	242.69	50.2	189	70.2	169	20	
WC-36	9924	50746	JLGA	Jun-87	232.5	234.38	40	194.38	60	174.38	20	
WC-39	51803.03	8720.38	WCC6	Sep-91	239.94	242.1	95	144.52	105	134.52	10	
WC-40	51277.55	8698.61	WCC	Sep-91	248.42	250.71	95	153.42	105	143.42	10	
WC-41	51593.77	8100.28	WCC	Feb-93	248.92	251.43	122.5	126.56	132.5	116.56	10	
WC-42	51939.85	7489.57	WCC	Feb-93	249.04	252.21	117	132.36	127	122.36	10	
WC-43	51595.42	9320.68	WCC	Feb-93	235.81	238.33	106	129.23	116	119.23	10	
WC-44	50976.95	8081.22	Premier	Jun-05	240.18	240.03	44	196.13	64	176.3	20	
WC-45	51262.94	8722.78	Premier	Oct-06	248.48	248.15	98	150.48	108	141.48	10	
WC-46	51285.86	8679.64	Premier	Oct-06	248.30	247.93	65	183.3	75	173.3	10	
WC-47	51289.65	8669.40	Premier	Oct-06	248.21	247.77	95	153.21	105	143.21	10	
WC-48	51906.05	8265.80	Premier	Oct-06	241.32	240.79	55	186.32	65	176.32	10	
PILOT STID	Y WELLS											
WC-48i	486188.63	892433.67	EarthCon	Oct-11	214.84	217.84	15	202.84	50	187.84	15	
WC-49s	486190.91	892428.82	EarthCon	Oct-11	214.41	217.71	15	202.71	30	187.71	15	

EarthCon Project No. 02.20000006.18 Copyright © 2019 EarthCon Consultants, Inc. All Rights Reserved

**Table 1. Monitoring Well Completion Data** 


Well	Coordi	nates <sup>8</sup>	Well Inst	allation	Eleva	ition <sup>1</sup>	Scre	en Top	Screer	Bottom	Screen Length
Number	East	North	Ву	Date	Ground	TOC <sup>2</sup>	Depth	Elevation	Depth	Elevation	(feet)
WC-49i	486188.63	892433.67	EarthCon	Oct-11	214.84	217.84	35	182.84	50	167.84	15
WC-50i	486156.64	892458.70	EarthCon	Oct-11	218.4	221.41	10	211.41	50	171.41	10
WC-50s	486161.68	892454.71	EarthCon	Oct-11	217.6	221.10	20	201.1	35	186.1	15
WC-51i	486128.34	892490.22	EarthCon	Oct-11	220.79	223.64	45	178.64	55	168.64	10
WC-51s	486132.99	892485.81	EarthCon	Oct-11	219.17	222.97	25	197.97	40	182.97	15
WC-52i	486063.92	892338.52	EarthCon	Oct-11	221.41	224.76	55	169.76	65	159.76	10
WC-52s	486066.83	892332.92	EarthCon	Oct-11	221.43	224.93	30	194.93	40	184.93	10
WC-53i	4865051.28	892406.53	EarthCon	Oct-11	225.21	228.21	55	173.21	65	163.21	10
WC-53s	486057.38	892403.78	EarthCon	Oct-11	224.81	228.01	35	193.01	50	178.01	15
WC-54s	485908.37	892197.81	EarthCon	Oct-11	228.92	232.52	35	197.52	50	182.52	15
WC-55i	485902.31	892361.63	EarthCon	Oct-11	230.8	234.23	55	179.23	65	169.23	10
WC-55s	485908.45	892354.82	EarthCon	Oct-11	230.84	234.09	35	199.09	50	180.84	15
RECOVERY	WELLS										
WCP-1	51852.92	9753.23	JLGA	Nov-88	205.47	208.35	15.5	189.7	40.5	164.7	25
WCP-2	51721.74	9566.54	JLGA	Nov-88	223.14	225.67	32.8	190	57.9	165	25.1
WCP-3	51602.79	9410.99	JLGA	Nov-88	229.59	231.85	45.7	183.3	70.7	158.3	25
WCP-4	51388.16	9340.05	JLGA	Nov-88	239.43	242.26	50	189.1	75	164.1	25
WCP-5	51786.76	9403.72	JLGA	Nov-88	230.57	233.36	35	195.3	60	170.3	25
WCP-6	51551.46	9267.35	JLGA	Nov-88	238.25	241.38	45.6	193.1	70.6	168.1	25
WCP-7	51748.16	9105.31	JLGA	Nov-88	240.65	244.21	52	188.7	77	163.7	25
WCP-8	51485.87	9091.15	JLGA	Nov-88	244.09	247.24	56.5	187.5	81.5	162.5	25
WCP-9	50669.18	9325.18	JLGA	Nov-88	243.32	245.62	57	186.4	82	161.4	25
PASCAGOL	JLA WELLS										
WP-1	N/A	N/A	LAW	May-83	205.79	207.52	135	N/A	144.4	N/A	9.4
WP-2	N/A	N/A	JLGA	Aug-84	238.6	239.39	169	N/A	189	N/A	20
WP-3	N/A	N/A	JLGA	Aug-84	239.54	242.59	159	N/A	169	N/A	10
WP-4P	N/A	N/A	JLGA	Dec-85	205.4	207.55	167	N/A	217	N/A	50
RECHARGE	WELLS										
WCR-17	51561	9844	JLGA	Nov-88	219.9	222.89	30	189.9	45	174.9	15
WCR-27	51475	9795	JLGA	Nov-88	221.2	224.19	30	191.2	45	176.2	15
WCR-3 <sup>7</sup>	51386	9751	JLGA	Nov-88	224.2	226.36	35	189.2	50	174.2	15
WCR-4 <sup>7</sup>	51292	9705	JLGA	Nov-88	227.3	230.22	35	192.3	50	177.3	15
WCR-5 <sup>7</sup>	51603	9864	JLGA	Apr-89	218.2	221.02	18.5	199.7	110.5	107.7	92
WCR-6 <sup>7</sup>	51518	9821	JLGA	Apr-89	220.8	223.16	20	200.8	110.5	110.3	90
WCR-7 <sup>7</sup>	51443	9785	JLGA	Apr-89	222.8	225.16	16.5	206.3	108	114.8	91.5

EarthCon Project No. 02.20000006.18 Copyright © 2019 EarthCon Consultants, Inc. All Rights Reserved

**Table 1. Monitoring Well Completion Data** 

Well	Coordinates <sup>8</sup>		Well Installation		Elevation <sup>1</sup>		Screen Top		Screen Bottom		Screen Length
Number	East	North	Ву	Date	Ground	TOC <sup>2</sup>	Depth	Elevation	Depth	Elevation	(feet)
WCR-8 <sup>7</sup>	51327	9719	JLGA	Apr-89	226	228.83	25	201	105	121	80


#### Notes:




Prepared by: TJM 2/25/19 Reviewed by: JRM 2/28/19


Table 2. Monitoring Parameters and GWPS


Constituent	GWPS (ug/L)			
2,3,4,6-Tetrachlorophenol	1100			
2,4,6-Trichlorophenol	3.6			
2,4-Dichlorophenol	110			
2,4-Dimethylphenol	730			
2-Methylnaphthalene	122			
2-Methylphenol (o Cresol)	1800			
3 and 4-Methylphenol (m and p Cresol)*	180**			
Acenaphthene	370			
Acenaphthylene	2190			
Anthracene	1800			
Benzo(b)fluoranthene	0.092			
Benzo(k)fluoranthene	0.92			
Carbazole	3.4			
Chrysene	9.2			
Dibenzofuran	12			
Fluoranthene	1500			
Fluorene*	240			
Naphthalene*	6.2			
Pentachlorophenol*	1.0			
Phenanthrene*	1100			
Phenol	11000			
Pyrene	180			
Ethylbenzene	700			
Xylene	10000			





\_













## APPENDIX A SOIL BORING AND WELL CONSTRUCTION LOGS FOR SELECT WELLS



#### MONITOR WELL INSTALLATION REPORT

DATE COMPLETED 09/12/91  INSPECTED BY Steve Krul  DATE 09/12/91  DATE 09/12/91  DEPTH INTERVAL  ELEVATION  BLEVATION  CROUND SURFACE CASING/ CASING/RISER PIPE ABOVE GROUND SURFACE CASING/RISER PIPE ABOVE GROUND SURFACE CASING AT THE OF SURFACE CASING STEEL THE OF SURFACE CASING BELOW GROUND 4.0'  LD. OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING BELOW GROUND 4.0'  LD. OF SURFACE CASING STEEL THE SURFACE CASING BELOW GROUND 4.0'  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING BELOW GROUND 4.0'  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEPTH OF SURFACE CASING STEEL WITH A 10cking cap  DEP	PROJECTInternational Paper 91B618C	LIC 40
CHECKED BY	ORIGINAL DEPTH 110	AOUIFER Citronelle
RISER PIPE HEIGHT OF TOP OF SURFACE CASING/RISER PPE ABOVE GROUND SURFACE  DEPTH OF SURFACE SEAL BELOW GROUND SURFACE TYPE OF SURFACE CASING TYPE OF SURFACE CASING TYPE OF SURFACE CASING Steel with a locking cap  DEPTH OF SURFACE CASING BELOW GROUND LD. OF RISER PIPE TYPE OF BACKFILL: GROUT PORTLAND DIAMETER OF BOREHOLE DEPTH OF BOREHOLE TYPE OF BACKFILL: GROUT PORTLAND DEPTH OF TOP OF SALL TYPE OF SALL BENDONICE PELETS ELE//DEPTH BOTTOM OF SEAL TYPE OF SAND PACK 2"  THE OF SAND PACK 20/40 Silica Sand DEPTH OF TOP OF SAND PACK BI'  DESCRIBE OPENINGS 0.01  LID. OF SCREENED SECTION 2"  ELEV./DEPTH BOTTOM OF SCREENED SECTION TYPE OF SCREENED SECTION 2"  ELEV./DEPTH BOTTOM OF SCREENED SECTION LENGTH OF BLANK SECTION 2.5'  ELEV./DEPTH BOTTOM OF PLUGGED BLANK SECTION ELEV./DEPTH BOTTOM OF SAND COLUMN	CHECKED BY DATE	DEPTH INTERVAL
TYPE OF BACKFILL BELOW OBSERVATION PIPE Sand 110	GROUND ELEVATION  GROUND ELEVATION  A  DEPTH OF SURFACE S  GROUND SURFACE S  GROUND SURFACE CAS  TYPE OF SURFACE CAS  TYPE OF SURFACE CAS  TYPE OF SURFACE CAS  TYPE OF RISER PIPE  TYPE OF RISER PIPE  TYPE OF RISER PIPE  TYPE OF BACKFILL:  ELEV_DEPTH TOP OF  TYPE OF SAND PACK  DEPTH OF TOP OF  TYPE OF SCREENED SECOND  LENGTH OF BLANK SECOND  ELEV_DEPTH BOTTOM  ELEV_DEPTH BOTTOM  LENGTH OF BLANK SECOND  ELEV_DEPTH BOTTOM  ELEV_D	URFACE CASING/RISER SURFACE  SEAL BELOW  AL:

JAN-19-00 14:42 FROM:WOODWARD-CLYDE BTR ID:5047523809 PAGE 8/1: LOG OF BORING WC-43 BORING: Modification to Corrective Action Program 91B618C PROJECT: FILE: 2/24/93 LOCATION: International Paper Company DATE: Wiggins, Mississippi SAK TECHNICIAN: MEC APPROVED: International Paper Company CLIENT: 1 of 3 PAGE: Wiggins, Mississippi Wash Bored: Full Depth DEPTH (FEET) S.P.T.(b/ft) Description of Stratum OVA Recovery (inch) P.Pen.(tsf) (ppm) Dense dark red Silty SANDS, dry (SM) 12 24 -with white sand streaks at 10' 18 15 20 Firm light reddish pink and yellow Silty SANDS, dry **^42)** 19 Alternating layers of stiff dark reddish purple laminated CLAYS and reddish pink and tan SANDS (CH/SP) 20 Loose red, white and tan SANDS, moist (SP) 16 -with red, purple and yellow clay pockets at 35' 14 16 -wel to saturated at 45' 20 Continued Next Page Unified Soil Classifications based on visual observations.

PAGE 9/1: LOG OF BORING WC-43 BORING: Modification to Corrective Action Program PROJECT: 91B618C FILE: 2/24/93 LOCATION: International Paper Company DATE: Wiggins, Mississippi SAK TECHNICIAN: APPROVED: MEC International Paper Company CLIENT: 2 of 3 PAGE: Wiggins, Mississippi DEPTH (FEET) S.P.T.(b/ft) Description of Stratum OVA or P.Pen.(tsf) Recovery (inch) (ppm) 50 Loose red and white medium to fine grained SANDS (SP) 16 —tan at 55' 22 Alternating layers of purple CLAYS with yellow and red streaks and tan and dark red SANDS (CH/SP) 17 Firm brown SANDS, moist, with saturated tan sand and gravel (SP) 15 Firm to loose tan Silty SANDS, saturated (SM) 24 22 19 -with dark red and purple clay pockets at 85' Loose tan, pink and white SANDS, saturated (SP) NR 7 Continued Next Page NR = No Recovery Unified Soil Classifications based on visual observations. Woodward-Clyde Consultants MAR 4 93 ENVIRS 18618 577XDT

ID:5047523809

JAN-19-00 14:42 FROM:WOODWARD-CLYDE BTR ID:5047523809 PAGE 10/10 LOG OF BORING WC-43 BORING: PROJECT: Modification to Corrective Action Program FILE: 91B618C LOCATION: International Paper Company 2/24/93 DATE: Wiggins, Mississippi SAK TECHNICIAN: APPROVED: MEC International Paper Company CLIENT: 3 of 3 PAGE: Wiggins, Mississippi DEPTH (FEET) S.P.T.(b/ft) Recovery (inch) Description of Stratum OVA or P.Pen\_(usf) (ppm) 100 Dense to firm tan SANDS, saturated (SP) NR 105 4 -dense to very dense pink, red and tan at 110' 5 (CH) Stiff tan, yellow and light gray CLAYS 120 Bottom of boring at 120". Well WC-43 was set in borehole. NR = No Recovery Unified Soil Classifications based on visual observations.

#### Woodward-Clyde Consultants

#### MONITOR WELL INSTALLATION REPORT

ATION wiggins	125/93	DRIGINAL DEPTH 120 AQUIFER	itconelle
PECTED BY Ste.	ue Krul	DATE 2/25/93 70-	7 <b>e</b>
CKED BY		DATE DEPTH INTE	RVAL
GROUND ELEVATION Deck red		ELEVATION OF TOP OF SURFACE CASING/ RISER PIPE  HEIGHT OF TOP OF SURFACE CASING/RISER PIPE ABOVE GROUND SURFACE  DEPTH OF SURFACE SEAL BELOW GROUND SURFACE	
silty sand with Red, pink + white		LD. OF SURFACE CASING  TYPE OF SURFACE CASING  Steel  Lith locking cap	ر د "
with clay pockets		DEPTH OF SURFACE CASING BELOW GROUND	3.0
water at		LD. OF RISER PIPE PUC	
42.29'on 1 2/26/93		DIAMETER OF BOREHOLE	6
		TYPE OF BACKFILL: Grout - Portland Cement +	
20 - 100' Dense tan		ELEV. DEPTH TOP TO SEAL Pellets  TYPE OF SEAL: Bentonite Pellets	96
Sand		TYPE OF SAND PACK <u>ZO-40 silice</u> sound DEPTH OF TOP OF SAND PACK	101
		TYPE OF SCREENED SECTION:	10
		I.D. OF SCREENED SECTION	
	耳-	ELEV./DEPTH BOTTOM OF SCREENED SECTION	1/6
	1	LENGTH OF BLANK SECTION	٠. ٢
		ELEV./DEPTH BOTTOM OF PLUGGED BLANK SECTION	1/83
100-118.5'		ELEV./DEPTH BOTTOM OF SAND COLUMN TYPE OF BACKFILL BELOW OBSERVATION PIPE	118.5
Tan to yellow end light gray		ELEV./DEPTH OF HOLE	1/8-5

	State We	ell Report	
County: Stane	1	riller's Log	For Office Use Only:
	Mississippi Department	Aquifer:	
Permit #:		d Water Resources	
Driller: 0578	P.O. Bo	Well #:	
Date drilling completed: 6-4-05		39289-0631 51-5210	L. S. Elevation:
		6938 (fax)	E-log #:
State Law requires that this report Department at the above address Information on Well C	t be prepared by the licen within 30 days of comple	se holder responsible for the tion of drilling of the well	he work and filed with the
(Landowner if borehole is not fo			
Owner Name Intenational Pro	مهر		" Longitude: <b>85°07'36</b> "
Mailing Address:	1	Method of Lat/Long (circle one	e): Conventional Survey,
		USGS quad, Hand-held	GPS, Survey-grade GPS
		ne 14 nw 14 Sec 31	Twn_ <u>25</u> Rng_11 W
City Stat	e Zip Code I	Distance Direction	Nearest Town
Telephone No. ()		Mileso	f Wissins
	Well / Boreho	le Data	
Date drilling started: 6-6-05 Date dri Location of the source of any surface water Method of dosing and volume of Chlorine Logs run (circle all applicable): No log run Name of organization running log(s):  Purpose of borehole (check one): Water We	used for drilling:  Used in drilling and develop  Electric Gamma Ray I	ment:	ther: $\Lambda A$
Seismic S  If drilling is not related	urvey Other (describe) _ to water well construction.	Monitor well skip the remainder of this block	·k
Purpose of Well (check one): Home In			
If a flowing well, method of flow regulation		r (describe)	
Static Water Level:feet abo	ove or below (circle one) land	surface Date measured:	
Method of Measurement (circle one) ste	el tape electric tape	air line other:	
Well depth: 64 Well grouted to a dep			
Casing length: 44 feet Casing			
Screen length: ZO feet Screen			1
Screen slot size: inches			
Type of completion (circle all applicable):			ole Natural Development
	Other (describe): g''	Flush mant	

Top of lap pipe or reduction in casing: \_\_\_\_\_\_ feet. If telescoped or more than one screen, describe on next page

	- ZIN CIM	_   0	20
	Silk Sand	-05	38
	Kapkeil Sound	38	64
			<del></del>
		<del></del>	+
			<del>-  </del> -
		<del></del>	
}			<del> </del>
1			<b></b>
1		<del></del>	
j			
aid in locating the well; 3) any roads, power 4) a north arrow.			
See Attach	ed Copy		
andowner Name:  ertify that the well/borchole was drilled, constructed, a ssissippi Department of Environmental Quality and the ss.	and completed in accordance with all applicable me Mississippi Department of Health regulation	s, if applicable, an	the
andowner Name:  ertify that the well/borehole was drilled, constructed, a ssissippi Department of Environmental Quality and the s.	and completed in accordance with all applicabl	e requirements of as, if applicable, an	the


Description of formations encountered must be provided for all wells and boreholes, unless specifically exempted by regulations

From (depth) To (depth) Ground Level

Description of Formations Encountered

The sketch below only required for water wells

If well telescopes, show depths on sketch.
Ground Level



) i i i

MONITORING WELL WC-44 Well ID: WC-44 Hole Dia.: 8.5" Driller: WALKER-HILL Date: <u>6-6-05</u> Drill Method: HSA Logged By: PREMO DEPTH (ft) DESCRIPTION WELL CONSTRUCTION DETAIL 8" Flush Mount - 0 -Surface Seal - 5 -SILTY CLAY - 10 -- 15 -- Neat Cement Grout - 20 -- 25 -2" ID SCH 40 PVC Casing -30-SILTY SAND - 35 -40 -- Bentonite Seal - 45 -- Filter Sand - 50 -RED SILTY SAND 0.010 Slot PVC Screen - 55 -- 60 -- 65 -BOREHOLE TERMINATED AT 64' INTERNATIONAL (A) PAPER MONITORING WELL PREMO CONSTRUCTION DETAIL Treated Wood Product Facility Wiggins, MS 1880 WEST OAK PKWY, BLISH 100, SUITE 100 MARIETTA, OEOROJA 10060 DATE: APRIL 2006 FIGURE 1

		BORING	REC	OKD	
Surface Elev. (Feet)	Depth (Feet)	Description	Unified Soil Classif.	Penetration Resistance, "N" Blows per Foot 30 20 30 40 50 60 70 80 90	Sample Bemarks
223.24	51.5	Soil sampling started at 54.5'. (See Boring WC-8 for 0 to 54.5')			
	54.5 55.0	CITRONELLE FORMATION: Firm to dense, white and tan silty fine to medium sand with thin purple silty clay layers			NO
	60.0				NO
	65.0				NO
	-		SM		
	75.0				NO
	80.0				NO
	84.0	Very dense yellow silty medium sand			NO
Date Dr Drilling Drilled Logged Checke	ByM	8/8/84  Rotary POPE Water Table (24Hd) S.L.W. Laboratory Test Lo	le our) e of Bo	ring) NO No contai	ntaminant odor noderate contaminant odor ninant odor
J	_	AMES L. GRANT & ASSOCIATES  geotechnical engineering • management •  computer science  ENGLEWOOD COLORADO	Jo	oring Number <u>WC-</u> ob Number <u>80402</u> age <u>1 of 2</u>	8A 4

		BORING	KLC	Ok							
Elev. (Feet)	Depth (Feet)	Description	Unified Soil Classif.	l E	Resi Slow	stan s pe	ation ce, * r Foc		Sample	Da ta	Remarks
	90.0	(See 84.0' to 90.0')							X		
	95.0									NO	
	100.0		SM						•	NO	
	105.0	Same									
	-108.6										
	110.0	PASCAGOULA FORMATION: Very hard yellow and grey silty clay	СН			-				NO	
		Boring terminated @ 110.5									
·· 	115.0										
	·								•		
Drilled	Method _ ByPO	Standard Penetrate  Rotary  Undisturbed Sample  Water Table (24Ho  Jewett  Water Table (Time  L.W.  Laboratory Test Loc	e our) of Bori			wo.	Wea	k to m	noder	nant date co	ntaminant odor
0		MES L. GRANT & ASSOCIATES  peorechnical engineering • management •  computer science  ENGLEWOOD, COLORADO	Jol	rin b. N ge	um	u m b e r	·	W 804 1 2	.024		

## MONITORING WELL INSTALLATION RECORD

Job Name IP WIGGINS TWP		Well Number	WC-8A
Job Number <u>804024</u> Installati	on Date <u>8/8/84</u>	Location Wigg	rins. MS
Datum Elevation 224.43	Ground	Surface Elevation	223.24
Datum for Water Level Measuremen			
Screen Diameter & Material2" i.d	1. SCH 40 PVC	Slot Size	0.005"
Riser Diameter & Material2" i.c	a. SCH 40 PVC	Borehole Diameter	6 3/4"
Granular Backfill Material Fine grave			· —
Drilling Method Rotary wash			POPE
Lockable Cover ——  Vented Cap ——  Well Protector ——		Stickup: 1.19	Ground Surface
Threaded Coupling—  Solid Riser—  Depth to Top of Upper Granular Backfill N/A  Depth to Top of 81.0			Fotal depth of monitoring well: 109.0
Granular Materal 83.0  Screen —		ength of screen:	
	b	ength of backfilled orehole: 1.5 ackfilled with: (caved)	
: Grout		<b>*</b> ** * * . * *	31 02
Bentonite	(Not to Scale)	Stabilized water below datum.  Measured on8	
Granular Backfill			

Jlg


JAMES L. GRANT & ASSOCIATES


geotechnical engineering a management a computer science

ENGLEWOOD, COLORADO


WELL WC-8A


MONITORING WELL
INSTALLATION RECORD






## TEST BORING RECORD





## TEST BORING RECORD



# TEST BORING RECORD

ft msl	PEET	DESCRIPTION	MIFIED		PLOWS	RATION NCE, "P PER FO	or	SAMPLE TYPE OR CORE DAIA	REMARKS
	120		)	1	10 20	30 40	60 80	N + 0 0	
		Same as 117.5' to 120.0'							
	125								
	125						++++	$1\times$	NO
	130		SM					Image: Control of the con	NO ·
	135	Reddish-brown silty fine to							NO
		medium sand layer @ 134.0'.							
			- N						
								L	
	140							X	CII
	142.								
		Very firm light gray clayey							
	145	silty fine to medium SAND.							NO
	145.								140
		Boring Terminated @ 145.5'							
DATE DRI		5/10-11/83  rotary wash  STANDARD PE	NETR	ATION 1	rest	В	ORING	3 NUME	BER WF-1

DRILLING METHOD TOTATY Wash H. Carnley WIF LOGGED SY CHECKED BY \_\_SLW

WATER TABLE 24 HR

WATER TABLE TIME OF BORING

UNDISTURBED SAMPLE

LABORATORY TEST

BORING NUMBER 812073 JOB NUMBER \_

PAGE

SO STRONG CONTAMINANT ODOR

WEAK TO MODERATE WO NO NO CONTAMINANT ODOR

## TYPE II MONITORING WELL INSTALLATION RECORD IP-Wiggins JOB NAME \_\_ WELL NUMBER WP-1 JOB NUMBER 812073 INSTALLATION DATE 5/10-13/83 refer to location map DATUM ELEVATION 207.56' msl GROUND SURFACE ELEVATION 205.79' msl DATUM FOR WATER LEVEL MEASUREMENT top PVC casing SCREEN DIAMETER AND MATERIAL 2" i.d. schedule 40 PVC SLOT SIZE .010" 2" i.d. schedule RISER DIAMETER AND MATERIAL 40 PVC BOREHOLE DIAMETER 8" Gravelly silty GRANULAR BACKFILL MATERIAL fine-coarse sand FIELD REPRESENTATIVE W. Bath rotary wash DRILLING TECHNIQUE Law-Birmingham DRILLING CONTRACTOR\_ LOCKABLE COVER (NOT TO SCALE) VENTED CAP STICKUP\_1.8' WELL PROTECTOR-GROUND SURFACE THREADED COUPLING RISER LENGTH OF SOLID, 135.0 SECTION TOTAL DEPTH OF N/A DEPTH TO TOP OF UPPER WELL 144.4' GRANULAR BACKFILL 129.3' DEPTH TO TOP OF BENTONITE SEAL 133.2' DEPTH TO TOP OF LOWER GRANULAR MATERIAL LENGTH OF SLOTTED SECTION 9.4' SCREEN CAP GROUT STABILIZED WATER LEVEL 10.9 FEET BENTONITE BELOW GROUND SURFACE GRANULAR BACKFILL MEASURED ON 5/24/83



LAW ENGINEERING TESTING COMPANY

DENVER, COLORADO

TYPE II MONITORING WELL WP-1
INSTALLATION RECORD

#### MONITORING WELL INSTALLATION RECORD

Job Name <u>IP WIGGINS TWP</u> Job Number <u>80/02/</u> Installa  Datum Elevation <u>239.39</u>	tion Date <u>8/</u>	15/84 Location_i	Wispins, MS
Datum for Water Level Measurem	ent Top of P	VC casing	
Screen Diameter & Material2" i			
Riser Diameter & Material2" i	.d. SCH 40 PV	Borehole Diame	ter 4 3/4"
Granular Backfill Material <u>Fine grav</u>	el	JLGA Representat	ive M Javett
Drilling Method <u>Rotary wash</u>		Drilling Contract	tor POPE
Lockable Cover — Vented Cap —	\	51492,9	289
Well Protector		<del></del>	~
		Stickup: <u>0.79</u>	Ground Surface
りまっている。「「「な」「「な」「の」「「な」「「な」「「な」「「な」「「な」「「な」「「な」		THE THE THE THE THE THE	
Threaded Coupling —			
Solid Rises		Length of solid riser: 169.0	
Depth to Top of Upper Granular Backfill Depth to Top of			Total depth of monitoring well: 189.0
Bentonite Seal	_	9	1
Depth to Top of Lower Granular Materal 1/5.0  Screen		Leagth of screen:	3
Cap —		Length of backfilled borehole: 0.0  Backfilled with: (caved)	
: Grout	(Not to Scale)	Stabilized water	level 50.61 feet
- Destainte		Measured on	8/31/84
.: Granular Backfill			

Ĵlg

JAMES L. GRANT & ASSOCIATES
georechicol engineering a management a

ENGLEWOOD, COLORADO

WELL WP-2

MONITORING WELL

		11(1/11)		C/Ki'
Elev. (Feet)	Depth (Feet)	Description	Unified Soil Classif	Penetration Resistance, "N" Blows per Foot 10 70 30 40 50 40 70 40 90
?38.60	119.0	No samples taken from 0 to 119.0'. See log of WC-2 for interval between 0 and 69.5.		
	120.0	CITRONELLE FORMATION: Very dense red and pink fine to medium silty sand	SM	No
	123.0		СН	NO
	130.0			
	132.5			
	135.0	Very stiff to hard blue-grey silty clay		NO
	140.0	2.		
	145.0			NO NO
	150.0			
20)	155.0			NO.
ate Dritted rilling Me ritled By Ogged By hecked 8	thod 70 M. y	Rotary PE  Jewett  L. W. Laboratory Test Locat  Standard Penetration Undisturbed Sample Water Table (24Hour Water Table (Time of Laboratory Test Locat  ES L. GRANT & ASSOCIATES	) Boring)	SO Strong contaminant odor WO Weak to moderate contaminant odor

ગુીઠ

JAMES L. GRANT & ASSOCIATES

georethical ingineering 6 munagement a computer science
ENGLEWOOD, COLORADO

Job Number <u>S04024</u>
Page 1 of 2

ગુઠ

JAMES L. GRANT & ASSOCIATES

combitat ficience disolativuicas euflimatività e uravadiament e

ENGLEWOOD, COLORADO

Boring Number WP\_2 Job: Number 804024 Page 2 of 2

## APPENDIX B PHOTOGRAPHS

Data Gap Investigation Work Plan International Paper Company – Closed Former Wood Treating Site Units



Photograph of one of three monitoring wells observed inside the closed units on December 10, 2019.

## APPENDIX C FIELDWORK DOCUMENTATION FORMS



#### International Paper Groundwater Sampling Record | PROJECT # | LOCATION | DATE |

			PROJECT#			LOCATIC					DATE
SAMPLE No.  PROJECT NAME  FIELD PERSONNEL/COMPANY							ERSONNEL/C	OMPANY			
SAMPLE T	IME:		SITE			FIELD CO	ONDITIONS/W	/EATHER			
Well Condi	ition Inspe	ction (d	circle one)		Equipment Cleaning Procedures						
cover:	locked	not loc	ked		- potable water and phosphate-free soap						
number:	legible	not legi	ible		- potable water rinse						
outer casing	_	_	fair	poor	- water rinse	e:	distilled		deionize	d	
inner casing	g:	good	fair	poor	- solvent rin	se:	acetone		hexane		
well photog	raphed:	yes	no		- air dry						
Casing Dia	meter:										
(circle one)	411		0			7 40	,e.3\				
	4" Othor:		•		ation: (πr <sup>2</sup> h)(7 s/ft) for: 2" =	_	•	2 6" - 1	17		
U	Other:		Casing voi	ume (gallon	5/11) 101. 2 -	0.103,	4 - 0.05	5, 0 - 1.	47		
Depth to Wa	ater (feet):					Measu	ing Point E	levation (1	feet):		
Depth of We	ell (feet):					Ground	lwater Surfa	ace Elevat	tion:		
Water Colum							present:			thickness:	
_	me (gallons):		•				present:			thickness:	
	Purge Volume		s):			Remai	ks:				
Actual Purge	e Volume (ga	llons):									
Well Evacu											
Water level	I recovery is	<b>5</b> :	very slow	slow	moderate	fast		Bailed di	ry:	yes	no
TIME 2400 hrs	CUMULA VOLUME		TEMP (°C)	рН	CONDUCT (μs/cm, 2					TURBIDITY (NTU)	ODOR/COLOR/ REMARKS
	0										PURGE START
Measureme Ty pH/ORP/Cor	pe			acturer			Model #			Calibra	tion Date
Ty	pe			acturer			Model #			Calibra	tion Date
Ty pH/ORP/Cor	pe nd/DO/Temp			acturer			Model #			Calibra	tion Date
TylpH/ORP/Cor Turbidity SS Bladder I	pe nd/DO/Temp Pump		Manuf	AL		TLE TYP	PE/			Calibra	
Ty pH/ORP/Cor Turbidity SS Bladder I	pe nd/DO/Temp Pump		Manuf	AL		TLE TYPERVATIV	PE/				
TylpH/ORP/Cor Turbidity SS Bladder I	pe nd/DO/Temp Pump		Manuf	AL			PE/				
pH/ORP/Cor Turbidity SS Bladder I SAM	pe nd/DO/Temp Pump		Manuf	AL			PE/				

## Photo Log IP-Wiggins, MS June 2020 Data Gap Investigation Field Activities



Photo 1: WC-57 & WC-56 Well Locations June 15, 2020



Photo 3: Recovered Soil Cores-WC-57 Top to Bottom 50'-140' bgs. June 15, 2020



Photo 2: Recovered Soil Cores-WC-57 June 15, 2020



Photo 4: Pascagoula Formation contact at 142'bgs (nearest soil core 140' bgs (bottom right) to 150' bgs (top left)).

## Photo Log IP-Wiggins, MS June 2020 Data Gap Investigation Field Activities



Photo 5: Packer Assembly June 17, 2020



Photo 7: Well Abandonment June 17, 2020



Photo 6: Well Abandonment June 17, 2020



Photo 8: Survey Activities June 18, 2020

#### **BORING NUMBER**



WC-56 FACILITY NAME IP WIGGINS FORMER TREATED WOOD PRODUCTS PLANT FAC. E.P.A./STATE I.D.# MSD980600084 LOCATION WIGGINS, MISSISSIPPI TOTAL WELL DEPTH (ft) 105 BOREHOLE DIA. (in) 6 1/2" WELL COMPLETION FLUSH MOUNT CASING DIA. (in) 2 TYPE PVC SCREEN LENGTH (ft) 10 SLOT SIZE (in) 0.010 DRILLING CO. WALKER-HILL \_\_ DRILLING METHOD Rotosonic GEOLOGIST\_\_\_Norm Kennel DATE DRILLED 6/16/2020 TOP OF CASING ELEV. (ft MSL) 245.09 GROUND SURFACE ELEV. (ft MSL) 245.84 484909.07 **NORTHING EASTING** HEADSPACE READING (ppm) LITHOLOGIC DESCRIPTION/ COMMENTS WELL LITHOLOGIC LOG CONSTRUCTION DEPTH (feet) SOIL CLASSIFI-CATION ANALYSIS INT./REC. **DETAILS** 2' X 2' VAULT 4' X 4' CONCRETE PAD %001 Hand Auger. Fill Material, Sand and Gravel 8-1/4" BORHOLE %01 PID RED-BROWN SILTY CLAY, Poor Recovery CL %00I PID RED-BROWN SILTY CLAY, WITH SAND AND SAND LENSES SCHEDULE 40 PVC .GROUT. %001 SALMON SILT AND SAND, INTERBEDDED WITH YELLOW CLAY AND SILT 100% PID SP-SM PINK SAND WITH SILT, REDDISH-WHITE SAND AND CLAY POCKETS PID < 1.0 YELLOW-BROWN SAND, TRACE CLAY SW PID < 1.0 RED SAND, TRACE CLAY AND SILT, SLIGHTLY MOIST, cont'd to next page

_		EC.	SIS	HEADSPACE READING (ppm)	LITHOLOGIC LOG	SIFI- N	LITHOLOGIC DESCRIPTION/ COMMENTS	WELL CONSTRUCTION DETAILS I
PEPTH (feet)	TYPE	INT./REC.	ANALYSIS	HEAD! READ! (ppm)	LITHO	SOIL CLASSIFI- CATION		DETAILS I L (19 eg) 45
50—		100%	OIA	< 1.0		SW	RED SAND, TRACE CLAY AND SILT, SLIGHTLY MOIST	
70—————————————————————————————————————							LIGNITE BAND	
85— 90— 95— 100—		100%	Old	< 1.0		SP	PINK-YELLOW SAND, WELL-SORTED, MOIST, VERY SLIGHT ODOR FROM 75' TO 85', PERIODIC CLAY STRINGERS.  MOTTLED YELLOW CLAY IN SHOE  COMMENTS	
	BOR FAC				RNATION	IAL PAPE	_	EARTHCON°  PAGE 2 OF _3

		.:	S	ACE	GIC	-	LITHOLOGIC DESCRIPTION/ COMMENTS	WELL CONSTRUCTION
DEPTH (feet)	TYPE	INT./REC.	ANALYSIS	HEADSPACE READING (ppm)	LITHOLOGIC	SOIL CLASSIFI- CATION		DETAILS HLAG
当 100——	Ł	Ξ	AN	뿐만		S J S		100
								105
		100%	PID	< 1.0		SP	PINK-YELLOW SAND, WELL-SORTED, MOIST	
105								
							BORING TERMINATED AT 105 FT.	110
110								110
115								115
120								120
125								125
130								130
135								135
140								= 140 = = = 140
145								= = 145
143								
								135
150								E_ E_ =150
155—								E
		•					COMMENTS	
	BORI	ING#	WC-5	56			_	●EARTHCON®
	FACI	LITY	NAM	E <u>INTE</u>	RNATION	IAL PAPE	<del>R</del>	PAGE 3 OF 3

#### BORING NUMBER



SW


PID


< 1.0

WC-57 FACILITY NAME IP WIGGINS FORMER TREATED WOOD PRODUCTS PLANT FAC. E.P.A./STATE I.D.# MSD980600084 LOCATION \_ WIGGINS, MISSISSIPPI TOTAL WELL DEPTH (ft) 145 BOREHOLE DIA. (in) 6 1/2" WELL COMPLETION FLUSH MOUNT CASING DIA. (in) 2 TYPE PVC SCREEN LENGTH (ft) 10 SLOT SIZE (in) 0.010 DRILLING CO. WALKER-HILL \_\_ DRILLING METHOD Rotosonic GEOLOGIST Norm Kennel \_ DATE DRILLED <u>6/15/2020 - 6/16/2020</u> TOP OF CASING ELEV. (ft MSL) 245.11 GROUND SURFACE ELEV. (ft MSL) 245.82 **NORTHING** 484909.07 **EASTING** 891769.51 LITHOLOGIC LOG LITHOLOGIC DESCRIPTION/ COMMENTS WELL SOIL CLASSIFI-CATION CONSTRUCTION ANALYSIS INT./REC **DETAILS** 2' X 2' VAULT 4' X 4' CONCRETE PAD Hand Auger. Fill Material, Sand and Gravel 100 8-1/4" BORHOLE RED-BROWN SILTY CLAY, Poor Recovery Ы RED-BROWN SILTY CLAY, WITH SAND AND SAND LENSES SCHEDULE 40 SALMON SILT AND SAND, INTERBEDDED WITH YELLOW CLAY AND SILT SM 30 PID SP-SM PINK SAND WITH SILT, REDDISH-WHITE SAND AND CLAY POCKETS PID < 1.0 YELLOW-BROWN SAND, TRACE CLAY

RED SAND, TRACE CLAY AND SILT, SLIGHTLY MOIST, cont'd to next page

**LOCATION MAP** 





#### STATE WELL REPORT

# County: \_\_\_\_\_ Permit #: \_\_\_\_\_ Driller: \_\_\_\_\_ Date drilling completed: \_\_\_\_\_\_

#### Part 1 Driller's Log

Mississippi Department of Environmental Quality
Office of Land and Water Resources
P.O. Box 2309
Jackson, MS 39225-2309
(601)961-5555

(601)961-5228 (fax)

For Office Use Only:					
Well #:					
Aquifer:					
E-Log #:					

State Law requires that this report be prepared by the license holder responsible for the work and filed with the Department at the above address within 30 days of completion of drilling of the well or borehole.

Well Owner Information	Well or Borehole Location
(Landowner if borehole is not for a water well)	Latitude: Longitude:
Owner Name:	Method of Lat/Long (check one): Conventional Survey,
Mailing Address:	
	USGS quad, Hand-held GPS, Survey-grade GPS
City State Zip Code	Miles of (Distance) (Direction) (Nearest Town)
Telephone No. ()	(Distance) (Direction) (Nearest Town)
Well / B	orehole Data
Date drilling started: Date drilling completed:	Hole depth: Hole diameter:
Location of the source of any surface water used for drillir	ng:
Method of dosing and volume of Chlorine used in drilling a	nd development:
Logs run (check all applicable): No log run Electric Gamm	na Ray Density Sonic Neutron Other:
Name of organization running log(s):	
Purpose of borehole (check one): Water Well Geotechni	cal/Geological Investigation Ground Source Heat Pump
	describe)
	onstruction, skip the remainder of this block
Purpose of Well (check all applicable): Home Industria	
Other (describe):	
	Other (describe)
Static Water Level:feet [ above or below (check one)	ow] land surface Date measured:
Method of measurement (check one): Steel tape Electric	tape Air line Other (describe):
Well depth: for the depth of: for the depth of: for the depth of t	eet Type of grout (check one): Neat Cement Bentonite Mix
Casing length:feet Casing diameter:	inches Type of casing:
Screen length:feet Screen diameter:	inches Type of screen:
Screen slot size:inches Setting depth:	Fromfeet tofeet
Type of completion (check all applicable): Gravel packed	Underreamed Open hole Natural Development
Other (describe):	
Top of lap pipe or reduction in casing:feet	
If telescoped or more than o	one screen, describe on next page

Form: OLWR-SWR-1A (4/13)

Permit #:		We	For Office Use	-
The sketch below only re	quired for water wells	Description of formations encour and boreholes, unless specifically		
<i>f well telescopes</i> , <i>show d</i> Ground Level	lepths on sketch.	Description of Formations Encounte		To (depth)
	Riser		Ground tevet	
	Cement/Bentonite			
	Bentonite Pellets			
	20/40 Sand Filler			
	Screen			
f more than one screen, sho	w location of each on sketch			
3) any roads, power lines	ures on the property that may a	aid in locating the well n locating the property and the well		
4) north arrow				

Date

Print Name of Responsible Licensee and License No.

Signature of Licensee
Form: OLWR-SWR-1B (4/13)

#### STATE WELL REPORT

# County: \_\_\_\_\_ Permit #: \_\_\_\_\_ Driller: \_\_\_\_\_ Date drilling completed: \_\_\_\_\_\_

#### Part 1 Driller's Log

Mississippi Department of Environmental Quality
Office of Land and Water Resources
P.O. Box 2309
Jackson, MS 39225-2309
(601)961-5555

(601)961-5228 (fax)

For Office Use Only:					
Well #:					
Aquifer:					
E-Log #:					

State Law requires that this report be prepared by the license holder responsible for the work and filed with the Department at the above address within 30 days of completion of drilling of the well or borehole.

Well Owner Information	Well or Borehole Location
(Landowner if borehole is not for a water well)	Latitude: Longitude:
Owner Name:	Method of Lat/Long (check one): Conventional Survey,
Mailing Address:	
	USGS quad, Hand-held GPS, Survey-grade GPS
City State Zip Code	Miles of (Distance) (Direction) (Nearest Town)
Telephone No. ()	(Distance) (Direction) (Nearest Town)
Well / B	orehole Data
Date drilling started: Date drilling completed:	Hole depth: Hole diameter:
Location of the source of any surface water used for drillir	ng:
Method of dosing and volume of Chlorine used in drilling a	nd development:
Logs run (check all applicable): No log run Electric Gamm	na Ray Density Sonic Neutron Other:
Name of organization running log(s):	
Purpose of borehole (check one): Water Well Geotechni	cal/Geological Investigation Ground Source Heat Pump
	describe)
	onstruction, skip the remainder of this block
Purpose of Well (check all applicable): Home Industria	
Other (describe):	
	Other (describe)
Static Water Level:feet [ above or below (check one)	ow] land surface Date measured:
Method of measurement (check one): Steel tape Electric	tape Air line Other (describe):
Well depth: for the depth of: for the depth of: for the depth of t	eet Type of grout (check one): Neat Cement Bentonite Mix
Casing length:feet Casing diameter:	inches Type of casing:
Screen length:feet Screen diameter:	inches Type of screen:
Screen slot size:inches Setting depth:	Fromfeet tofeet
Type of completion (check all applicable): Gravel packed	Underreamed Open hole Natural Development
Other (describe):	
Top of lap pipe or reduction in casing:feet	
If telescoped or more than o	one screen, describe on next page

Form: OLWR-SWR-1A (4/13)

Permit #:		We	For Office Use	-
The sketch below only re	quired for water wells	Description of formations encour and boreholes, unless specifically		
<i>f well telescopes</i> , <i>show d</i> Ground Level	lepths on sketch.	Description of Formations Encounte		To (depth)
	Riser		Ground tevet	
	Cement/Bentonite			
	Bentonite Pellets			
	20/40 Sand Filler			
	Screen			
f more than one screen, sho	w location of each on sketch			
3) any roads, power lines	ures on the property that may a	aid in locating the well n locating the property and the well		
4) north arrow				

Date

Print Name of Responsible Licensee and License No.

Signature of Licensee
Form: OLWR-SWR-1B (4/13)

#### MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY

#### Office of Land and Water Resources

P. O. Box 2309 Jackson, MS 39225

## Water Well Plugging/Decommissioning Form OLWR-DF-1 (04/08) (601)961-5555 (601)961-5228 (fax)

COUNTY WELL LOCATED:			WELL NUMBER:
PERMIT NUMBER:		DATE WELL PLUGGE	D:
NAME OF FIRM TELEPHONE NUMBER:			:
NAME AND ADDRESS OF CURRENT LANDOWNER:			
WELL LOCATION: SECTI	ION: TOWNSH	HIP: RANGE:	
WELL LOCATION: LATITUDE:	LONGITUDE:	METHOD (Check ONE):	(1) USGS QUAD (2) CONVENTIONAL SURVEY (3) GPS – HAND HELD OR SURVEY GRADE
DISTANCE: DIRECTION:	NEAREST TOWN:	ОТНЕ	ER LANDMARK:
WELL PURPOSE (HOME, IRRIGATION, MUNICIPAL, ETC.):			
NAME OF WELL CONTRACTOR WHO DRILLED THE WELL:			
NAME OF LANDOWNER WHEN WELL WAS DRILLED:			
	WE	LL DATA	
WELL DEPTH:		HOLE DEPTH:	
CASING DIAMETER (IN.): CAS	ING LENGTH (FT.):	TYPE OF CAS	ING:
DEPTH TO STATIC WATER LEVEL:	DATE W	ELL COMPLETED:	
WHY IS THE WELL BEING ABANDONED?	<u> </u>		
DESCRIBE HOW THE WELL OR HOLE WAS MATERIAL AND AMOUNT USED IN PLUGGI	NG, METHOD OF PLACING I	MATERIAL, ETC.)	HAT WAS REMOVED OR LEFT IN HOLE,
	NAME) / 7 //		MS LICENSE NUMBER
SIGNA	TURE		DATE

#### MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY

### Office of Land and Water Resources P. O. Box 2309

Jackson, MS 39225 Water Well Plugging/Decommissioning Form OLWR-DF-1 (04/08) (601)961-5555 (601)961-5228 (fax)

COUNTY WELL LOCATED: Stone		WELL NUMBER: WC-491
PERMIT NUMBER:	DATE WELL PLUGGE	D: 6/17/20
NAME OF FIRM PLUGGING WELL: Walker-Hill Environn	nental, Inc TELEPHONE NUMBER	<sup>3</sup> 601-736-3500
NAME AND ADDRESS OF CURRENT LANDOWNER: International Paper	er, Emily Lee, 6400 Popla	ar Avenue, Memphis, TN 38197
WELL LOCATION: SECTION: 31	TOWNSHIP: 2S RANGE:	11W
WELL LOCATION: LATITUDE: 30°50'01" LONGITUE	DE:89°07'38" METHOD (Check ONE)	:     USGS QUAD   CONVENTIONAL SURVEY   3) GPS - HAND HELD OR SURVEY GRADE
DISTANCE: 1.8 DIRECTION: S NEAR	REST TOWN: Wiggins OTH	ER LANDMARK:
WELL PURPOSE (HOME, IRRIGATION, MUNICIPAL, ETC.):		
NAME OF WELL CONTRACTOR Walker-F	Hill Environment	al, Inc.
NAME OF LANDOWNER WHEN WELL WAS DRILLED: Internation	onal Paper	
	WELL DATA	
WELL DEPTH: 92.5	HOLE DEPTH:	92.5
CASING DIAMETER (IN.): CASING LENGTH	H (FT.): 72.5	PVC
DEPTH TO STATIC WATER LEVEL:	DATE WELL COMPLETED: 200	7
WHY IS THE WELL BEING ABANDONED? Well not	used	
DESCRIBE HOW THE WELL OR HOLE WAS PLUGGED (A MATERIAL AND AMOUNT USED IN PLUGGING, METHOD		HAT WAS REMOVED OR LEFT IN HOLE,
Checked Well	. Well was then grouted v	with cement
bentonite slurry pumped by trem	nie pipe from the bottom	of the well to ground surface.
Finished by	covering site with native	materials.
I CERTIFY THAT THE WELL WAS PLUGGED OR	R ABANDONED IN ACCORDANCE WITH T	HE STATE OF MISSISSIPPI REGULATIONS.
Gary P. Hill		0-578
PRINT NAME L	7	MS LICENSE NUMBER 7/8/2020
SIGNATURE		DATE

#### MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY

Office of Land and Water Resources P. O. Box 2309 Jackson, MS 39225

## Water Well Plugging/Decommissioning Form OLWR-DF-1 (04/08) (601)961-5555 (601)961-5228 (fax)

COUNTY WELL LOCATED: Stone	WELL NUMBER: WC-501			
DATE WELL PLUGGED: 6/17/20  IAME OF FIRM DATE WELL FIRM THE PLUGGED STORY  AND OF FIRM DATE WELL FIRM THE PLUGGED STORY  AND OF FIRM DATE WELL PLUGGED STORY  A				
PLUGGING WELL: VVAIKET-HIII ENVIRONMENTAI, II	ic TELEPHONE NUMBER: 601-736-3500			
NAME AND ADDRESS OF CURRENT LANDOWNER: International Paper, Emily	Lee, 6400 Poplar Avenue, Memphis,	TN 38197		
WELL LOCATION: SECTION: 31 TOWNS	HIP: 2S RANGE: 11W			
WELL LOCATION: LATITUDE: 30°50'01" LONGITUDE: 89°07'3	G" METHOD (Check ONE): Ø USGS QUAD □ ) CONVENTION □ 3) GPS – HAND HELD OR SURVI	IAL SURVEY EY GRADE		
DISTANCE: 1.8 DIRECTION: S NEAREST TOWN: V	Jiggins OTHER LANDMARK:			
WELL PURPOSE (HOME, IRRIGATION, MUNICIPAL, ETC.): Injection				
NAME OF WELL CONTRACTOR Walker-Hill En	vironmental, Inc.			
International F	aper			
W	LL DATA			
WELL DEPTH: 75.68	ноге дертн: 75.68			
CASING DIAMETER (IN.): CASING LENGTH (FT.): 55.6	B TYPE OF CASING: PVC			
DEPTH TO STATIC WATER LEVEL: DATE WELL COMPLETED: 2007				
WHY IS THE WELL BEING ABANDONED? Well not used				
DESCRIBE HOW THE WELL OR HOLE WAS PLUGGED (AMOUNT OF C MATERIAL AND AMOUNT USED IN PLUGGING, METHOD OF PLACING		LE,		
Checked Well. Well was then grouted with cement				
bentonite slurry pumped by tremie pipe from the bottom of the well to ground surface.				
Finished by covering	site with native materials.			
I CERTIFY THAT THE WELL WAS PLUGGED OR ABANDONED	IN ACCORDANCE WITH THE STATE OF MISSISSIPPI REGULAT	лоns.		
Gary P. Hill	0-578			
MS LICENSE NUMBER 7/8/2020				
SIGNATURE DATE				



## ANALYTICAL REPORT

June 26, 2020

### EarthCon Consultants, Inc - Marietta, GA

Sample Delivery Group: L1231761

Samples Received: 06/20/2020

Project Number: 02.20000006.20

Description: IP Wiggins

Report To: Doug Seely

1880 West Oak Pkwy.

Bld 100, Suite106

Marietta, GA 30062

Entire Report Reviewed By:

Chris McCord

Project Manager Results relate only to the items tested or calibrated and are reported as rounded values. This test report shall not be reproduced, except in full, without written approval of the laboratory. Where applicable, sampling conducted by Pace Analytical National is performed per guidance provided in laboratory standard operating procedures ENV-SOP-MTJL-0067 and ENV-SOP-MTJL-0068. Where sampling conducted by the customer, results relate to the accuracy of the information provided, and as the samples are received.



















Cp: Cover Page	1
Tc: Table of Contents	2
Ss: Sample Summary	3
Cn: Case Narrative	4
Sr: Sample Results	5
WC-8 L1231761-01	5
WC-39 L1231761-02	6
WC-41 L1231761-03	7
WC-44 L1231761-04	8
EB-1 L1231761-05	9
WC-11 L1231761-06	10
DUP-01 L1231761-07	11
WC-26 L1231761-08	12
Qc: Quality Control Summary	13
Semi Volatile Organic Compounds (GC/MS) by Method 8270C	13
GI: Glossary of Terms	17
Al: Accreditations & Locations	18
Sc: Sample Chain of Custody	19





















WC-8 L1231761-01 GW			Collected by Kimberly B	Collected date/time 06/15/20 11:31	Received da 06/20/20 08		
Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location	
Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1496409	1	06/21/20 10:42	06/21/20 20:16	SHG	Mt. Juliet, TN	
WC-39 L1231761-02 GW			Collected by Kimberly B	Collected date/time 06/15/20 12:21	Received da 06/20/20 08		
Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location	
Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1496409	1	06/21/20 10:42	06/21/20 20:38	SHG	Mt. Juliet, TN	
WC-41 L1231761-03 GW			Collected by Kimberly B	Collected date/time 06/15/20 13:24	Received da 06/20/20 08		
Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location	
Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1496409	1	06/21/20 10:42	06/21/20 21:00	SHG	Mt. Juliet, TN	
WC-44 L1231761-04 GW			Collected by Kimberly B	Collected date/time 06/15/20 14:23	Received da 06/20/20 08		
Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location	
Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1496409	1	06/21/20 10:42	06/21/20 21:22	SHG	Mt. Juliet, TN	
EB-1 L1231761-05 GW			Collected by Kimberly B	Collected date/time 06/15/20 13:45		Received date/time 06/20/20 08:45	
Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location	
Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1496409	1	06/21/20 10:42	06/21/20 22:27	SHG	Mt. Juliet, TN	
WC-11 L1231761-06 GW			Collected by Kimberly B	Collected date/time 06/15/20 15:29	Received da 06/20/20 08		
Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location	
Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1496409	1	06/21/20 10:42	06/21/20 22:49	SHG	Mt. Juliet, TN	
DUP-01 L1231761-07 GW			Collected by Kimberly B	Collected date/time 06/15/20 15:32	Received da 06/20/20 08		
Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location	
Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1496409	1	06/21/20 10:42	06/21/20 23:10	SHG	Mt. Juliet, TN	
WC-26 L1231761-08 GW			Collected by Kimberly B	Collected date/time 06/16/20 07:39	Received da 06/20/20 08		
Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location	



















EarthCon Consultants, Inc - Marietta, GA

Semi Volatile Organic Compounds (GC/MS) by Method 8270C

WG1496709

1.25

06/23/20 06:45

06/23/20 16:55

AO

Mt. Juliet, TN

All sample aliquots were received at the correct temperature, in the proper containers, with the appropriate preservatives, and within method specified holding times, unless qualified or notated within the report. Where applicable, all MDL (LOD) and RDL (LOQ) values reported for environmental samples have been corrected for the dilution factor used in the analysis. All Method and Batch Quality Control are within established criteria except where addressed in this case narrative, a non-conformance form or properly qualified within the sample results. By my digital signature below, I affirm to the best of my knowledge, all problems/anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by the laboratory, and no information or data have been knowingly withheld that would affect the quality of the data.















Chris McCord Project Manager

ONE LAB. NATIONWIDE.

Collected date/time: 06/15/20 11:31

L1231/01

	Result	Qualifier	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	ug/l		ug/l		date / time	
Fluorene	ND		1.00	1	06/21/2020 20:16	WG1496409
Naphthalene	ND		1.00	1	06/21/2020 20:16	WG1496409
Phenanthrene	ND		1.00	1	06/21/2020 20:16	WG1496409
3&4-methyl phenol	ND		10.0	1	06/21/2020 20:16	WG1496409
Pentachlorophenol	ND		1.00	1	06/21/2020 20:16	WG1496409
(S) 2-Fluorophenol	46.8		10.0-120		06/21/2020 20:16	WG1496409
(S) Phenol-d5	30.0		10.0-120		06/21/2020 20:16	WG1496409
(S) Nitrobenzene-d5	57.3		10.0-127		06/21/2020 20:16	WG1496409
(S) 2-Fluorobiphenyl	64.2		10.0-130		06/21/2020 20:16	WG1496409
(S) 2,4,6-Tribromophenol	56.0		10.0-155		06/21/2020 20:16	WG1496409
(S) p-Terphenyl-d14	70.7		10.0-128		06/21/2020 20:16	WG1496409



















#### SAMPLE RESULTS - 02 ONE LAB. NATIONWIDE.

Collected date/time: 06/15/20 12:21

1231761

	Result	Qualifier	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	ug/l		ug/l		date / time	
Fluorene	ND		1.00	1	06/21/2020 20:38	WG1496409
Naphthalene	ND		1.00	1	06/21/2020 20:38	WG1496409
Phenanthrene	ND		1.00	1	06/21/2020 20:38	WG1496409
3&4-methyl phenol	ND		10.0	1	06/21/2020 20:38	WG1496409
Pentachlorophenol	ND		1.00	1	06/21/2020 20:38	WG1496409
(S) 2-Fluorophenol	48.4		10.0-120		06/21/2020 20:38	WG1496409
(S) Phenol-d5	30.0		10.0-120		06/21/2020 20:38	WG1496409
(S) Nitrobenzene-d5	58.6		10.0-127		06/21/2020 20:38	WG1496409
(S) 2-Fluorobiphenyl	64.6		10.0-130		06/21/2020 20:38	WG1496409
(S) 2,4,6-Tribromophenol	55.5		10.0-155		06/21/2020 20:38	WG1496409
(S) p-Terphenyl-d14	70.5		10.0-128		06/21/2020 20:38	WG1496409



















#### ONE LAB. NATIONWIDE.

Collected date/time: 06/15/20 13:24

Semi Volatile Organic Compounds (GC/MS) by Method 8270C

SAMPLE RESULTS - 03

	Result	Qualifier	RDL	Dilution	Analysis	Batch_
Analyte	ug/l		ug/l		date / time	_
Fluorene	ND		1.00	1	06/21/2020 21:00	WG1496409
Naphthalene	ND		1.00	1	06/21/2020 21:00	WG1496409
Phenanthrene	ND		1.00	1	06/21/2020 21:00	WG1496409
3&4-methyl phenol	ND		10.0	1	06/21/2020 21:00	WG1496409
Pentachlorophenol	ND		1.00	1	06/21/2020 21:00	WG1496409
(S) 2-Fluorophenol	47.7		10.0-120		06/21/2020 21:00	WG1496409
(S) Phenol-d5	30.6		10.0-120		06/21/2020 21:00	WG1496409
(S) Nitrobenzene-d5	55.6		10.0-127		06/21/2020 21:00	WG1496409
(S) 2-Fluorobiphenyl	63.5		10.0-130		06/21/2020 21:00	WG1496409
(S) 2,4,6-Tribromophenol	53.4		10.0-155		06/21/2020 21:00	WG1496409
(S) p-Terphenyl-d14	64.3		10.0-128		06/21/2020 21:00	WG1496409



















ONE LAB. NATIONWIDE.

Collected date/time: 06/15/20 14:23

L1231761

	Result	Qualifier	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	ug/l		ug/l		date / time	
Fluorene	ND		1.00	1	06/21/2020 21:22	WG1496409
Naphthalene	ND		1.00	1	06/21/2020 21:22	WG1496409
Phenanthrene	ND		1.00	1	06/21/2020 21:22	WG1496409
3&4-methyl phenol	ND		10.0	1	06/21/2020 21:22	WG1496409
Pentachlorophenol	ND		1.00	1	06/21/2020 21:22	WG1496409
(S) 2-Fluorophenol	44.6		10.0-120		06/21/2020 21:22	WG1496409
(S) Phenol-d5	27.4		10.0-120		06/21/2020 21:22	WG1496409
(S) Nitrobenzene-d5	53.6		10.0-127		06/21/2020 21:22	WG1496409
(S) 2-Fluorobiphenyl	60.8		10.0-130		06/21/2020 21:22	WG1496409
(S) 2,4,6-Tribromophenol	51.6		10.0-155		06/21/2020 21:22	WG1496409
(S) p-Terphenyl-d14	66.6		10.0-128		06/21/2020 21:22	WG1496409



















Collected date/time: 06/15/20 13:45

	Result	Qualifier	RDL	Dilution	Analysis	Batch
Analyte	ug/l		ug/l		date / time	
Fluorene	ND		1.00	1	06/21/2020 22:27	WG1496409
Naphthalene	ND		1.00	1	06/21/2020 22:27	WG1496409
Phenanthrene	ND		1.00	1	06/21/2020 22:27	WG1496409
3&4-methyl phenol	ND		10.0	1	06/21/2020 22:27	WG1496409
Pentachlorophenol	ND		1.00	1	06/21/2020 22:27	WG1496409
(S) 2-Fluorophenol	48.6		10.0-120		06/21/2020 22:27	WG1496409
(S) Phenol-d5	30.9		10.0-120		06/21/2020 22:27	WG1496409
(S) Nitrobenzene-d5	57.7		10.0-127		06/21/2020 22:27	WG1496409
(S) 2-Fluorobiphenyl	62.0		10.0-130		06/21/2020 22:27	WG1496409
(S) 2,4,6-Tribromophenol	56.3		10.0-155		06/21/2020 22:27	WG1496409
(S) p-Terphenyl-d14	69.3		10.0-128		06/21/2020 22:27	WG1496409



















ONE LAB. NATIONWIDE.

Collected date/time: 06/15/20 15:29

L1231761

	Result	Qualifier	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	ug/l		ug/l		date / time	
Fluorene	ND		1.00	1	06/21/2020 22:49	WG1496409
Naphthalene	ND		1.00	1	06/21/2020 22:49	WG1496409
Phenanthrene	ND		1.00	1	06/21/2020 22:49	WG1496409
3&4-methyl phenol	ND		10.0	1	06/21/2020 22:49	WG1496409
Pentachlorophenol	ND		1.00	1	06/21/2020 22:49	WG1496409
(S) 2-Fluorophenol	48.1		10.0-120		06/21/2020 22:49	WG1496409
(S) Phenol-d5	30.2		10.0-120		06/21/2020 22:49	WG1496409
(S) Nitrobenzene-d5	56.3		10.0-127		06/21/2020 22:49	WG1496409
(S) 2-Fluorobiphenyl	58.5		10.0-130		06/21/2020 22:49	WG1496409
(S) 2,4,6-Tribromophenol	54.6		10.0-155		06/21/2020 22:49	WG1496409
(S) p-Terphenyl-d14	57.3		10.0-128		06/21/2020 22:49	WG1496409



















ONE LAB. NATIONWIDE.

Collected date/time: 06/15/20 15:32

L1231761

	Result	Qualifier	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	ug/l		ug/l		date / time	
Fluorene	ND		1.00	1	06/21/2020 23:10	WG1496409
Naphthalene	ND		1.00	1	06/21/2020 23:10	WG1496409
Phenanthrene	ND		1.00	1	06/21/2020 23:10	WG1496409
3&4-methyl phenol	ND		10.0	1	06/21/2020 23:10	WG1496409
Pentachlorophenol	ND		1.00	1	06/21/2020 23:10	WG1496409
(S) 2-Fluorophenol	46.9		10.0-120		06/21/2020 23:10	WG1496409
(S) Phenol-d5	28.8		10.0-120		06/21/2020 23:10	WG1496409
(S) Nitrobenzene-d5	53.2		10.0-127		06/21/2020 23:10	WG1496409
(S) 2-Fluorobiphenyl	57.0		10.0-130		06/21/2020 23:10	WG1496409
(S) 2,4,6-Tribromophenol	52.5		10.0-155		06/21/2020 23:10	WG1496409
(S) p-Terphenyl-d14	55.8		10.0-128		06/21/2020 23:10	WG1496409



















ONE LAB. NATIONWIDE.

Collected date/time: 06/16/20 07:39

1231761

	Result	Qualifier	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	ug/l		ug/l		date / time	
Fluorene	ND		1.25	1.25	06/23/2020 16:55	WG1496709
Naphthalene	ND		1.25	1.25	06/23/2020 16:55	WG1496709
Phenanthrene	ND		1.25	1.25	06/23/2020 16:55	WG1496709
3&4-methyl phenol	ND		12.5	1.25	06/23/2020 16:55	WG1496709
Pentachlorophenol	1.45		1.25	1.25	06/23/2020 16:55	WG1496709
(S) 2-Fluorophenol	45.6		10.0-120		06/23/2020 16:55	WG1496709
(S) Phenol-d5	28.9		10.0-120		06/23/2020 16:55	WG1496709
(S) Nitrobenzene-d5	64.1		10.0-127		06/23/2020 16:55	WG1496709
(S) 2-Fluorobiphenyl	67.6		10.0-130		06/23/2020 16:55	WG1496709
(S) 2,4,6-Tribromophenol	83.2		10.0-155		06/23/2020 16:55	WG1496709
(S) p-Terphenyl-d14	81.6		10.0-128		06/23/2020 16:55	WG1496709



















ONE LAB. NATIONWIDE.

Semi Volatile Organic Compounds (GC/MS) by Method 8270C

L1231761-01,02,03,04,05,06,07

#### Method Blank (MB)

(MB) R3541581-2 06/21/2	20 16:37			
	MB Result	MB Qualifier	MB MDL	MB RDL
Analyte	ug/l		ug/l	ug/l
Fluorene	U		0.0844	1.00
Naphthalene	U		0.159	1.00
Phenanthrene	U		0.112	1.00
3&4-Methyl Phenol	U		0.168	10.0
Pentachlorophenol	U		0.313	1.00
(S) Nitrobenzene-d5	56.5			10.0-127
(S) 2-Fluorobiphenyl	64.1			10.0-130
(S) p-Terphenyl-d14	70.3			10.0-128
(S) Phenol-d5	28.1			10.0-120
(S) 2-Fluorophenol	45.0			10.0-120
(S) 2,4,6-Tribromophenol	56.5			10.0-155

#### Laboratory Control Sample (LCS)

(LCS) R3541581-1 06/2	21/20 16:15				
	Spike Amount	LCS Result	LCS Rec.	Rec. Limits	LCS Qualifier
Analyte	ug/l	ug/l	%	%	
Fluorene	50.0	31.2	62.4	47.0-120	
Naphthalene	50.0	28.1	56.2	27.0-120	
Phenanthrene	50.0	32.1	64.2	46.0-120	
3&4-Methyl Phenol	50.0	29.9	59.8	31.0-120	
Pentachlorophenol	50.0	29.4	58.8	23.0-120	
(S) Nitrobenzene-d5			44.7	10.0-127	
(S) 2-Fluorobiphenyl			64.1	10.0-130	
(S) p-Terphenyl-d14			70.1	10.0-128	
(S) Phenol-d5			28.7	10.0-120	
(S) 2-Fluorophenol			45.2	10.0-120	
(S) 2,4,6-Tribromopheno	)/		60.5	10.0-155	

#### L1231761-04 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1231/61-04   06/21/20 21:22 • (MS) R3541581-3   06/21/20 21:44 • (MSD) R3541581-4   06/21/20 22:05												
	Spike Amount	Original Result	MS Result	MSD Result	MS Rec.	MSD Rec.	Dilution	Rec. Limits	MS Qualifier	MSD Qualifier	RPD	RPD Limits
Analyte	ug/l	ug/l	ug/l	ug/l	%	%		%			%	%
Fluorene	45.5	ND	29.7	28.4	65.3	62.4	1	37.0-120			4.48	24
Naphthalene	45.5	ND	25.6	26.0	56.3	57.1	1	10.0-120			1.55	31
Phenanthrene	45.5	ND	29.0	29.4	63.7	64.6	1	33.0-120			1.37	22
3&4-Methyl Phenol	45.5	ND	29.1	27.2	64.0	59.8	1	10.0-120			6.75	36
Pentachlorophenol	45.5	ND	25.9	25.7	56.9	56.5	1	10.0-128			0.775	37

 ACCOUNT:
 PROJECT:
 SDG:
 DATE/TIME:
 PAGE:

 EarthCon Consultants, Inc - Marietta, GA
 02.20000006.20
 L1231761
 06/26/20 14:04
 13 of 19

ONE LAB. NATIONWIDE.

Semi Volatile Organic Compounds (GC/MS) by Method 8270C

L1231761-01,02,03,04,05,06,07

#### L1231761-04 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(00) = = 0 = 0 = 0 = 0 = 0 = 0	, ,			,								
	Spike Amount	Original Result	MS Result	MSD Result	MS Rec.	MSD Rec.	Dilution	Rec. Limits	MS Qualifier	MSD Qualifier	RPD	RPD Limits
Analyte	ug/l	ug/l	ug/l	ug/l	%	%		%			%	%
(S) Nitrobenzene-d5					48.6	46.0		10.0-127				
(S) 2-Fluorobiphenyl					61.6	66.2		10.0-130				
(S) p-Terphenyl-d14					63.7	70.5		10.0-128				
(S) Phenol-d5					29.1	28.9		10.0-120				
(S) 2-Fluorophenol					44.1	44.7		10.0-120				
(S) 2,4,6-Tribromophenol					55.5	60.4		10.0-155				



















PAGE:

ONE LAB. NATIONWIDE.

Semi Volatile Organic Compounds (GC/MS) by Method 8270C

L1231761-08

#### Method Blank (MB)

(MB) R3542249-2 06/23/	20 14:06			
	MB Result	MB Qualifier	MB MDL	MB RDL
Analyte	ug/l		ug/l	ug/l
Fluorene	U		0.0844	1.00
Naphthalene	0.349	<u>J</u>	0.159	1.00
Phenanthrene	U		0.112	1.00
3&4-Methyl Phenol	U		0.168	10.0
Pentachlorophenol	U		0.313	1.00
(S) Nitrobenzene-d5	65.6			10.0-127
(S) 2-Fluorobiphenyl	<i>75.5</i>			10.0-130
(S) p-Terphenyl-d14	<i>85.2</i>			10.0-128
(S) Phenol-d5	29.0			10.0-120
(S) 2-Fluorophenol	44.9			10.0-120
(S) 2,4,6-Tribromophenol	83.5			10.0-155

#### Laboratory Control Sample (LCS)

(LCS) R3542249-1 06/	23/20 13:45				
	Spike Amount	LCS Result	LCS Rec.	Rec. Limits	LCS Qualifier
Analyte	ug/l	ug/l	%	%	
Fluorene	50.0	39.4	78.8	47.0-120	
Naphthalene	50.0	33.7	67.4	27.0-120	
Phenanthrene	50.0	44.3	88.6	46.0-120	
3&4-Methyl Phenol	50.0	33.0	66.0	31.0-120	
Pentachlorophenol	50.0	40.8	81.6	23.0-120	
(S) Nitrobenzene-d5			61.7	10.0-127	
(S) 2-Fluorobiphenyl			83.1	10.0-130	
(S) p-Terphenyl-d14			89.0	10.0-128	
(S) Phenol-d5			29.5	10.0-120	
(S) 2-Fluorophenol			46.5	10.0-120	
(S) 2,4,6-Tribromopheno	l .		98.5	10.0-155	

#### L1231742-06 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1231/42-06 06/2	23/20 15:09 • (MS)	R3542249-3 (	06/23/20 15:3	1 • (MSD) R3542	2249-4 06/23	/20 15:52						
	Spike Amount	Original Result	MS Result	MSD Result	MS Rec.	MSD Rec.	Dilution	Rec. Limits	MS Qualifier	MSD Qualifier	RPD	RPD Limits
Analyte	ug/l	ug/l	ug/l	ug/l	%	%		%			%	%
Fluorene	45.5	3.17	39.1	35.6	79.0	71.3	1	37.0-120			9.37	24
Naphthalene	45.5	4.81	32.8	30.6	61.5	56.7	1	10.0-120			6.94	31
Phenanthrene	45.5	ND	41.1	37.8	88.9	81.7	1	33.0-120			8.37	22
3&4-Methyl Phenol	45.5	ND	29.7	28.7	65.3	63.1	1	10.0-120			3.42	36
Pentachlorophenol	45.5	ND	38.0	35.3	83.5	77.6	1	10.0-128			7.37	37

 ACCOUNT:
 PROJECT:
 SDG:
 DATE/TIME:
 PAGE:

 EarthCon Consultants, Inc - Marietta, GA
 02.20000006.20
 L1231761
 06/26/20 14:04
 15 of 19

ONE LAB. NATIONWIDE.

Semi Volatile Organic Compounds (GC/MS) by Method 8270C

L1231761-08

#### L1231742-06 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1231742-06 06/23/2	20 15:09 • (MS)	R3542249-3 C	06/23/20 15:31	• (MSD) R3542	249-4 06/23/2	20 15:52						
	Spike Amount	Original Result	MS Result	MSD Result	MS Rec.	MSD Rec.	Dilution	Rec. Limits	MS Qualifier	MSD Qualifier	RPD	RPD Limits
Analyte	ug/l	ug/l	ug/l	ug/l	%	%		%			%	%
(S) Nitrobenzene-d5					60.5	57.9		10.0-127				
(S) 2-Fluorobiphenyl					76.3	75.4		10.0-130				
(S) p-Terphenyl-d14					88.8	82.4		10.0-128				
(S) Phenol-d5					27.9	28.0		10.0-120				
(S) 2-Fluorophenol					44.0	43.8		10.0-120				
(S) 2,4,6-Tribromophenol					94.5	91.2		10.0-155				



















#### **GLOSSARY OF TERMS**

#### ONE LAB. NATIONWIDE.

#### Guide to Reading and Understanding Your Laboratory Report

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.

Results Disclaimer - Information that may be provided by the customer, and contained within this report, include Permit Limits, Project Name, Sample ID, Sample Matrix, Sample Preservation, Field Blanks, Field Spikes, Field Duplicates, On-Site Data, Sampling Collection Dates/Times, and Sampling Location. Results relate to the accuracy of this information provided, and as the samples are received.

#### Abbreviations and Definitions

Appleviations and	Definitions
MDL	Method Detection Limit.
ND	Not detected at the Reporting Limit (or MDL where applicable).
RDL	Reported Detection Limit.
Rec.	Recovery.
RPD	Relative Percent Difference.
SDG	Sample Delivery Group.
(S)	Surrogate (Surrogate Standard) - Analytes added to every blank, sample, Laboratory Control Sample/Duplicate and Matrix Spike/Duplicate; used to evaluate analytical efficiency by measuring recovery. Surrogates are not expected to be detected in all environmental media.
U	Not detected at the Reporting Limit (or MDL where applicable).
Analyte	The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported.
Dilution	If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor.
Limits	These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges.
Original Sample	The non-spiked sample in the prep batch used to determine the Relative Percent Difference (RPD) from a quality control sample. The Original Sample may not be included within the reported SDG.
Qualifier	This column provides a letter and/or number designation that corresponds to additional information concerning the result reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable.
Result	The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state "ND" (Not Detected) or "BDL" (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte.
Uncertainty (Radiochemistry)	Confidence level of 2 sigma.
Case Narrative (Cn)	A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report.
Quality Control Summary (Qc)	This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material.
Sample Chain of Custody (Sc)	This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis.
Sample Results (Sr)	This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section for each sample will provide the name and method number for the analysis reported.
Sample Summary (Ss)	This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis.

#### Qualifier Description

The identification of the analyte is acceptable; the reported value is an estimate.





















PAGE:

17 of 19

#### **ACCREDITATIONS & LOCATIONS**





#### **State Accreditations**

Alabama	40660
Alaska	17-026
Arizona	AZ0612
Arkansas	88-0469
California	2932
Colorado	TN00003
Connecticut	PH-0197
Florida	E87487
Georgia	NELAP
Georgia <sup>1</sup>	923
Idaho	TN00003
Illinois	200008
Indiana	C-TN-01
lowa	364
Kansas	E-10277
Kentucky 16	90010
Kentucky <sup>2</sup>	16
Louisiana	Al30792
Louisiana <sup>1</sup>	LA180010
Maine	TN0002
Maryland	324
Massachusetts	M-TN003
Michigan	9958
Minnesota	047-999-395
Mississippi	TN00003
Missouri	340
Montana	CERT0086

Nebraska	NE-OS-15-05
Nevada	TN-03-2002-34
New Hampshire	2975
New Jersey-NELAP	TN002
New Mexico <sup>1</sup>	n/a
New York	11742
North Carolina	Env375
North Carolina <sup>1</sup>	DW21704
North Carolina <sup>3</sup>	41
North Dakota	R-140
Ohio-VAP	CL0069
Oklahoma	9915
Oregon	TN200002
Pennsylvania	68-02979
Rhode Island	LAO00356
South Carolina	84004
South Dakota	n/a
Tennessee 1 4	2006
Texas	T104704245-18-15
Texas <sup>5</sup>	LAB0152
Utah	TN00003
Vermont	VT2006
Virginia	460132
Washington	C847
West Virginia	233
Wisconsin	9980939910
Wyoming	A2LA

#### Third Party Federal Accreditations

A2LA – ISO 17025	1461.01
A2LA - ISO 17025 5	1461.02
Canada	1461.01
EPA-Crypto	TN00003

AIHA-LAP,LLC EMLAP	100789
DOD	1461.01
USDA	P330-15-00234

<sup>&</sup>lt;sup>1</sup> Drinking Water <sup>2</sup> Underground Storage Tanks <sup>3</sup> Aquatic Toxicity <sup>4</sup> Chemical/Microbiological <sup>5</sup> Mold <sup>6</sup> Wastewater n/a Accreditation not applicable

#### Our Locations

Pace National has sixty-four client support centers that provide sample pickup and/or the delivery of sampling supplies. If you would like assistance from one of our support offices, please contact our main office. Pace National performs all testing at our central laboratory.



















			Billing Info	rmation:			_		Analysis	/ Conta	iner / Preservative	The state of the s	Chain of Custody	Page of
EarthCon Consultants	, Inc - Mai	rietta,		s Payable		Pres		7					100	Anah tigal®
GA				est Oak Pkw	ry, Bld 100,	Chk							National C	Analytical * enter for Testing & Innovation
1880 West Oak Pkwy.			Suite106 Marietta	6 a, GA 30062		***		7						
Report to:			Email To:	artheon comid	adkins@earthco	n com							12065 Lebanon Rd Mount Juliet, TN 37	122
Doug Seely		Cit. /5+++	aseerywea	ar tricon.com,u	Please (								Phone: 615-758-58 Phone: 800-767-58	
Project Description:  IP Wiggins		City/State Collected: (	Wiggir	15. MS	PT MT								Fax: 615-758-5859	- 407/
Phone: <b>770-973-2100</b>	Client Proje		00	Lab Project	# IGA-WIGGINS		Amb NoPres						SDG# // J202	
Collected by (print):	Site/Facility	VID#	00	P.O.#			- S						ette er som fort	
Kimberly Barfield							mp						Acctnum: PRE	
Collected by (signature):  Kimbuly Barbald	Same	(Lab MUST Be	Day	Quote #			100ml A						Prelogin: P77 PM: 526 - Chri	6523
Immediately Packed on Ice N YX	Next Two Three	Day 5 Day Day 10 Day e Day	(Rad Only) ay (Rad Only)		esults Needed	No. of							PB: Cb C	3 2000 edEX Ground
Sample ID	Comp/Gra	b Matrix *	Depth	Date	Time	Cntrs	8270PCP						Remarks	Sample # (lab only)
8-24/	Grab	GW		6-15-2	020 11:31	2	X							-01
WC-39		GW		1	12:21	2	X							02
wc-41	40 - 1	GW		The second	13:24	1 2	X					機體		03
WC-44		GW	-		14:23	2	X							04
EB-1		GW			13:45	2	X							65
WC-44 MSIMSP		GW			14:20		X							06
WC-11		GW			15:20	-	X				1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			07
		GW		1	15:32		X							07
100-01	1	GW		10-11-0	020 07:39	-	X							08
WC-26		GW		0 10 2	000 01.0	2	X				- BESSE			
* Matrix	Remarks:8270		ethylphon	ol fluorene	nanhthalene		1000000	henol and	d			9	Sample Receipt Ch	necklist /
* Matrix:  SS - Soil AIR - Air F - Filter  GW - Groundwater B - Bioassay  WW - WasteWater	phenanthrene		earyipiieii	oi, nuorene,	napricinal circ,		шогор		pH Flov		Temp	COC Seal COC Sign Bottles	Present/Intact ned/Accurate: arrive intact: bottles used:	: _NP Y _N _N _N
DW - Drinking Water OT - Other	Samples return UPS 🗶 Fed	ed via: IEx Courier		Тг	racking # 179	030	33	3135	)			Sufficie VOA Zero	ent volume sent:  If Applicab  Headspace:	le Y_X
Relinquished by: (Signature)  Numberly Bol W	2)	Date: 6/18/20	Time	e: R	eceived by: (Sign	ature)			Trip Bla	ank Rece	HCL / MeoH		ation Correct/Ch een <0.5 mR/hr:	ecked: Y N
Relinquished by :48ignature)		Date:	Time		eceived by: (Sign	ature)			Temp:	MY	TBR  C Bottles Received:	If preserv	ation required by Lo	gin: Date/Time
Relinquished by : (Signature)		Date:	Time	e: R	eceived for lab b	y: (Signat	ture)		Date:	1/20	Time: 8:45	Hold:		Condition: NCF / OK



## ANALYTICAL REPORT

June 29, 2020

#### EarthCon Consultants, Inc - Marietta, GA

Sample Delivery Group: L1231742

Samples Received: 06/20/2020

Project Number: 02.20000006.20

Description: IP Wiggins

Report To: Doug Seely

1880 West Oak Pkwy.

Bld 100, Suite106

Marietta, GA 30062

Entire Report Reviewed By:

Chris McCord

Project Manager Results relate only to the items tested or calibrated and are reported as rounded values. This test report shall not be reproduced, except in full, without written approval of the laboratory. Where applicable, sampling conducted by Pace Analytical National is performed per guidance provided in laboratory standard operating procedures ENV-SOP-MTJL-0067 and ENV-SOP-MTJL-0068. Where sampling conducted by the customer, results relate to the accuracy of the information provided, and as the samples are received.

















Cp: Cover Page	1
Tc: Table of Contents	2
Ss: Sample Summary	3
Cn: Case Narrative	5
Sr: Sample Results	6
WP-1 L1231742-01	6
WP-2 L1231742-02	7
DUP-02 L1231742-03	8
WC-8A L1231742-04	9
WC-43 L1231742-05	10
WCP-8 L1231742-06	11
EB-2 L1231742-07	12
WC-56 L1231742-08	13
DUP-03 L1231742-09	14
WC-57 L1231742-10	15
DUP-04 L1231742-11	16
Qc: Quality Control Summary	17
Volatile Organic Compounds (GC/MS) by Method 8260B	17
Semi Volatile Organic Compounds (GC/MS) by Method 8270 C-SIM	18
Semi Volatile Organic Compounds (GC/MS) by Method 8270C	20
Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM	23
GI: Glossary of Terms	30
Al: Accreditations & Locations	31



















Sc: Sample Chain of Custody

32



Method   Satch   Substant   Su		0711111	3 0 11111	<b>*17 (1 ( 1</b>			
Marchael Organic Compounds (COMS) by Method 3200E   WC198378   1 062320 00436   062320 01436	WP-1 L1231742-01 GW			•			
Vocatic Organic Compounds (ISCMS) by Method 82608   WiSH98313   1 082420 14:10   062420 14:10   50M8   M. Juliet, TN Semi Volatide Organic Compounds (ISCMS) by Method 8270CSM   WISH97092   1 082320 06:15   062320 17:86   AD	Method	Batch	Dilution	Preparation	Analysis	Analyst	Location
Serial Volution Organic Compounds (SCMS) by Method 8270C SIM				date/time	date/time	·	
Semi Volatile Organic Compounds (SCMS) by Method 8270C SIM   WSH497092   1   09/2320 18:36   06/24/20 05:10   DMC   ML Juliet, TN	Volatile Organic Compounds (GC/MS) by Method 8260B	WG1498313	1	06/24/20 14:10	06/24/20 14:10	BMB	Mt. Juliet, TN
Method   Batch   Dilution   Proparation   Analysis	Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1496709	1	06/23/20 06:45	06/23/20 17:58	AO	Mt. Juliet, TN
Method   Batch   Dilution   Preparation   Analysis	Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM	WG1497092	1	06/23/20 18:36	06/24/20 05:10	DMG	Mt. Juliet, TN
Method   Batch   Dilution   Preparation   Analysis   Analysis   Location   Collection   Compounds (CCMS) by Method 8270C   WG149873   1 06274270 1434   06274270 1434   BMB   Mt. Juliet, TN   Serni Valuatile Organic Compounds (CCMS) by Method 8270C   WG1496709   1 0623270 1836   0627420 1838   Analysis   Mt. Juliet, TN   Serni Valuatile Organic Compounds (CCMS) by Method 8270C   WG1497092   1 0623270 1836   0627420 1836				Collected by	Collected date/time	Received da	te/time
Volatile Organic Compounds (EC/MS) by Method 8260B	WP-2 L1231742-02 GW			Kimberly B	06/17/20 16:28	06/20/20 08	3:45
Valatile Organic Compounds (GCMS) by Method 8260B   WGM98313   1   06/24/20 14.34   06/24/20 18.38   A0   M. Juliet, TN	Method	Batch	Dilution	Preparation	Analysis	Analyst	Location
Semi Volatile Organic Compounds (GC/MS) by Method 8270C SIM   WG1497092   1   06/23/20 18:36   06/23/20 18				date/time	date/time		
Semi Volatile Organic Compounds (GCMS) by Method 8270C-SIM   WG1497092   1	Volatile Organic Compounds (GC/MS) by Method 8260B	WG1498313	1	06/24/20 14:34	06/24/20 14:34	BMB	Mt. Juliet, TN
DUP-O2 L1231742-03 GW	Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1496709	1	06/23/20 06:45	06/23/20 18:18	AO	Mt. Juliet, TN
DUP-02 L1231742-03 GW   Satch   Batch   Batch   Dilution   Preparation   Analysis   Analysis   Location   date/time   date/	Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM	WG1497092	1	06/23/20 18:36	06/24/20 05:30	Analyst  BMB AO DMG  Received dat 06/20/20 08  Analyst  BMB AO DMG  Received dat 06/20/20 08  Analyst  BMB AO LEA  Received dat 06/20/20 08  Analyst  BMB AO LEA	Mt. Juliet, TN
Method   Batch   Dilution   Preparation date/time   Analysis   A				Collected by	Collected date/time	Received da	ite/time
Volatile Organic Compounds (GC/MS) by Method 8260B   WG1498313   1   G6/24/20 14:58   G6/23/20 14:58   BMB   Mt. Juliet, TN	DUP-02 L1231742-03 GW			Kimberly B	06/17/20 16:35	06/20/20 08	3:45
Volatile Organic Compounds (GC/MS) by Method 8260B   WG1498313   1 06/24/20 14-58   06/24/20 14-58   BMB   Mt. Juliet, TN   Semi Volatile Organic Compounds (GC/MS) by Method 8270C   WG1496709   1 06/23/20 06-45   06/23/20 18-39   A0   Mt. Juliet, TN   Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM   WG1497093   1 06/23/20 06-21   06/23/20 15-30   LEA   Mt. Juliet, TN	Method	Batch	Dilution	Preparation	Analysis	Analyst	Location
Semi Volatile Organic Compounds (GC/MS) by Method 8270C SIM				date/time	date/time		
Semi Volatile Organic Compounds (GCMS) by Method 8270C-SIM   WG1497093   1   O6/23/20 06:21   O6/23/20 15:03   LEA   Mt. Juliet, TN	Volatile Organic Compounds (GC/MS) by Method 8260B	WG1498313	1	06/24/20 14:58	06/24/20 14:58	BMB	Mt. Juliet, TN
MC-8A L1231742-04 GW   Collected by Kimberly B   Collected date/time   Received date/time   Collected date/t	Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1496709	1	06/23/20 06:45	06/23/20 18:39	AO	Mt. Juliet, TN
WC-8A         L1231742-04         GW         Kimberly B         06/17/20 15:26         06/20/20 08:45           Method         Batch         Dilution date/time         Preparation date/time         Analysis         Analysis         Location           Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/24/20 15:22         06/24/20 15:22         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 14:27         AO         Mt. Juliet, TN           WC-43         L1231742-05         GW         WG1498709         1         06/23/20 06:21         06/23/20 15:23         LEA         Mt. Juliet, TN           WC-43         L1231742-05         GW         WG1498709         1         06/23/20 06:21         06/23/20 15:23         LEA         Mt. Juliet, TN           WC-43         L1231742-05         GW         Description of date/time date/time date/time         NG1/20/20 08:45         06/20/20 08:45         06/20/20 08:45         Description of date/time         NG1/20/20 08:45         NG	Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM	WG1497093	1	06/23/20 06:21	06/23/20 15:03	LEA	Mt. Juliet, TN
Method   Batch   Dilution   Preparation   Analysis   Analyst   Location				Collected by	Collected date/time	Received da	te/time
Volatile Organic Compounds (GC/MS) by Method 8260B   WG1498313   1 06/24/20 15:22 06/24/20 15:22   BMB   Mt. Juliet, TN	WC-8A L1231742-04 GW			Kimberly B	06/17/20 15:26	06/20/20 08	3:45
Volatile Organic Compounds (GC/MS) by Method 8260B   WG1498313   1 O6/24/20 15:22 O6/24/20 15:22   BMB   Mt. Juliet, TN   Semi Volatile Organic Compounds (GC/MS) by Method 8270C   WG1496709   1 O6/23/20 06:45 O6/23/20 14:27   AO   Mt. Juliet, TN   Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM   WG1497093   1 O6/23/20 06:21 O6/23/20 15:23   LEA   Mt. Juliet, TN   Collected by Kimberly B   O6/17/20 11:20   O6/23/20 06:21   O6/23/20 15:23   LEA   Mt. Juliet, TN   Collected State of the properties o	Method	Batch	Dilution	Preparation	Analysis	Analyst	Location
Semi Volatile Organic Compounds (GC/MS) by Method 8270C   WG1496709   1 O6/23/20 06:21 O6/23/20 14:27   A0 Mt. Juliet, TN Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM   WG1497093   1 O6/23/20 06:21 O6/23/20 15:23   LEA Mt. Juliet, TN				date/time	date/time		
Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM   WG1497093   1   O6/23/20 06:21   O6/23/20 15:23   LEA   Mt. Juliet, TN	Volatile Organic Compounds (GC/MS) by Method 8260B	WG1498313	1	06/24/20 15:22	06/24/20 15:22	BMB	Mt. Juliet, TN
Collected by Kimberly B   Collected date/time   Received date/time   O6/17/20 11:20   O6/20/20 08:45	Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1496709	1	06/23/20 06:45	06/23/20 14:27	AO	Mt. Juliet, TN
WC-43 L1231742-05 GW         Kimberly B         06/17/20 11:20         06/20/20 08:45           Method         Batch         Dilution date/time         Analysis date/time         Analysis date/time           Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/24/20 15:46         06/24/20 15:46         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 14:48         AO         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM         WG1497093         1         06/23/20 06:21         06/23/20 15:44         LEA         Mt. Juliet, TN           WCP-8 L1231742-06 GW         Kimberly B         O6/17/20 12:07         06/20/20 08:45           Method         Batch         Dilution         Preparation date/time         Analysis         Analysis         Analyst         Location           Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/24/20 16:10         06/24/20 16:10         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 15:09         AO         Mt. Juliet, TN	Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM	WG1497093	1	06/23/20 06:21	06/23/20 15:23	LEA	Mt. Juliet, TN
Method         Batch         Dilution date/time         Preparation date/time         Analysis date/time         Analysis date/time           Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/24/20 15:46         06/24/20 15:46         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 14:48         AO         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM         WG1497093         1         06/23/20 06:21         06/23/20 15:44         LEA         Mt. Juliet, TN           WCP-8 L1231742-06 GW         Collected by Kimberly B         Collected date/time date/time         Mc1497093         Analysis Analyst date/time           Method         Batch         Dilution Preparation date/time date/time         Analysis Analyst date/time         Location date/time           Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/24/20 16:10         06/24/20 16:10         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 15:09         AO         Mt. Juliet, TN				Collected by	Collected date/time	AO DMG  Received dat 06/20/20 08:  Analyst  BMB AO DMG  Received dat 06/20/20 08:  Analyst  BMB AO LEA	te/time
Volatile Organic Compounds (GC/MS) by Method 8260B   WG1498313   1 06/24/20 15:46   06/24/20 15:46   BMB   Mt. Juliet, TN	WC-43 L1231742-05 GW			Kimberly B	06/17/20 11:20	06/20/20 08	3:45
Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/24/20 15:46         06/24/20 15:46         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 14:48         AO         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM         WG1497093         1         06/23/20 06:21         06/23/20 15:44         LEA         Mt. Juliet, TN           WCP-8 L1231742-06 GW         Collected by Kimberly B         Collected date/time         Received date/time           Method         Batch         Dilution date/time         Preparation date/time         Analysis         Analyst         Location           Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/24/20 16:10         06/24/20 16:10         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 15:09         AO         Mt. Juliet, TN	Method	Batch	Dilution	Preparation	Analysis	Analyst	Location
Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 14:48         AO         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM         WG1497093         1         06/23/20 06:45         06/23/20 15:44         LEA         Mt. Juliet, TN           Collected by Kimberly B         Collected date/time         Received date/time           Method         Batch         Dilution date/time         Preparation date/time         Analysis         Analyst         Location           Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/23/20 16:10         06/24/20 16:10         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 15:09         AO         Mt. Juliet, TN				date/time	date/time		
Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM         WG1497093         1         06/23/20 06:21         06/23/20 15:44         LEA         Mt. Juliet, TN           WCP-8 L1231742-06 GW         Collected by Kimberly B         Collected date/time 06/17/20 12:07         06/20/20 08:45           Method         Batch         Dilution date/time date/time date/time         Analysis date/time         Analysis date/time           Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/24/20 16:10         06/24/20 16:10         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 15:09         AO         Mt. Juliet, TN	3 . , , ,		1				
WCP-8 L1231742-06 GW         Collected by Kimberly B         Collected date/time 06/17/20 12:07         Received date/time 06/20/20 08:45           Method         Batch         Dilution date/time date/time date/time         Analysis date/time         Analysis date/time           Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/24/20 16:10         06/24/20 16:10         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 15:09         AO         Mt. Juliet, TN							
WCP-8         L1231742-06         GW         Kimberly B         06/17/20 12:07         06/20/20 08:45           Method         Batch         Dilution date/time         Preparation place/time         Analysis place/time         Analysis place/time           Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/24/20 16:10         06/24/20 16:10         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 15:09         AO         Mt. Juliet, TN	Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM	WG1497093	1	06/23/20 06:21	06/23/20 15:44	LEA	Mt. Juliet, TN
Method         Batch         Dilution date/time         Preparation date/time         Analysis         Analyst         Location           Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/24/20 16:10         06/24/20 16:10         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 15:09         AO         Mt. Juliet, TN				Collected by	Collected date/time	Received da	te/time
Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/24/20 16:10         06/24/20 16:10         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 15:09         AO         Mt. Juliet, TN	WCP-8 L1231742-06 GW			Kimberly B	06/17/20 12:07	06/20/20 08	3:45
Volatile Organic Compounds (GC/MS) by Method 8260B         WG1498313         1         06/24/20 16:10         06/24/20 16:10         BMB         Mt. Juliet, TN           Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 15:09         AO         Mt. Juliet, TN	Method	Batch	Dilution	•	•	Analyst	Location
Semi Volatile Organic Compounds (GC/MS) by Method 8270C         WG1496709         1         06/23/20 06:45         06/23/20 15:09         AO         Mt. Juliet, TN	Volatile Organic Compounds (GC/MS) by Method 8260B	WG1498313	1			BMB	Mt. Juliet, TN

SAMPLE SUMMARY



















EarthCon Consultants, Inc - Marietta, GA



			Collected by	Collected date/time		
EB-2 L1231742-07 GW			Kimberly B	06/17/20 11:43	06/20/20 08	3:45
Method	Batch	Dilution	Preparation	Analysis	Analyst	Location
			date/time	date/time		
Volatile Organic Compounds (GC/MS) by Method 8260B	WG1498313	1	06/24/20 13:47	06/24/20 13:47	BMB	Mt. Juliet, TN
Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1496709	1	06/23/20 06:45	06/23/20 16:13	AO	Mt. Juliet, TN
Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM	WG1497093	1	06/23/20 06:21	06/23/20 16:04	LEA	Mt. Juliet, TN
			Collected by	Collected date/time	Received da	te/time
WC-56 L1231742-08 GW			Kimberly B	06/18/20 08:44	06/20/20 08	3:45
Method	Batch	Dilution	Preparation	Analysis	Analyst	Location
			date/time	date/time		
Volatile Organic Compounds (GC/MS) by Method 8260B	WG1498313	1	06/24/20 16:34	06/24/20 16:34	BMB	Mt. Juliet, TN
Semi Volatile Organic Compounds (GC/MS) by Method 8270 C-SIM	WG1497672	1	06/25/20 20:19	06/26/20 00:12	AAT	Mt. Juliet, TN
Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1496709	1	06/23/20 06:45	06/23/20 16:34	AO	Mt. Juliet, TN
			Collected by	Collected date/time	Received da	te/time
DUP-03 L1231742-09 GW			Kimberly B	06/18/20 08:47	06/20/20 08	3:45
Method	Batch	Dilution	Preparation	Analysis	Analyst	Location
			date/time	date/time		
Volatile Organic Compounds (GC/MS) by Method 8260B	WG1498313	1	06/24/20 16:58	06/24/20 16:58	BMB	Mt. Juliet, TN
Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1497670	1	06/24/20 15:18	06/25/20 17:24	JNJ	Mt. Juliet, TN
Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM	WG1497880	1	06/24/20 13:19	06/25/20 08:32	DMG	Mt. Juliet, TN
			Collected by	Collected date/time	Received da	te/time
WC-57 L1231742-10 GW			Kimberly B	06/18/20 09:20	06/20/20 08	3:45
Method	Batch	Dilution	Preparation	Analysis	Analyst	Location
			date/time	date/time		
Volatile Organic Compounds (GC/MS) by Method 8260B	WG1498313	1	06/24/20 17:22	06/24/20 17:22	ACG	Mt. Juliet, TN
Semi Volatile Organic Compounds (GC/MS) by Method 8270C	WG1497670	1	06/24/20 15:18	06/25/20 17:45	JNJ	Mt. Juliet, TN
Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM	WG1498394	1	06/24/20 18:49	06/25/20 18:41	DMG	Mt. Juliet, TN
			Collected by	Collected date/time	Received da	te/time
DUP-04 L1231742-11 GW			Kimberly B	06/18/20 09:25	06/20/20 08	3:45
Method	Batch	Dilution	Preparation	Analysis	Analyst	Location
V   11   0   1   0   1   0   0   0   0	W04400040		date/time	date/time	100	
Volatile Organic Compounds (GC/MS) by Method 8260B	WG1498313	1	06/24/20 17:45	06/24/20 17:45	ACG	Mt. Juliet, TN

WG1497670

WG1498394

1

06/24/20 15:18

06/24/20 18:49

06/25/20 18:05

06/25/20 19:05

JNJ

DMG

Mt. Juliet, TN

Mt. Juliet, TN



















EarthCon Consultants, Inc - Marietta, GA

Semi Volatile Organic Compounds (GC/MS) by Method 8270C

. 🕶

All sample aliquots were received at the correct temperature, in the proper containers, with the appropriate preservatives, and within method specified holding times, unless qualified or notated within the report. Where applicable, all MDL (LOD) and RDL (LOQ) values reported for environmental samples have been corrected for the dilution factor used in the analysis. All Method and Batch Quality Control are within established criteria except where addressed in this case narrative, a non-conformance form or properly qualified within the sample results. By my digital signature below, I affirm to the best of my knowledge, all problems/anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by the laboratory, and no information or data have been knowingly withheld that would affect the quality of the data.

Ss 4Cn













Chris McCord
Project Manager

SDG:

L1231742

ONE LAB. NATIONWIDE.

Collected date/time: 06/17/20 10:30

L1231742

#### Volatile Organic Compounds (GC/MS) by Method 8260B

	-		-				
	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Ethylbenzene	U		0.000137	0.00100	1	06/24/2020 14:10	WG1498313
Total Xylenes	U		0.000174	0.00300	1	06/24/2020 14:10	WG1498313
(S) Toluene-d8	109			80.0-120		06/24/2020 14:10	WG1498313
(S) 4-Bromofluorobenzene	108			77.0-126		06/24/2020 14:10	WG1498313
(S) 1,2-Dichloroethane-d4	119			70.0-130		06/24/2020 14:10	WG1498313







Cn

#### Semi Volatile Organic Compounds (GC/MS) by Method 8270C

	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Carbazole	0.000112	<u>J</u>	0.000111	0.0100	1	06/23/2020 17:58	WG1496709
Dibenzofuran	0.000252	J	0.0000970	0.0100	1	06/23/2020 17:58	WG1496709
2,4-Dichlorophenol	U		0.000102	0.0100	1	06/23/2020 17:58	WG1496709
2,4-Dimethylphenol	U		0.0000636	0.0100	1	06/23/2020 17:58	WG1496709
2-Methylphenol	U		0.0000929	0.0100	1	06/23/2020 17:58	WG1496709
3&4-methyl phenol	U		0.000168	0.0100	1	06/23/2020 17:58	WG1496709
Phenol	0.00487	<u>J</u>	0.00433	0.0100	1	06/23/2020 17:58	WG1496709
Pentachlorophenol	0.00182		0.000313	0.00100	1	06/23/2020 17:58	WG1496709
2,4,6-Trichlorophenol	U		0.000100	0.0100	1	06/23/2020 17:58	WG1496709
2,3,4,6-Tetrachlorophenol	0.000391	<u>J</u>	0.000231	0.0100	1	06/23/2020 17:58	WG1496709
(S) 2-Fluorophenol	46.4			10.0-120		06/23/2020 17:58	WG1496709
(S) Phenol-d5	29.4			10.0-120		06/23/2020 17:58	WG1496709
(S) Nitrobenzene-d5	68.4			10.0-127		06/23/2020 17:58	WG1496709
(S) 2-Fluorobiphenyl	77.1			10.0-130		06/23/2020 17:58	WG1496709
(S) 2,4,6-Tribromophenol	95.1			10.0-155		06/23/2020 17:58	WG1496709
(S) p-Terphenyl-d14	91.0			10.0-128		06/23/2020 17:58	WG1496709

## 7 GI

СQс





	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Anthracene	U		0.0000190	0.0000500	1	06/24/2020 05:10	WG1497092
Acenaphthene	0.0000354	<u>J</u>	0.0000190	0.0000500	1	06/24/2020 05:10	WG1497092
Acenaphthylene	U		0.0000171	0.0000500	1	06/24/2020 05:10	WG1497092
Benzo(b)fluoranthene	U		0.0000168	0.0000500	1	06/24/2020 05:10	WG1497092
Benzo(k)fluoranthene	0.0000330	<u>J</u>	0.0000202	0.0000500	1	06/24/2020 05:10	WG1497092
Chrysene	U		0.0000179	0.0000500	1	06/24/2020 05:10	WG1497092
Fluoranthene	U		0.0000270	0.000100	1	06/24/2020 05:10	WG1497092
Fluorene	0.0000337	<u>J</u>	0.0000169	0.0000500	1	06/24/2020 05:10	WG1497092
Naphthalene	0.00248		0.0000917	0.000250	1	06/24/2020 05:10	WG1497092
Phenanthrene	0.0000286	<u>J</u>	0.0000180	0.0000500	1	06/24/2020 05:10	WG1497092
Pyrene	0.0000209	<u>J</u>	0.0000169	0.0000500	1	06/24/2020 05:10	WG1497092
2-Methylnaphthalene	0.000100	<u>J</u>	0.0000674	0.000250	1	06/24/2020 05:10	WG1497092
(S) Nitrobenzene-d5	55.8			31.0-160		06/24/2020 05:10	WG1497092
(S) 2-Fluorobiphenyl	22.7	<u>J2</u>		48.0-148		06/24/2020 05:10	WG1497092
(S) p-Terphenyl-d14	17.0	J2		37.0-146		06/24/2020 05:10	WG1497092

ONE LAB. NATIONWIDE.

Collected date/time: 06/17/20 16:28

#### L1231742

#### Volatile Organic Compounds (GC/MS) by Method 8260B

	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Ethylbenzene	U		0.000137	0.00100	1	06/24/2020 14:34	WG1498313
Total Xylenes	U		0.000174	0.00300	1	06/24/2020 14:34	WG1498313
(S) Toluene-d8	109			80.0-120		06/24/2020 14:34	WG1498313
(S) 4-Bromofluorobenzene	104			77.0-126		06/24/2020 14:34	WG1498313
(S) 1,2-Dichloroethane-d4	118			70.0-130		06/24/2020 14:34	WG1498313









#### Semi Volatile Organic Compounds (GC/MS) by Method 8270C

	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Carbazole	U		0.000111	0.0100	1	06/23/2020 18:18	WG1496709
Dibenzofuran	U		0.0000970	0.0100	1	06/23/2020 18:18	WG1496709
2,4-Dichlorophenol	U		0.000102	0.0100	1	06/23/2020 18:18	WG1496709
2,4-Dimethylphenol	U		0.0000636	0.0100	1	06/23/2020 18:18	WG1496709
2-Methylphenol	U		0.0000929	0.0100	1	06/23/2020 18:18	WG1496709
3&4-methyl phenol	U		0.000168	0.0100	1	06/23/2020 18:18	WG1496709
Phenol	U		0.00433	0.0100	1	06/23/2020 18:18	WG1496709
Pentachlorophenol	U		0.000313	0.00100	1	06/23/2020 18:18	WG1496709
2,4,6-Trichlorophenol	U		0.000100	0.0100	1	06/23/2020 18:18	WG1496709
2,3,4,6-Tetrachlorophenol	U		0.000231	0.0100	1	06/23/2020 18:18	WG1496709
(S) 2-Fluorophenol	42.6			10.0-120		06/23/2020 18:18	WG1496709
(S) Phenol-d5	26.3			10.0-120		06/23/2020 18:18	WG1496709
(S) Nitrobenzene-d5	60.1			10.0-127		06/23/2020 18:18	WG1496709
(S) 2-Fluorobiphenyl	64.4			10.0-130		06/23/2020 18:18	WG1496709
(S) 2,4,6-Tribromophenol	79.7			10.0-155		06/23/2020 18:18	WG1496709
(S) p-Terphenyl-d14	75.6			10.0-128		06/23/2020 18:18	WG1496709

## <sup>′</sup>Gl

СQс





	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Anthracene	U		0.0000190	0.0000500	1	06/24/2020 05:30	WG1497092
Acenaphthene	U		0.0000190	0.0000500	1	06/24/2020 05:30	WG1497092
Acenaphthylene	U		0.0000171	0.0000500	1	06/24/2020 05:30	WG1497092
Benzo(b)fluoranthene	U		0.0000168	0.0000500	1	06/24/2020 05:30	WG1497092
Benzo(k)fluoranthene	U		0.0000202	0.0000500	1	06/24/2020 05:30	WG1497092
Chrysene	U		0.0000179	0.0000500	1	06/24/2020 05:30	WG1497092
Fluoranthene	U		0.0000270	0.000100	1	06/24/2020 05:30	WG1497092
Fluorene	U		0.0000169	0.0000500	1	06/24/2020 05:30	WG1497092
Naphthalene	U		0.0000917	0.000250	1	06/24/2020 05:30	WG1497092
Phenanthrene	U		0.0000180	0.0000500	1	06/24/2020 05:30	WG1497092
Pyrene	U		0.0000169	0.0000500	1	06/24/2020 05:30	WG1497092
2-Methylnaphthalene	U		0.0000674	0.000250	1	06/24/2020 05:30	WG1497092
(S) Nitrobenzene-d5	103			31.0-160		06/24/2020 05:30	WG1497092
(S) 2-Fluorobiphenyl	92.6			48.0-148		06/24/2020 05:30	WG1497092
(S) p-Terphenyl-d14	99.5			37.0-146		06/24/2020 05:30	WG1497092

ONE LAB. NATIONWIDE.

Collected date/time: 06/17/20 16:35

#### L1231742

#### Volatile Organic Compounds (GC/MS) by Method 8260B

	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Ethylbenzene	U		0.000137	0.00100	1	06/24/2020 14:58	WG1498313
Total Xylenes	U		0.000174	0.00300	1	06/24/2020 14:58	WG1498313
(S) Toluene-d8	106			80.0-120		06/24/2020 14:58	WG1498313
(S) 4-Bromofluorobenzene	99.4			77.0-126		06/24/2020 14:58	WG1498313
(S) 1,2-Dichloroethane-d4	123			70.0-130		06/24/2020 14:58	WG1498313







## <sup>4</sup>Cn

#### Semi Volatile Organic Compounds (GC/MS) by Method 8270C

	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Carbazole	U		0.000111	0.0100	1	06/23/2020 18:39	WG1496709
Dibenzofuran	U		0.0000970	0.0100	1	06/23/2020 18:39	WG1496709
2,4-Dichlorophenol	U		0.000102	0.0100	1	06/23/2020 18:39	WG1496709
2,4-Dimethylphenol	U		0.0000636	0.0100	1	06/23/2020 18:39	WG1496709
2-Methylphenol	U		0.0000929	0.0100	1	06/23/2020 18:39	WG1496709
3&4-methyl phenol	U		0.000168	0.0100	1	06/23/2020 18:39	WG1496709
Phenol	U		0.00433	0.0100	1	06/23/2020 18:39	WG1496709
Pentachlorophenol	U		0.000313	0.00100	1	06/23/2020 18:39	WG1496709
2,4,6-Trichlorophenol	U		0.000100	0.0100	1	06/23/2020 18:39	WG1496709
2,3,4,6-Tetrachlorophenol	U		0.000231	0.0100	1	06/23/2020 18:39	WG1496709
(S) 2-Fluorophenol	45.5			10.0-120		06/23/2020 18:39	WG1496709
(S) Phenol-d5	28.0			10.0-120		06/23/2020 18:39	WG1496709
(S) Nitrobenzene-d5	66.2			10.0-127		06/23/2020 18:39	WG1496709
(S) 2-Fluorobiphenyl	70.3			10.0-130		06/23/2020 18:39	WG1496709
(S) 2,4,6-Tribromophenol	84.1			10.0-155		06/23/2020 18:39	WG1496709
(S) p-Terphenyl-d14	84.2			10.0-128		06/23/2020 18:39	WG1496709

# <sup>7</sup>Gl





	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Anthracene	U		0.0000190	0.0000500	1	06/23/2020 15:03	WG1497093
Acenaphthene	U		0.0000190	0.0000500	1	06/23/2020 15:03	WG1497093
Acenaphthylene	U		0.0000171	0.0000500	1	06/23/2020 15:03	WG1497093
Benzo(b)fluoranthene	U		0.0000168	0.0000500	1	06/23/2020 15:03	WG1497093
Benzo(k)fluoranthene	U		0.0000202	0.0000500	1	06/23/2020 15:03	WG1497093
Chrysene	U		0.0000179	0.0000500	1	06/23/2020 15:03	WG1497093
Fluoranthene	U		0.0000270	0.000100	1	06/23/2020 15:03	WG1497093
Fluorene	U		0.0000169	0.0000500	1	06/23/2020 15:03	WG1497093
Naphthalene	U		0.0000917	0.000250	1	06/23/2020 15:03	WG1497093
Phenanthrene	U		0.0000180	0.0000500	1	06/23/2020 15:03	WG1497093
Pyrene	U		0.0000169	0.0000500	1	06/23/2020 15:03	WG1497093
2-Methylnaphthalene	U		0.0000674	0.000250	1	06/23/2020 15:03	WG1497093
(S) Nitrobenzene-d5	97.4			31.0-160		06/23/2020 15:03	WG1497093
(S) 2-Fluorobiphenyl	86.3			48.0-148		06/23/2020 15:03	WG1497093
(S) p-Terphenyl-d14	88.9			37.0-146		06/23/2020 15:03	WG1497093

ONE LAB. NATIONWIDE.

Collected date/time: 06/17/20 15:26

#### L1231742

#### Volatile Organic Compounds (GC/MS) by Method 8260B

	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Ethylbenzene	U		0.000137	0.00100	1	06/24/2020 15:22	WG1498313
Total Xylenes	U		0.000174	0.00300	1	06/24/2020 15:22	WG1498313
(S) Toluene-d8	109			80.0-120		06/24/2020 15:22	WG1498313
(S) 4-Bromofluorobenzene	110			77.0-126		06/24/2020 15:22	WG1498313
(S) 1,2-Dichloroethane-d4	120			70.0-130		06/24/2020 15:22	WG1498313







Cn

СQс

Gl



#### Semi Volatile Organic Compounds (GC/MS) by Method 8270C

	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Carbazole	U		0.000111	0.0100	1	06/23/2020 14:27	WG1496709
Dibenzofuran	U		0.0000970	0.0100	1	06/23/2020 14:27	WG1496709
2,4-Dichlorophenol	U		0.000102	0.0100	1	06/23/2020 14:27	WG1496709
2,4-Dimethylphenol	U		0.0000636	0.0100	1	06/23/2020 14:27	WG1496709
2-Methylphenol	U		0.0000929	0.0100	1	06/23/2020 14:27	WG1496709
3&4-methyl phenol	U		0.000168	0.0100	1	06/23/2020 14:27	WG1496709
Phenol	U		0.00433	0.0100	1	06/23/2020 14:27	WG1496709
Pentachlorophenol	0.000889	<u>J</u>	0.000313	0.00100	1	06/23/2020 14:27	WG1496709
2,4,6-Trichlorophenol	U		0.000100	0.0100	1	06/23/2020 14:27	WG1496709
2,3,4,6-Tetrachlorophenol	U		0.000231	0.0100	1	06/23/2020 14:27	WG1496709
(S) 2-Fluorophenol	47.3			10.0-120		06/23/2020 14:27	WG1496709
(S) Phenol-d5	29.3			10.0-120		06/23/2020 14:27	WG1496709
(S) Nitrobenzene-d5	69.7			10.0-127		06/23/2020 14:27	WG1496709
(S) 2-Fluorobiphenyl	76.3			10.0-130		06/23/2020 14:27	WG1496709
(S) 2,4,6-Tribromophenol	90.1			10.0-155		06/23/2020 14:27	WG1496709
(S) p-Terphenyl-d14	90.8			10.0-128		06/23/2020 14:27	WG1496709

## <sup>8</sup> Al



	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Anthracene	U		0.0000190	0.0000500	1	06/23/2020 15:23	WG1497093
Acenaphthene	U		0.0000190	0.0000500	1	06/23/2020 15:23	WG1497093
Acenaphthylene	U		0.0000171	0.0000500	1	06/23/2020 15:23	WG1497093
Benzo(b)fluoranthene	U		0.0000168	0.0000500	1	06/23/2020 15:23	WG1497093
Benzo(k)fluoranthene	U		0.0000202	0.0000500	1	06/23/2020 15:23	WG1497093
Chrysene	U		0.0000179	0.0000500	1	06/23/2020 15:23	WG1497093
Fluoranthene	U		0.0000270	0.000100	1	06/23/2020 15:23	WG1497093
Fluorene	U		0.0000169	0.0000500	1	06/23/2020 15:23	WG1497093
Naphthalene	U		0.0000917	0.000250	1	06/23/2020 15:23	WG1497093
Phenanthrene	0.0000183	<u>J</u>	0.0000180	0.0000500	1	06/23/2020 15:23	WG1497093
Pyrene	U		0.0000169	0.0000500	1	06/23/2020 15:23	WG1497093
2-Methylnaphthalene	U		0.0000674	0.000250	1	06/23/2020 15:23	WG1497093
(S) Nitrobenzene-d5	97.4			31.0-160		06/23/2020 15:23	WG1497093
(S) 2-Fluorobiphenyl	88.4			48.0-148		06/23/2020 15:23	WG1497093
(S) p-Terphenyl-d14	88.4			37.0-146		06/23/2020 15:23	WG1497093

ONE LAB. NATIONWIDE.

Collected date/time: 06/17/20 11:20

#### L1231742

#### Volatile Organic Compounds (GC/MS) by Method 8260B

		,					
	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Ethylbenzene	U		0.000137	0.00100	1	06/24/2020 15:46	WG1498313
Total Xylenes	U		0.000174	0.00300	1	06/24/2020 15:46	WG1498313
(S) Toluene-d8	106			80.0-120		06/24/2020 15:46	WG1498313
(S) 4-Bromofluorobenzene	101			77.0-126		06/24/2020 15:46	WG1498313
(S) 1,2-Dichloroethane-d4	123			70.0-130		06/24/2020 15:46	WG1498313









#### Semi Volatile Organic Compounds (GC/MS) by Method 8270C

	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	<del></del>
Carbazole	U		0.000111	0.0100	1	06/23/2020 14:48	WG1496709
Dibenzofuran	U		0.0000970	0.0100	1	06/23/2020 14:48	WG1496709
2,4-Dichlorophenol	U		0.000102	0.0100	1	06/23/2020 14:48	WG1496709
2,4-Dimethylphenol	U		0.0000636	0.0100	1	06/23/2020 14:48	WG1496709
2-Methylphenol	U		0.0000929	0.0100	1	06/23/2020 14:48	WG1496709
3&4-methyl phenol	U		0.000168	0.0100	1	06/23/2020 14:48	WG1496709
Phenol	U		0.00433	0.0100	1	06/23/2020 14:48	WG1496709
Pentachlorophenol	U		0.000313	0.00100	1	06/23/2020 14:48	WG1496709
2,4,6-Trichlorophenol	U		0.000100	0.0100	1	06/23/2020 14:48	WG1496709
2,3,4,6-Tetrachlorophenol	U		0.000231	0.0100	1	06/23/2020 14:48	WG1496709
(S) 2-Fluorophenol	50.2			10.0-120		06/23/2020 14:48	WG1496709
(S) Phenol-d5	30.7			10.0-120		06/23/2020 14:48	WG1496709
(S) Nitrobenzene-d5	73.8			10.0-127		06/23/2020 14:48	WG1496709
(S) 2-Fluorobiphenyl	81.1			10.0-130		06/23/2020 14:48	WG1496709
(S) 2,4,6-Tribromophenol	90.7			10.0-155		06/23/2020 14:48	WG1496709
(S) p-Terphenyl-d14	92.3			10.0-128		06/23/2020 14:48	WG1496709

## <sup>6</sup>Qc







	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Anthracene	U		0.0000190	0.0000500	1	06/23/2020 15:44	WG1497093
Acenaphthene	U		0.0000190	0.0000500	1	06/23/2020 15:44	WG1497093
Acenaphthylene	U		0.0000171	0.0000500	1	06/23/2020 15:44	WG1497093
Benzo(b)fluoranthene	U		0.0000168	0.0000500	1	06/23/2020 15:44	WG1497093
Benzo(k)fluoranthene	U		0.0000202	0.0000500	1	06/23/2020 15:44	WG1497093
Chrysene	U		0.0000179	0.0000500	1	06/23/2020 15:44	WG1497093
Fluoranthene	U		0.0000270	0.000100	1	06/23/2020 15:44	WG1497093
Fluorene	U		0.0000169	0.0000500	1	06/23/2020 15:44	WG1497093
Naphthalene	U		0.0000917	0.000250	1	06/23/2020 15:44	WG1497093
Phenanthrene	U		0.0000180	0.0000500	1	06/23/2020 15:44	WG1497093
Pyrene	U		0.0000169	0.0000500	1	06/23/2020 15:44	WG1497093
2-Methylnaphthalene	U		0.0000674	0.000250	1	06/23/2020 15:44	WG1497093
(S) Nitrobenzene-d5	118			31.0-160		06/23/2020 15:44	WG1497093
(S) 2-Fluorobiphenyl	101			48.0-148		06/23/2020 15:44	WG1497093
(S) p-Terphenyl-d14	104			37.0-146		06/23/2020 15:44	WG1497093

ONE LAB. NATIONWIDE.

Collected date/time: 06/17/20 12:07

#### L1231742

#### Volatile Organic Compounds (GC/MS) by Method 8260B

	<u>'</u>	,					
	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Ethylbenzene	U		0.000137	0.00100	1	06/24/2020 16:10	WG1498313
Total Xylenes	U		0.000174	0.00300	1	06/24/2020 16:10	WG1498313
(S) Toluene-d8	105			80.0-120		06/24/2020 16:10	WG1498313
(S) 4-Bromofluorobenzene	107			77.0-126		06/24/2020 16:10	WG1498313
(S) 1,2-Dichloroethane-d4	126			70.0-130		06/24/2020 16:10	WG1498313

## <sup>1</sup>Cp





Cn



#### Semi Volatile Organic Compounds (GC/MS) by Method 8270C

	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l	<del>dado.</del>	mg/l	mg/l	2	date / time	<u> </u>
Carbazole	0.00503		0.000111	0.0100	1	06/23/2020 15:09	WC1406700
		7			ı		<u>WG1496709</u>
Dibenzofuran	0.00164	<u>J</u>	0.0000970	0.0100	1	06/23/2020 15:09	WG1496709
2,4-Dichlorophenol	U		0.000102	0.0100	1	06/23/2020 15:09	WG1496709
2,4-Dimethylphenol	U		0.0000636	0.0100	1	06/23/2020 15:09	WG1496709
2-Methylphenol	U		0.0000929	0.0100	1	06/23/2020 15:09	WG1496709
3&4-methyl phenol	U		0.000168	0.0100	1	06/23/2020 15:09	WG1496709
Phenol	U		0.00433	0.0100	1	06/23/2020 15:09	WG1496709
Pentachlorophenol	U		0.000313	0.00100	1	06/23/2020 15:09	WG1496709
2,4,6-Trichlorophenol	U		0.000100	0.0100	1	06/23/2020 15:09	WG1496709
2,3,4,6-Tetrachlorophenol	U		0.000231	0.0100	1	06/23/2020 15:09	WG1496709
(S) 2-Fluorophenol	44.7			10.0-120		06/23/2020 15:09	WG1496709
(S) Phenol-d5	27.7			10.0-120		06/23/2020 15:09	WG1496709
(S) Nitrobenzene-d5	67.0			10.0-127		06/23/2020 15:09	WG1496709
(S) 2-Fluorobiphenyl	73.5			10.0-130		06/23/2020 15:09	WG1496709
(S) 2,4,6-Tribromophenol	87.9			10.0-155		06/23/2020 15:09	WG1496709
(S) p-Terphenyl-d14	84.6			10.0-128		06/23/2020 15:09	WG1496709

# <sup>5</sup>Sr







	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Anthracene	0.0000325	J	0.0000190	0.0000500	1	06/24/2020 09:58	WG1497657
Acenaphthene	0.000509		0.0000190	0.0000500	1	06/24/2020 09:58	WG1497657
Acenaphthylene	U		0.0000171	0.0000500	1	06/24/2020 09:58	WG1497657
Benzo(b)fluoranthene	U		0.0000168	0.0000500	1	06/24/2020 09:58	WG1497657
Benzo(k)fluoranthene	U		0.0000202	0.0000500	1	06/24/2020 09:58	WG1497657
Chrysene	U		0.0000179	0.0000500	1	06/24/2020 09:58	WG1497657
Fluoranthene	0.0000280	<u>J</u>	0.0000270	0.000100	1	06/24/2020 09:58	WG1497657
Fluorene	0.00440		0.0000169	0.0000500	1	06/24/2020 09:58	WG1497657
Naphthalene	0.00609		0.0000917	0.000250	1	06/24/2020 09:58	WG1497657
Phenanthrene	0.000937		0.0000180	0.0000500	1	06/24/2020 09:58	WG1497657
Pyrene	U		0.0000169	0.0000500	1	06/24/2020 09:58	WG1497657
2-Methylnaphthalene	0.00138		0.0000674	0.000250	1	06/24/2020 09:58	WG1497657
(S) Nitrobenzene-d5	104			31.0-160		06/24/2020 09:58	WG1497657
(S) 2-Fluorobiphenyl	97.4			48.0-148		06/24/2020 09:58	WG1497657
(S) p-Terphenyl-d14	101			37.0-146		06/24/2020 09:58	WG1497657

ONE LAB. NATIONWIDE.

Collected date/time: 06/17/20 11:43

L1231742

#### Volatile Organic Compounds (GC/MS) by Method 8260B

		,					
	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Ethylbenzene	U		0.000137	0.00100	1	06/24/2020 13:47	WG1498313
Total Xylenes	U		0.000174	0.00300	1	06/24/2020 13:47	WG1498313
(S) Toluene-d8	109			80.0-120		06/24/2020 13:47	WG1498313
(S) 4-Bromofluorobenzene	103			77.0-126		06/24/2020 13:47	WG1498313
(S) 1,2-Dichloroethane-d4	123			70.0-130		06/24/2020 13:47	WG1498313









#### Semi Volatile Organic Compounds (GC/MS) by Method 8270C

	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Carbazole	U		0.000111	0.0100	1	06/23/2020 16:13	WG1496709
Dibenzofuran	U		0.0000970	0.0100	1	06/23/2020 16:13	WG1496709
2,4-Dichlorophenol	U		0.000102	0.0100	1	06/23/2020 16:13	WG1496709
2,4-Dimethylphenol	U		0.0000636	0.0100	1	06/23/2020 16:13	WG1496709
2-Methylphenol	U		0.0000929	0.0100	1	06/23/2020 16:13	WG1496709
3&4-methyl phenol	U		0.000168	0.0100	1	06/23/2020 16:13	WG1496709
Phenol	U		0.00433	0.0100	1	06/23/2020 16:13	WG1496709
Pentachlorophenol	0.00182		0.000313	0.00100	1	06/23/2020 16:13	WG1496709
2,4,6-Trichlorophenol	U		0.000100	0.0100	1	06/23/2020 16:13	WG1496709
2,3,4,6-Tetrachlorophenol	U		0.000231	0.0100	1	06/23/2020 16:13	WG1496709
(S) 2-Fluorophenol	47.4			10.0-120		06/23/2020 16:13	WG1496709
(S) Phenol-d5	29.7			10.0-120		06/23/2020 16:13	WG1496709
(S) Nitrobenzene-d5	68.8			10.0-127		06/23/2020 16:13	WG1496709
(S) 2-Fluorobiphenyl	74.9			10.0-130		06/23/2020 16:13	WG1496709
(S) 2,4,6-Tribromophenol	90.7			10.0-155		06/23/2020 16:13	WG1496709
(S) p-Terphenyl-d14	91.5			10.0-128		06/23/2020 16:13	WG1496709

# <sup>′</sup>Gl

СQс





	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Anthracene	U		0.0000190	0.0000500	1	06/23/2020 16:04	WG1497093
Acenaphthene	U		0.0000190	0.0000500	1	06/23/2020 16:04	WG1497093
Acenaphthylene	U		0.0000171	0.0000500	1	06/23/2020 16:04	WG1497093
Benzo(b)fluoranthene	U		0.0000168	0.0000500	1	06/23/2020 16:04	WG1497093
Benzo(k)fluoranthene	U		0.0000202	0.0000500	1	06/23/2020 16:04	WG1497093
Chrysene	U		0.0000179	0.0000500	1	06/23/2020 16:04	WG1497093
Fluoranthene	U		0.0000270	0.000100	1	06/23/2020 16:04	WG1497093
Fluorene	U		0.0000169	0.0000500	1	06/23/2020 16:04	WG1497093
Naphthalene	U		0.0000917	0.000250	1	06/23/2020 16:04	WG1497093
Phenanthrene	U		0.0000180	0.0000500	1	06/23/2020 16:04	WG1497093
Pyrene	U		0.0000169	0.0000500	1	06/23/2020 16:04	WG1497093
2-Methylnaphthalene	U		0.0000674	0.000250	1	06/23/2020 16:04	WG1497093
(S) Nitrobenzene-d5	101			31.0-160		06/23/2020 16:04	WG1497093
(S) 2-Fluorobiphenyl	91.6			48.0-148		06/23/2020 16:04	WG1497093
(S) p-Terphenyl-d14	94.7			37.0-146		06/23/2020 16:04	WG1497093

ONE LAB. NATIONWIDE.

Collected date/time: 06/18/20 08:44

#### Volatile Organic Compounds (GC/MS) by Method 8260B

_	-		-				
	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Ethylbenzene	U		0.000137	0.00100	1	06/24/2020 16:34	WG1498313
Total Xylenes	U		0.000174	0.00300	1	06/24/2020 16:34	WG1498313
(S) Toluene-d8	107			80.0-120		06/24/2020 16:34	WG1498313
(S) 4-Bromofluorobenzene	106			77.0-126		06/24/2020 16:34	WG1498313
(S) 1,2-Dichloroethane-d4	125			70.0-130		06/24/2020 16:34	WG1498313









СQс

Gl

Sc

#### Semi Volatile Organic Compounds (GC/MS) by Method 8270 C-SIM

	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Anthracene	U		0.0000190	0.0000500	1	06/26/2020 00:12	WG1497672
Acenaphthene	U		0.0000190	0.0000500	1	06/26/2020 00:12	WG1497672
Acenaphthylene	U		0.0000170	0.0000500	1	06/26/2020 00:12	WG1497672
Benzo(b)fluoranthene	U		0.0000170	0.0000500	1	06/26/2020 00:12	WG1497672
Benzo(k)fluoranthene	U		0.0000200	0.000250	1	06/26/2020 00:12	WG1497672
Chrysene	U		0.0000180	0.0000500	1	06/26/2020 00:12	WG1497672
Fluoranthene	0.0000213	J	0.0000110	0.0000500	1	06/26/2020 00:12	WG1497672
Fluorene	U		0.0000170	0.0000500	1	06/26/2020 00:12	WG1497672
Naphthalene	U		0.000128	0.000500	1	06/26/2020 00:12	WG1497672
Phenanthrene	0.0000184	<u>J</u>	0.0000180	0.0000500	1	06/26/2020 00:12	WG1497672
Pyrene	U		0.0000170	0.0000500	1	06/26/2020 00:12	WG1497672
2-Methylnaphthalene	U		0.0000280	0.000500	1	06/26/2020 00:12	WG1497672
(S) Nitrobenzene-d5	86.1			11.0-135		06/26/2020 00:12	WG1497672
(S) 2-Fluorobiphenyl	70.6			32.0-120		06/26/2020 00:12	WG1497672
(S) p-Terphenyl-d14	74.4			23.0-122		06/26/2020 00:12	WG1497672
(S) 2-Methylnaphthalene-D10	62.8			50.0-150		06/26/2020 00:12	WG1497672
(S) Fluoranthene-D10	66.7			50.0-150		06/26/2020 00:12	WG1497672

	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Carbazole	U		0.000111	0.0100	1	06/23/2020 16:34	WG1496709
Dibenzofuran	U		0.0000970	0.0100	1	06/23/2020 16:34	WG1496709
2,4-Dichlorophenol	U		0.000102	0.0100	1	06/23/2020 16:34	WG1496709
2,4-Dimethylphenol	U		0.0000636	0.0100	1	06/23/2020 16:34	WG1496709
2-Methylphenol	U		0.0000929	0.0100	1	06/23/2020 16:34	WG1496709
3&4-methyl phenol	U		0.000168	0.0100	1	06/23/2020 16:34	WG1496709
Phenol	U		0.00433	0.0100	1	06/23/2020 16:34	WG1496709
Pentachlorophenol	U		0.000313	0.00100	1	06/23/2020 16:34	WG1496709
2,4,6-Trichlorophenol	U		0.000100	0.0100	1	06/23/2020 16:34	WG1496709
2,3,4,6-Tetrachlorophenol	U		0.000231	0.0100	1	06/23/2020 16:34	WG1496709
(S) 2-Fluorophenol	44.3			10.0-120		06/23/2020 16:34	WG1496709
(S) Phenol-d5	27.5			10.0-120		06/23/2020 16:34	WG1496709
(S) Nitrobenzene-d5	65.4			10.0-127		06/23/2020 16:34	WG1496709
(S) 2-Fluorobiphenyl	70.8			10.0-130		06/23/2020 16:34	WG1496709
(S) 2,4,6-Tribromophenol	83.0			10.0-155		06/23/2020 16:34	WG1496709
(S) p-Terphenyl-d14	83.1			10.0-128		06/23/2020 16:34	WG1496709

ONE LAB. NATIONWIDE.

Collected date/time: 06/18/20 08:47

L1231742

#### Volatile Organic Compounds (GC/MS) by Method 8260B

	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Ethylbenzene	U		0.000137	0.00100	1	06/24/2020 16:58	WG1498313
Total Xylenes	U		0.000174	0.00300	1	06/24/2020 16:58	WG1498313
(S) Toluene-d8	107			80.0-120		06/24/2020 16:58	WG1498313
(S) 4-Bromofluorobenzene	104			77.0-126		06/24/2020 16:58	WG1498313
(S) 1,2-Dichloroethane-d4	124			70.0-130		06/24/2020 16:58	WG1498313









#### Semi Volatile Organic Compounds (GC/MS) by Method 8270C

	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Carbazole	U		0.000111	0.0100	1	06/25/2020 17:24	WG1497670
Dibenzofuran	U		0.0000970	0.0100	1	06/25/2020 17:24	WG1497670
2,4-Dichlorophenol	U		0.000102	0.0100	1	06/25/2020 17:24	WG1497670
2,4-Dimethylphenol	U		0.0000636	0.0100	1	06/25/2020 17:24	WG1497670
2-Methylphenol	U		0.0000929	0.0100	1	06/25/2020 17:24	WG1497670
3&4-methyl phenol	U		0.000168	0.0100	1	06/25/2020 17:24	WG1497670
Phenol	U		0.00433	0.0100	1	06/25/2020 17:24	WG1497670
Pentachlorophenol	U		0.000313	0.00100	1	06/25/2020 17:24	WG1497670
2,4,6-Trichlorophenol	U		0.000100	0.0100	1	06/25/2020 17:24	WG1497670
2,3,4,6-Tetrachlorophenol	U		0.000231	0.0100	1	06/25/2020 17:24	WG1497670
(S) 2-Fluorophenol	37.7			10.0-120		06/25/2020 17:24	WG1497670
(S) Phenol-d5	22.5			10.0-120		06/25/2020 17:24	WG1497670
(S) Nitrobenzene-d5	61.7			10.0-127		06/25/2020 17:24	WG1497670
(S) 2-Fluorobiphenyl	67.0			10.0-130		06/25/2020 17:24	WG1497670
(S) 2,4,6-Tribromophenol	74.2			10.0-155		06/25/2020 17:24	WG1497670
(S) p-Terphenyl-d14	78.3			10.0-128		06/25/2020 17:24	WG1497670

## <sup>7</sup>Gl

СQс





	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Anthracene	U		0.0000190	0.0000500	1	06/25/2020 08:32	WG1497880
Acenaphthene	U		0.0000190	0.0000500	1	06/25/2020 08:32	WG1497880
Acenaphthylene	U		0.0000171	0.0000500	1	06/25/2020 08:32	WG1497880
Benzo(b)fluoranthene	U		0.0000168	0.0000500	1	06/25/2020 08:32	WG1497880
Benzo(k)fluoranthene	U		0.0000202	0.0000500	1	06/25/2020 08:32	WG1497880
Chrysene	U		0.0000179	0.0000500	1	06/25/2020 08:32	WG1497880
Fluoranthene	0.0000324	<u>J</u>	0.0000270	0.000100	1	06/25/2020 08:32	WG1497880
Fluorene	U		0.0000169	0.0000500	1	06/25/2020 08:32	WG1497880
Naphthalene	U		0.0000917	0.000250	1	06/25/2020 08:32	WG1497880
Phenanthrene	U		0.0000180	0.0000500	1	06/25/2020 08:32	WG1497880
Pyrene	U		0.0000169	0.0000500	1	06/25/2020 08:32	WG1497880
2-Methylnaphthalene	U		0.0000674	0.000250	1	06/25/2020 08:32	WG1497880
(S) Nitrobenzene-d5	159			31.0-160		06/25/2020 08:32	WG1497880
(S) 2-Fluorobiphenyl	107			48.0-148		06/25/2020 08:32	WG1497880
(S) p-Terphenyl-d14	89.5			37.0-146		06/25/2020 08:32	WG1497880

ONE LAB. NATIONWIDE.

Collected date/time: 06/18/20 09:20

L1231742

#### Volatile Organic Compounds (GC/MS) by Method 8260B

	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch			
Analyte	mg/l		mg/l	mg/l		date / time				
Ethylbenzene	U		0.000137	0.00100	1	06/24/2020 17:22	WG1498313			
Total Xylenes	U		0.000174	0.00300	1	06/24/2020 17:22	WG1498313			
(S) Toluene-d8	108			80.0-120		06/24/2020 17:22	WG1498313			
(S) 4-Bromofluorobenzene	108			77.0-126		06/24/2020 17:22	WG1498313			
(S) 1,2-Dichloroethane-d4	126			70.0-130		06/24/2020 17:22	WG1498313			









#### Semi Volatile Organic Compounds (GC/MS) by Method 8270C

	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Carbazole	U		0.000111	0.0100	1	06/25/2020 17:45	WG1497670
Dibenzofuran	0.00116	<u>J</u>	0.0000970	0.0100	1	06/25/2020 17:45	WG1497670
2,4-Dichlorophenol	U		0.000102	0.0100	1	06/25/2020 17:45	WG1497670
2,4-Dimethylphenol	U		0.0000636	0.0100	1	06/25/2020 17:45	WG1497670
2-Methylphenol	U		0.0000929	0.0100	1	06/25/2020 17:45	WG1497670
3&4-methyl phenol	U		0.000168	0.0100	1	06/25/2020 17:45	WG1497670
Phenol	U		0.00433	0.0100	1	06/25/2020 17:45	WG1497670
Pentachlorophenol	U		0.000313	0.00100	1	06/25/2020 17:45	WG1497670
2,4,6-Trichlorophenol	U		0.000100	0.0100	1	06/25/2020 17:45	WG1497670
2,3,4,6-Tetrachlorophenol	U		0.000231	0.0100	1	06/25/2020 17:45	WG1497670
(S) 2-Fluorophenol	38.8			10.0-120		06/25/2020 17:45	WG1497670
(S) Phenol-d5	24.8			10.0-120		06/25/2020 17:45	WG1497670
(S) Nitrobenzene-d5	62.2			10.0-127		06/25/2020 17:45	WG1497670
(S) 2-Fluorobiphenyl	65.1			10.0-130		06/25/2020 17:45	WG1497670
(S) 2,4,6-Tribromophenol	74.2			10.0-155		06/25/2020 17:45	WG1497670
(S) p-Terphenyl-d14	78.9			10.0-128		06/25/2020 17:45	WG1497670

## <sup>′</sup>Gl

СQс





	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Anthracene	U		0.0000190	0.0000500	1	06/25/2020 18:41	WG1498394
Acenaphthene	0.00199		0.0000190	0.0000500	1	06/25/2020 18:41	WG1498394
Acenaphthylene	0.0000256	<u>J</u>	0.0000171	0.0000500	1	06/25/2020 18:41	WG1498394
Benzo(b)fluoranthene	U		0.0000168	0.0000500	1	06/25/2020 18:41	WG1498394
Benzo(k)fluoranthene	U		0.0000202	0.0000500	1	06/25/2020 18:41	WG1498394
Chrysene	U		0.0000179	0.0000500	1	06/25/2020 18:41	WG1498394
Fluoranthene	0.0000340	<u>J</u>	0.0000270	0.000100	1	06/25/2020 18:41	WG1498394
Fluorene	0.00105		0.0000169	0.0000500	1	06/25/2020 18:41	WG1498394
Naphthalene	0.0591		0.0000917	0.000250	1	06/25/2020 18:41	WG1498394
Phenanthrene	0.000566		0.0000180	0.0000500	1	06/25/2020 18:41	WG1498394
Pyrene	U		0.0000169	0.0000500	1	06/25/2020 18:41	WG1498394
2-Methylnaphthalene	0.00521		0.0000674	0.000250	1	06/25/2020 18:41	WG1498394
(S) Nitrobenzene-d5	142			31.0-160		06/25/2020 18:41	WG1498394
(S) 2-Fluorobiphenyl	72.1			48.0-148		06/25/2020 18:41	WG1498394
(S) p-Terphenyl-d14	86.8			37.0-146		06/25/2020 18:41	WG1498394

ONE LAB. NATIONWIDE.

Collected date/time: 06/18/20 09:25

#### Volatile Organic Compounds (GC/MS) by Method 8260B

_	-		-				
	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Ethylbenzene	U		0.000137	0.00100	1	06/24/2020 17:45	WG1498313
Total Xylenes	U		0.000174	0.00300	1	06/24/2020 17:45	WG1498313
(S) Toluene-d8	111			80.0-120		06/24/2020 17:45	WG1498313
(S) 4-Bromofluorobenzene	112			77.0-126		06/24/2020 17:45	WG1498313
(S) 1,2-Dichloroethane-d4	124			70.0-130		06/24/2020 17:45	WG1498313







Cn



#### Semi Volatile Organic Compounds (GC/MS) by Method 8270C

	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
Analyte	mg/l		mg/l	mg/l		date / time	
Carbazole	0.000144	<u>J</u>	0.000111	0.0100	1	06/25/2020 18:05	WG1497670
Dibenzofuran	0.00152	<u>J</u>	0.0000970	0.0100	1	06/25/2020 18:05	WG1497670
2,4-Dichlorophenol	U		0.000102	0.0100	1	06/25/2020 18:05	WG1497670
2,4-Dimethylphenol	U		0.0000636	0.0100	1	06/25/2020 18:05	WG1497670
2-Methylphenol	U		0.0000929	0.0100	1	06/25/2020 18:05	WG1497670
3&4-methyl phenol	U		0.000168	0.0100	1	06/25/2020 18:05	WG1497670
Phenol	U		0.00433	0.0100	1	06/25/2020 18:05	WG1497670
Pentachlorophenol	U		0.000313	0.00100	1	06/25/2020 18:05	WG1497670
2,4,6-Trichlorophenol	U		0.000100	0.0100	1	06/25/2020 18:05	WG1497670
2,3,4,6-Tetrachlorophenol	U		0.000231	0.0100	1	06/25/2020 18:05	WG1497670
(S) 2-Fluorophenol	40.2			10.0-120		06/25/2020 18:05	WG1497670
(S) Phenol-d5	25.4			10.0-120		06/25/2020 18:05	WG1497670
(S) Nitrobenzene-d5	62.8			10.0-127		06/25/2020 18:05	WG1497670
(S) 2-Fluorobiphenyl	68.7			10.0-130		06/25/2020 18:05	WG1497670
(S) 2,4,6-Tribromophenol	77.5			10.0-155		06/25/2020 18:05	WG1497670
(S) p-Terphenyl-d14	74.0			10.0-128		06/25/2020 18:05	WG1497670

## СQс





## Sc

#### Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

	Result	Qualifier	MDL	RDL	Dilution	Analysis	<u>Batch</u>
Analyte	mg/l		mg/l	mg/l		date / time	
Anthracene	U		0.0000190	0.0000500	1	06/25/2020 19:05	WG1498394
Acenaphthene	0.00165		0.0000190	0.0000500	1	06/25/2020 19:05	WG1498394
Acenaphthylene	0.0000206	<u>J</u>	0.0000171	0.0000500	1	06/25/2020 19:05	WG1498394
Benzo(b)fluoranthene	0.0000170	<u>J</u>	0.0000168	0.0000500	1	06/25/2020 19:05	WG1498394
Benzo(k)fluoranthene	U		0.0000202	0.0000500	1	06/25/2020 19:05	WG1498394
Chrysene	U		0.0000179	0.0000500	1	06/25/2020 19:05	WG1498394
Fluoranthene	0.0000371	<u>J</u>	0.0000270	0.000100	1	06/25/2020 19:05	WG1498394
Fluorene	0.000888		0.0000169	0.0000500	1	06/25/2020 19:05	WG1498394
Naphthalene	0.0417		0.0000917	0.000250	1	06/25/2020 19:05	WG1498394
Phenanthrene	0.000400		0.0000180	0.0000500	1	06/25/2020 19:05	WG1498394
Pyrene	0.0000397	J	0.0000169	0.0000500	1	06/25/2020 19:05	WG1498394
2-Methylnaphthalene	0.00323		0.0000674	0.000250	1	06/25/2020 19:05	WG1498394
(S) Nitrobenzene-d5	145			31.0-160		06/25/2020 19:05	WG1498394
(S) 2-Fluorobiphenyl	81.1			48.0-148		06/25/2020 19:05	WG1498394
(S) p-Terphenyl-d14	85.3			37.0-146		06/25/2020 19:05	WG1498394

EarthCon Consultants, Inc - Marietta, GA 02.20000006.20 L1231742 06/29/20 11:52 16 of 33

ONE LAB. NATIONWIDE.

Volatile Organic Compounds (GC/MS) by Method 8260B

L1231742-01,02,03,04,05,06,07,08,09,10,11

#### Method Blank (MB)

(MB) R3542550-2 06/24/	20 13:07			
	MB Result	MB Qualifier	MB MDL	MB RDL
Analyte	mg/l		mg/l	mg/l
Ethylbenzene	U		0.000137	0.00100
Xylenes, Total	U		0.000174	0.00300
(S) Toluene-d8	108			80.0-120
(S) 4-Bromofluorobenzene	105			77.0-126
(S) 1,2-Dichloroethane-d4	120			70.0-130

## <sup>2</sup>Tc







#### Laboratory Control Sample (LCS)

(LCS) R3542550-1 06/24/	20 12:19				
	Spike Amount	LCS Result	LCS Rec.	Rec. Limits	LCS Qualifier
Analyte	mg/l	mg/l	%	%	
Ethylbenzene	0.00500	0.00431	86.2	79.0-123	
Xylenes, Total	0.0150	0.0131	87.3	79.0-123	
(S) Toluene-d8			103	80.0-120	
(S) 4-Bromofluorobenzene			103	77.0-126	
(S) 1,2-Dichloroethane-d4			119	70.0-130	









ONE LAB. NATIONWIDE.

Semi Volatile Organic Compounds (GC/MS) by Method 8270 C-SIM

L1231742-08

#### Method Blank (MB)

(MB) R3543279-3 06/25/2	20 23:52				
	MB Result	MB Qualifier	MB MDL	MB RDL	
Analyte	mg/l		mg/l	mg/l	
Anthracene	U		0.0000190	0.0000500	
Acenaphthene	U		0.0000190	0.0000500	
Acenaphthylene	U		0.0000170	0.0000500	
Benzo(b)fluoranthene	U		0.0000170	0.0000500	
Benzo(k)fluoranthene	U		0.0000200	0.000250	
Chrysene	U		0.0000180	0.0000500	
Fluoranthene	U		0.0000110	0.0000500	
Fluorene	U		0.0000170	0.0000500	
Naphthalene	U		0.000128	0.000500	
Phenanthrene	U		0.0000180	0.0000500	
Pyrene	U		0.0000170	0.0000500	
2-Methylnaphthalene	U		0.0000280	0.000500	
(S) Nitrobenzene-d5	82.5			11.0-135	
(S) 2-Methylnaphthalene-d10	62.0			50.0-150	
(S) 2-Fluorobiphenyl	69.5			32.0-120	
(S) Fluoranthene-d10	66.5			50.0-150	
(S) p-Terphenyl-d14	75.0			23.0-122	

#### Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3543279-1 06/25/	•	•			LCCD Das	Don Limito	I CC O. alifian	LCCD Ovelifier	DDD	DDD Limite
	Spike Amount		LCSD Result	LCS Rec.	LCSD Rec.	Rec. Limits	LCS Qualifier	LCSD Qualifier		RPD Limits
Analyte	mg/l	mg/l	mg/l	%	%	%			%	%
Anthracene	0.00200	0.00138	0.00135	69.0	67.5	43.0-127			2.20	20
Acenaphthene	0.00200	0.00149	0.00149	74.5	74.5	42.0-120			0.000	20
Acenaphthylene	0.00200	0.00147	0.00149	73.5	74.5	43.0-120			1.35	20
Benzo(b)fluoranthene	0.00200	0.00131	0.00134	65.5	67.0	43.0-122			2.26	20
Benzo(k)fluoranthene	0.00200	0.00135	0.00139	67.5	69.5	39.0-128			2.92	22
Chrysene	0.00200	0.00143	0.00143	71.5	71.5	42.0-129			0.000	20
Fluoranthene	0.00200	0.00143	0.00141	71.5	70.5	48.0-131			1.41	20
Fluorene	0.00200	0.00145	0.00145	72.5	72.5	42.0-120			0.000	20
Naphthalene	0.00200	0.00140	0.00142	70.0	71.0	30.0-120			1.42	22
Phenanthrene	0.00200	0.00150	0.00146	75.0	73.0	42.0-120			2.70	20
Pyrene	0.00200	0.00158	0.00159	79.0	79.5	38.0-124			0.631	20
2-Methylnaphthalene	0.00200	0.00138	0.00139	69.0	69.5	40.0-120			0.722	20
(S) Nitrobenzene-d5				81.5	81.5	11.0-135				
(S) 2-Methylnaphthalene-d1	0			62.0	62.5	50.0-150				
(S) 2-Fluorobiphenyl				69.0	69.5	32.0-120				
(S) Fluoranthene-d10				67.0	67.0	50.0-150				

Semi Volatile Organic Compounds (GC/MS) by Method 8270 C-SIM

#### Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3543279-1 06/25/20 23:12 • (LCSD) R3543279-2 06/25/20 23:32

	Spike Amount	LCS Result	LCSD Result	LCS Rec.	LCSD Rec.	Rec. Limits	LCS Qualifier	LCSD Qualifier	RPD	RPD Limits
Analyte	mg/l	mg/l	mg/l	%	%	%			%	%
(S) p-Terphenyl-d14				72.5	73.0	23.0-122				



















PAGE:

19 of 33

ONE LAB. NATIONWIDE.

Semi Volatile Organic Compounds (GC/MS) by Method 8270C

L1231742-01,02,03,04,05,06,07,08

#### Method Blank (MB)

(MB) R3542249-2 06/23	3/20 14:06				
	MB Result	MB Qualifier	MB MDL	MB RDL	
Analyte	mg/l		mg/l	mg/l	
Carbazole	U		0.000111	0.0100	
Dibenzofuran	U		0.0000970	0.0100	
2-Methylphenol	U		0.0000929	0.0100	
3&4-Methyl Phenol	U		0.000168	0.0100	
2,4-Dichlorophenol	U		0.000102	0.0100	
2,4-Dimethylphenol	U		0.0000636	0.0100	
Pentachlorophenol	U		0.000313	0.00100	
2,3,4,6-Tetrachlorophenol	U		0.000231	0.0100	
Phenol	U		0.00433	0.0100	
2,4,6-Trichlorophenol	U		0.000100	0.0100	
(S) Nitrobenzene-d5	65.6			10.0-127	
(S) 2-Fluorobiphenyl	<i>75.5</i>			10.0-130	
(S) p-Terphenyl-d14	85.2			10.0-128	
(S) Phenol-d5	29.0			10.0-120	
(S) 2-Fluorophenol	44.9			10.0-120	
(S) 2,4,6-Tribromophenol	83.5			10.0-155	

### Laboratory Control Sample (LCS)

(LCS) R3542249-1 06/23/	/20 13:45				
	Spike Amount	LCS Result	LCS Rec.	Rec. Limits	LCS Qualifier
Analyte	mg/l	mg/l	%	%	
Carbazole	0.0500	0.0415	83.0	51.0-122	
Dibenzofuran	0.0500	0.0414	82.8	44.0-120	
2-Methylphenol	0.0500	0.0345	69.0	28.0-120	
3&4-Methyl Phenol	0.0500	0.0330	66.0	31.0-120	
2,4-Dichlorophenol	0.0500	0.0346	69.2	36.0-120	
2,4-Dimethylphenol	0.0500	0.0352	70.4	33.0-120	
Pentachlorophenol	0.0500	0.0408	81.6	23.0-120	
Phenol	0.0500	0.0144	28.8	10.0-120	
2,4,6-Trichlorophenol	0.0500	0.0404	80.8	42.0-120	
2,3,4,6-Tetrachlorophenol	0.0500	0.0455	91.0	42.0-132	
(S) Nitrobenzene-d5			61.7	10.0-127	
(S) 2-Fluorobiphenyl			83.1	10.0-130	
(S) p-Terphenyl-d14			89.0	10.0-128	
(S) Phenol-d5			29.5	10.0-120	
(S) 2-Fluorophenol			46.5	10.0-120	
(S) 2,4,6-Tribromophenol			98.5	10.0-155	

ONE LAB. NATIONWIDE.

Semi Volatile Organic Compounds (GC/MS) by Method 8270C

L1231742-01,02,03,04,05,06,07,08

#### L1231742-06 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1231742-06 06/23/20 15:09 • (MS) R3542249-3 06/23/20 15:31 • (MSD) R3542249-4 06/23/20 15:52

	Spike Amount	Original Result	MS Result	MSD Result	MS Rec.	MSD Rec.	Dilution	Rec. Limits	MS Qualifier	MSD Qualifier	RPD	RPD Limits
Analyte	mg/l	mg/l	mg/l	mg/l	%	%		%			%	%
Carbazole	0.0455	0.00503	0.0432	0.0394	83.9	75.5	1	38.0-127			9.20	21
Dibenzofuran	0.0455	0.00164	0.0381	0.0354	80.1	74.2	1	32.0-120			7.35	26
2-Methylphenol	0.0455	U	0.0304	0.0295	66.8	64.8	1	10.0-120			3.01	30
3&4-Methyl Phenol	0.0455	U	0.0297	0.0287	65.3	63.1	1	10.0-120			3.42	36
2,4-Dichlorophenol	0.0455	U	0.0312	0.0304	68.6	66.8	1	19.0-120			2.60	27
2,4-Dimethylphenol	0.0455	U	0.0324	0.0318	71.2	69.9	1	15.0-120			1.87	28
Pentachlorophenol	0.0455	U	0.0380	0.0353	83.5	77.6	1	10.0-128			7.37	37
Phenol	0.0455	U	0.0152	0.0130	33.4	28.6	1	10.0-120			15.6	40
2,4,6-Trichlorophenol	0.0455	U	0.0351	0.0340	77.1	74.7	1	26.0-120			3.18	31
2,3,4,6-Tetrachlorophenol	0.0455	U	0.0417	0.0384	91.6	84.4	1	17.0-142			8.24	34
(S) Nitrobenzene-d5					60.5	57.9		10.0-127				
(S) 2-Fluorobiphenyl					76.3	75.4		10.0-130				
(S) p-Terphenyl-d14					88.8	82.4		10.0-128				
(S) Phenol-d5					27.9	28.0		10.0-120				
(S) 2-Fluorophenol					44.0	43.8		10.0-120				
(S) 2,4,6-Tribromophenol					94.5	91.2		10.0-155				



















ONE LAB. NATIONWIDE.

Sc

Semi Volatile Organic Compounds (GC/MS) by Method 8270C

L1231742-09,10,11

#### Method Blank (MB)

(MB) R3542952-3 06/25	/20 12:15				
	MB Result	MB Qualifier	MB MDL	MB RDL	
Analyte	mg/l		mg/l	mg/l	
Carbazole	U		0.000111	0.0100	
Dibenzofuran	U		0.0000970	0.0100	
2-Methylphenol	U		0.0000929	0.0100	
3&4-Methyl Phenol	U		0.000168	0.0100	
2,4-Dichlorophenol	U		0.000102	0.0100	
2,4-Dimethylphenol	U		0.0000636	0.0100	
Pentachlorophenol	U		0.000313	0.00100	
2,3,4,6-Tetrachlorophenol	U		0.000231	0.0100	
Phenol	U		0.00433	0.0100	
2,4,6-Trichlorophenol	U		0.000100	0.0100	
(S) Nitrobenzene-d5	63.4			10.0-127	
(S) 2-Fluorobiphenyl	69.0			10.0-130	
(S) p-Terphenyl-d14	73.2			10.0-128	
(S) Phenol-d5	24.8			10.0-120	
(S) 2-Fluorophenol	40.8			10.0-120	
(S) 2,4,6-Tribromophenol	68.5			10.0-155	

#### Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3542952-1 06/25	5/20 11:34 • (LCSI	D) R3542952	-2 06/25/20 11:	54							
	Spike Amount	LCS Result	LCSD Result	LCS Rec.	LCSD Rec.	Rec. Limits	LCS Qualifier	LCSD Qualifier	RPD	RPD Limits	
Analyte	mg/l	mg/l	mg/l	%	%	%			%	%	
Carbazole	0.0500	0.0404	0.0407	80.8	81.4	51.0-122			0.740	20	
Dibenzofuran	0.0500	0.0403	0.0383	80.6	76.6	44.0-120			5.09	22	
2-Methylphenol	0.0500	0.0351	0.0324	70.2	64.8	28.0-120			8.00	29	
3&4-Methyl Phenol	0.0500	0.0339	0.0320	67.8	64.0	31.0-120			5.77	30	
2,4-Dichlorophenol	0.0500	0.0350	0.0333	70.0	66.6	36.0-120			4.98	26	
2,4-Dimethylphenol	0.0500	0.0344	0.0325	68.8	65.0	33.0-120			5.68	26	
Pentachlorophenol	0.0500	0.0346	0.0314	69.2	62.8	23.0-120			9.70	25	
Phenol	0.0500	0.0189	0.0177	37.8	35.4	10.0-120			6.56	36	
2,4,6-Trichlorophenol	0.0500	0.0388	0.0361	77.6	72.2	42.0-120			7.21	23	
2,3,4,6-Tetrachlorophenol	0.0500	0.0437	0.0410	87.4	82.0	42.0-132			6.38	22	
(S) Nitrobenzene-d5				61.5	58.7	10.0-127					
(S) 2-Fluorobiphenyl				74.4	69.3	10.0-130					
(S) p-Terphenyl-d14				79.5	77.3	10.0-128					
(S) Phenol-d5				29.2	27.9	10.0-120					
(S) 2-Fluorophenol				46.1	42.7	10.0-120					
(S) 2,4,6-Tribromophenol				85.5	82.0	10.0-155					

ONE LAB. NATIONWIDE.

Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

L1231742-01,02

#### Method Blank (MB)

(MB) R3542178-3 06/23	3/20 22:50					
	MB Result	MB Qualifier	MB MDL	MB RDL		
Analyte	mg/l		mg/l	mg/l		
Anthracene	U		0.0000190	0.0000500		
Acenaphthene	U		0.0000190	0.0000500		
Acenaphthylene	U		0.0000171	0.0000500		
Benzo(b)fluoranthene	U		0.0000168	0.0000500		
Benzo(k)fluoranthene	U		0.0000202	0.0000500		
Chrysene	U		0.0000179	0.0000500		
Fluoranthene	U		0.0000270	0.000100		
Fluorene	U		0.0000169	0.0000500		
Naphthalene	U		0.0000917	0.000250		
Phenanthrene	U		0.0000180	0.0000500		
Pyrene	U		0.0000169	0.0000500		
2-Methylnaphthalene	U		0.0000674	0.000250		
(S) Nitrobenzene-d5	103			31.0-160		
(S) 2-Fluorobiphenyl	90.0			48.0-148		
(S) p-Terphenyl-d14	96.0			37.0-146		

#### Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3542178-1	06/23/20 22:10	• (LCSD) R3542178-2	06/23/20 22:30	
------------------	----------------	---------------------	----------------	--

	Spike Amount	LCS Result	LCSD Result	LCS Rec.	LCSD Rec.	Rec. Limits	LCS Qualifier	LCSD Qualifier	RPD	RPD Limits
Analyte	mg/l	mg/l	mg/l	%	%	%			%	%
Anthracene	0.00200	0.00180	0.00180	90.0	90.0	67.0-150			0.000	20
Acenaphthene	0.00200	0.00193	0.00193	96.5	96.5	65.0-138			0.000	20
Acenaphthylene	0.00200	0.00192	0.00194	96.0	97.0	66.0-140			1.04	20
Benzo(b)fluoranthene	0.00200	0.00184	0.00175	92.0	87.5	58.0-141			5.01	20
Benzo(k)fluoranthene	0.00200	0.00184	0.00179	92.0	89.5	58.0-148			2.75	20
Chrysene	0.00200	0.00186	0.00188	93.0	94.0	64.0-144			1.07	20
Fluoranthene	0.00200	0.00183	0.00184	91.5	92.0	69.0-153			0.545	20
Fluorene	0.00200	0.00187	0.00189	93.5	94.5	64.0-136			1.06	20
Naphthalene	0.00200	0.00182	0.00182	91.0	91.0	61.0-137			0.000	20
Phenanthrene	0.00200	0.00188	0.00190	94.0	95.0	62.0-137			1.06	20
Pyrene	0.00200	0.00206	0.00210	103	105	60.0-142			1.92	20
2-Methylnaphthalene	0.00200	0.00180	0.00185	90.0	92.5	62.0-136			2.74	20
(S) Nitrobenzene-d5				113	103	31.0-160				
(S) 2-Fluorobiphenyl				94.5	91.5	48.0-148				
(S) p-Terphenyl-d14				94.5	94.5	37.0-146				

ONE LAB. NATIONWIDE.

Sc

Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

L1231742-03,04,05,07

#### Method Blank (MB)

(MB) R3541724-2 06/23	3/20 09:42			
	MB Result	MB Qualifier	MB MDL	MB RDL
Analyte	mg/l		mg/l	mg/l
Anthracene	U		0.0000190	0.0000500
Acenaphthene	U		0.0000190	0.0000500
Acenaphthylene	U		0.0000171	0.0000500
Benzo(b)fluoranthene	U		0.0000168	0.0000500
Benzo(k)fluoranthene	U		0.0000202	0.0000500
Chrysene	U		0.0000179	0.0000500
Fluoranthene	U		0.0000270	0.000100
Fluorene	U		0.0000169	0.0000500
Naphthalene	U		0.0000917	0.000250
Phenanthrene	U		0.0000180	0.0000500
Pyrene	U		0.0000169	0.0000500
2-Methylnaphthalene	U		0.0000674	0.000250
(S) Nitrobenzene-d5	114			31.0-160
(S) 2-Fluorobiphenyl	103			48.0-148
(S) p-Terphenyl-d14	107			37.0-146

#### Laboratory Control Sample (LCS)

(LCS) R3541/24-1 06/	/23/20 09:22
----------------------	--------------

(LC3) R3541/24-1 00/23					
	Spike Amount	LCS Result	LCS Rec.	Rec. Limits	LCS Qualifier
Analyte	mg/l	mg/l	%	%	
Anthracene	0.00200	0.00181	90.5	67.0-150	
Acenaphthene	0.00200	0.00188	94.0	65.0-138	
Acenaphthylene	0.00200	0.00191	95.5	66.0-140	
Benzo(b)fluoranthene	0.00200	0.00174	87.0	58.0-141	
Benzo(k)fluoranthene	0.00200	0.00179	89.5	58.0-148	
Chrysene	0.00200	0.00189	94.5	64.0-144	
Fluoranthene	0.00200	0.00187	93.5	69.0-153	
Fluorene	0.00200	0.00185	92.5	64.0-136	
Naphthalene	0.00200	0.00169	84.5	61.0-137	
Phenanthrene	0.00200	0.00190	95.0	62.0-137	
Pyrene	0.00200	0.00200	100	60.0-142	
2-Methylnaphthalene	0.00200	0.00171	85.5	62.0-136	
(S) Nitrobenzene-d5			104	31.0-160	
(S) 2-Fluorobiphenyl			93.5	48.0-148	
(S) p-Terphenyl-d14			94.5	37.0-146	

ONE LAB. NATIONWIDE.

Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

L1231742-03,04,05,07

#### L1231366-01 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1231366-01 06/23/20 10:22 • (MS) R3541724-3 06/23/20 10:42 • (MSD) R3541724-4 06/23/20 11:02

	Spike Amount	Original Result	MS Result	MSD Result	MS Rec.	MSD Rec.	Dilution	Rec. Limits	MS Qualifier	MSD Qualifier	RPD	RPD Limits
Analyte	mg/l	mg/l	mg/l	mg/l	%	%		%			%	%
Anthracene	0.00190	0.000148	0.00219	0.00210	107	103	1	56.0-156			4.20	20
Acenaphthene	0.00190	0.000268	0.00221	0.00219	102	101	1	44.0-153			0.909	20
Acenaphthylene	0.00190	0.0000622	0.00209	0.00206	107	105	1	53.0-150			1.45	20
Benzo(b)fluoranthene	0.00190	U	0.00172	0.00167	90.5	87.9	1	43.0-142			2.95	20
Benzo(k)fluoranthene	0.00190	U	0.00177	0.00173	93.2	91.1	1	43.0-148			2.29	21
Chrysene	0.00190	U	0.00189	0.00186	99.5	97.9	1	50.0-148			1.60	20
Fluoranthene	0.00190	0.0000494	0.00210	0.00200	108	103	1	56.0-157			4.88	20
Fluorene	0.00190	0.000256	0.00217	0.00211	101	97.6	1	48.0-148			2.80	20
Naphthalene	0.00190	U	0.00185	0.00181	97.4	95.3	1	10.0-160			2.19	20
Phenanthrene	0.00190	0.000222	0.00205	0.00197	96.2	92.0	1	47.0-147			3.98	20
Pyrene	0.00190	0.000142	0.00213	0.00210	105	103	1	51.0-148			1.42	20
2-Methylnaphthalene	0.00190	U	0.00194	0.00186	102	97.9	1	31.0-160			4.21	20
(S) Nitrobenzene-d5					114	110		31.0-160				
(S) 2-Fluorobiphenyl					98.9	96.3		48.0-148				
(S) p-Terphenyl-d14					93.2	91.1		37.0-146				



















ONE LAB. NATIONWIDE.

Sc

Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

11231742-06

#### Method Blank (MB)

(MB) R3542237-2 06/2	4/20 09:18					
	MB Result	MB Qualifier	MB MDL	MB RDL		
Analyte	mg/l		mg/l	mg/l		
Anthracene	U		0.0000190	0.0000500		
Acenaphthene	U		0.0000190	0.0000500		
Acenaphthylene	U		0.0000171	0.0000500		
Benzo(b)fluoranthene	U		0.0000168	0.0000500		
Benzo(k)fluoranthene	U		0.0000202	0.0000500		
Chrysene	U		0.0000179	0.0000500		
Fluoranthene	U		0.0000270	0.000100		
Fluorene	U		0.0000169	0.0000500		
Naphthalene	U		0.0000917	0.000250		
Phenanthrene	U		0.0000180	0.0000500		
Pyrene	U		0.0000169	0.0000500		
2-Methylnaphthalene	U		0.0000674	0.000250		
(S) Nitrobenzene-d5	119			31.0-160		
(S) 2-Fluorobiphenyl	108			48.0-148		
(S) p-Terphenyl-d14	117			37.0-146		

#### Laboratory Control Sample (LCS)

(LCS) RS542237-1 06/2					
	Spike Amount	LCS Result	LCS Rec.	Rec. Limits	LCS Qualifier
Analyte	mg/l	mg/l	%	%	
Anthracene	0.00200	0.00200	100	67.0-150	
Acenaphthene	0.00200	0.00212	106	65.0-138	
Acenaphthylene	0.00200	0.00213	106	66.0-140	
Benzo(b)fluoranthene	0.00200	0.00193	96.5	58.0-141	
Benzo(k)fluoranthene	0.00200	0.00185	92.5	58.0-148	
Chrysene	0.00200	0.00201	100	64.0-144	
Fluoranthene	0.00200	0.00204	102	69.0-153	
Fluorene	0.00200	0.00206	103	64.0-136	
Naphthalene	0.00200	0.00201	100	61.0-137	
Phenanthrene	0.00200	0.00208	104	62.0-137	
Pyrene	0.00200	0.00227	114	60.0-142	
2-Methylnaphthalene	0.00200	0.00201	100	62.0-136	
(S) Nitrobenzene-d5			115	31.0-160	
(S) 2-Fluorobiphenyl			102	48.0-148	
(S) p-Terphenyl-d14			98.5	37.0-146	

(S) p-Terphenyl-d14

#### QUALITY CONTROL SUMMARY

ONE LAB. NATIONWIDE.

Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

11231742-06

#### L1231742-06 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1231742-06 06/24/20 09:58 • (MS) R3542237-3 06/24/20 10:18 • (MSD) R3542237-4 06/24/20 10:38

nalyte			MS Result	MSD Result	MS Rec.	MSD Rec.	Dilution	Rec. Limits	MS Qualifier	MSD Qualifier	RPD	RPD Limits
	mg/l	mg/l	mg/l	mg/l	%	%		%			%	%
nthracene	0.00200	0.0000325	0.00199	0.00195	97.9	95.9	1	56.0-156			2.03	20
cenaphthene	0.00200	0.000509	0.00257	0.00250	103	99.5	1	44.0-153			2.76	20
cenaphthylene	0.00200	U	0.00206	0.00199	103	99.5	1	53.0-150			3.46	20
enzo(b)fluoranthene	0.00200	U	0.00179	0.00172	89.5	86.0	1	43.0-142			3.99	20
enzo(k)fluoranthene	0.00200	U	0.00189	0.00178	94.5	89.0	1	43.0-148			5.99	21
hrysene	0.00200	U	0.00197	0.00190	98.5	95.0	1	50.0-148			3.62	20
luoranthene	0.00200	0.0000280	0.00199	0.00192	98.1	94.6	1	56.0-157			3.58	20
luorene	0.00200	0.00440	0.00646	0.00639	103	99.5	1	48.0-148			1.09	20
aphthalene	0.00200	0.00609	0.00809	0.00806	100	98.5	1	10.0-160			0.372	20
henanthrene	0.00200	0.000937	0.00298	0.00289	102	97.6	1	47.0-147			3.07	20
yrene	0.00200	U	0.00223	0.00219	111	109	1	51.0-148			1.81	20
-Methylnaphthalene	0.00200	0.00138	0.00330	0.00325	96.0	93.5	1	31.0-160			1.53	20
(S) Nitrobenzene-d5					108	103		31.0-160				
(S) 2-Fluorobiphenyl					100	97.0		48.0-148				

96.5

100

37.0-146





















ONE LAB. NATIONWIDE.

Sc

Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

L1231742-09

#### Method Blank (MB)

(S) p-Terphenyl-d14

(MB) R3542739-3 06/2	5/20 01:54				
	MB Result	MB Qualifier	MB MDL	MB RDL	
Analyte	mg/l		mg/l	mg/l	
Anthracene	U		0.0000190	0.0000500	
Acenaphthene	U		0.0000190	0.0000500	
Acenaphthylene	U		0.0000171	0.0000500	
Benzo(b)fluoranthene	U		0.0000168	0.0000500	
Benzo(k)fluoranthene	U		0.0000202	0.0000500	
Chrysene	U		0.0000179	0.0000500	
Fluoranthene	U		0.0000270	0.000100	
Fluorene	U		0.0000169	0.0000500	
Naphthalene	U		0.0000917	0.000250	
Phenanthrene	U		0.0000180	0.0000500	
Pyrene	U		0.0000169	0.0000500	
2-Methylnaphthalene	U		0.0000674	0.000250	
(S) Nitrobenzene-d5	132			31.0-160	
(S) 2-Fluorobiphenyl	95.0			48.0-148	

### Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

37.0-146

91.5

	Spike Amount	LCS Result	LCSD Result	LCS Rec.	LCSD Rec.	Rec. Limits	LCS Qualifier	LCSD Qualifier	RPD	RPD Limits
Analyte	mg/l	mg/l	mg/l	%	%	%			%	%
Anthracene	0.00200	0.00242	0.00235	121	117	67.0-150			2.94	20
Acenaphthene	0.00200	0.00204	0.00199	102	99.5	65.0-138			2.48	20
Acenaphthylene	0.00200	0.00200	0.00196	100	98.0	66.0-140			2.02	20
Benzo(b)fluoranthene	0.00200	0.00237	0.00228	118	114	58.0-141			3.87	20
Benzo(k)fluoranthene	0.00200	0.00245	0.00262	122	131	58.0-148			6.71	20
Chrysene	0.00200	0.00247	0.00243	123	122	64.0-144			1.63	20
Fluoranthene	0.00200	0.00246	0.00243	123	122	69.0-153			1.23	20
Fluorene	0.00200	0.00211	0.00205	105	103	64.0-136			2.88	20
Naphthalene	0.00200	0.00208	0.00203	104	102	61.0-137			2.43	20
Phenanthrene	0.00200	0.00215	0.00210	107	105	62.0-137			2.35	20
Pyrene	0.00200	0.00226	0.00221	113	111	60.0-142			2.24	20
2-Methylnaphthalene	0.00200	0.00192	0.00188	96.0	94.0	62.0-136			2.11	20
(S) Nitrobenzene-d5				133	130	31.0-160				
(S) 2-Fluorobiphenyl				95.0	92.5	48.0-148				
(S) p-Terphenyl-d14				88.5	87.0	37.0-146				

ONE LAB. NATIONWIDE.

Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

L1231742-10,11

#### Method Blank (MB)

(MB) R3543018-3 06/2!	5/20 14:21						
	MB Result	MB Qualifier	MB MDL	MB RDL			
Analyte	mg/l		mg/l	mg/l			
Anthracene	U		0.0000190	0.0000500			
Acenaphthene	U		0.0000190	0.0000500			
Acenaphthylene	U		0.0000171	0.0000500			
Benzo(b)fluoranthene	U		0.0000168	0.0000500			
Benzo(k)fluoranthene	U		0.0000202	0.0000500			
Chrysene	U		0.0000179	0.0000500			
Fluoranthene	U		0.0000270	0.000100			
Fluorene	U		0.0000169	0.0000500			
Naphthalene	U		0.0000917	0.000250			
Phenanthrene	U		0.0000180	0.0000500			
Pyrene	U		0.0000169	0.0000500			
2-Methylnaphthalene	U		0.0000674	0.000250			
(S) Nitrobenzene-d5	139			31.0-160			
(S) 2-Fluorobiphenyl	80.5			48.0-148			
(S) p-Terphenyl-d14	91.5			37.0-146			

### Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3543018-1 06/25/20 13:34 • (LCSI	D) R3543018-2	06/25/20 13:5	57		
Spike Amount	LCS Result	LCSD Result	LCS Rec.	LCSD Rec.	Rec. Limits

	Spike Amount	LCS Result	LCSD Result	LCS Rec.	LCSD Rec.	Rec. Limits	LCS Qualifier	LCSD Qualifier	RPD	RPD Limits
Analyte	mg/l	mg/l	mg/l	%	%	%			%	%
Anthracene	0.00200	0.00228	0.00225	114	112	67.0-150			1.32	20
Acenaphthene	0.00200	0.00189	0.00187	94.5	93.5	65.0-138			1.06	20
Acenaphthylene	0.00200	0.00196	0.00173	98.0	86.5	66.0-140			12.5	20
Benzo(b)fluoranthene	0.00200	0.00229	0.00216	115	108	58.0-141			5.84	20
Benzo(k)fluoranthene	0.00200	0.00243	0.00252	122	126	58.0-148			3.64	20
Chrysene	0.00200	0.00240	0.00237	120	118	64.0-144			1.26	20
Fluoranthene	0.00200	0.00279	0.00235	140	117	69.0-153			17.1	20
Fluorene	0.00200	0.00198	0.00198	99.0	99.0	64.0-136			0.000	20
Naphthalene	0.00200	0.00175	0.00175	87.5	87.5	61.0-137			0.000	20
Phenanthrene	0.00200	0.00202	0.00199	101	99.5	62.0-137			1.50	20
Pyrene	0.00200	0.00221	0.00219	111	109	60.0-142			0.909	20
2-Methylnaphthalene	0.00200	0.00157	0.00150	78.5	75.0	62.0-136			4.56	20
(S) Nitrobenzene-d5				138	128	31.0-160				
(S) 2-Fluorobiphenyl				79.0	65.5	48.0-148				
(S) p-Terphenyl-d14				89.0	88.0	37.0-146				

#### **GLOSSARY OF TERMS**

#### Guide to Reading and Understanding Your Laboratory Report

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.

Results Disclaimer - Information that may be provided by the customer, and contained within this report, include Permit Limits, Project Name, Sample ID, Sample Matrix, Sample Preservation, Field Blanks, Field Spikes, Field Duplicates, On-Site Data, Sampling Collection Dates/Times, and Sampling Location. Results relate to the accuracy of this information provided, and as the samples are received.

#### Abbreviations and Definitions

MDL	Method Detection Limit.
RDL	Reported Detection Limit.
Rec.	Recovery.
RPD	Relative Percent Difference.
SDG	Sample Delivery Group.
(S)	Surrogate (Surrogate Standard) - Analytes added to every blank, sample, Laboratory Control Sample/Duplicate and Matrix Spike/Duplicate; used to evaluate analytical efficiency by measuring recovery. Surrogates are not expected to be detected in all environmental media.
U	Not detected at the Reporting Limit (or MDL where applicable).
Analyte	The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported.
Dilution	If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor.
Limits	These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges.
Original Sample	The non-spiked sample in the prep batch used to determine the Relative Percent Difference (RPD) from a quality control sample. The Original Sample may not be included within the reported SDG.
Qualifier	This column provides a letter and/or number designation that corresponds to additional information concerning the resu reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable.
Result	The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state "ND" (Not Detected) or "BDL" (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte.
Uncertainty (Radiochemistry)	Confidence level of 2 sigma.
Case Narrative (Cn)	A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report.
Quality Control Summary (Qc)	This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material.
Sample Chain of Custody (Sc)	This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis.
Sample Results (Sr)	This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section fo each sample will provide the name and method number for the analysis reported.
Sample Summary (Ss)	This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis.
Qualifier	Description

<b>Qualifie</b>	Beschption
J	The identification of the analyte is acceptable; the reported value is an estimate.
J2	Surrogate recovery limits have been exceeded; values are outside lower control limits.

















#### **ACCREDITATIONS & LOCATIONS**





#### **State Accreditations**

Alabama	40660
Alaska	17-026
Arizona	AZ0612
Arkansas	88-0469
California	2932
Colorado	TN00003
Connecticut	PH-0197
Florida	E87487
Georgia	NELAP
Georgia <sup>1</sup>	923
Idaho	TN00003
Illinois	200008
Indiana	C-TN-01
lowa	364
Kansas	E-10277
Kentucky 16	90010
Kentucky <sup>2</sup>	16
Louisiana	Al30792
Louisiana <sup>1</sup>	LA180010
Maine	TN0002
Maryland	324
Massachusetts	M-TN003
Michigan	9958
Minnesota	047-999-395
Mississippi	TN00003
Missouri	340
Montana	CERT0086

Nebraska	NE-OS-15-05
Nevada	TN-03-2002-34
New Hampshire	2975
New Jersey-NELAP	TN002
New Mexico <sup>1</sup>	n/a
New York	11742
North Carolina	Env375
North Carolina <sup>1</sup>	DW21704
North Carolina <sup>3</sup>	41
North Dakota	R-140
Ohio-VAP	CL0069
Oklahoma	9915
Oregon	TN200002
Pennsylvania	68-02979
Rhode Island	LAO00356
South Carolina	84004
South Dakota	n/a
Tennessee 1 4	2006
Texas	T104704245-18-15
Texas <sup>5</sup>	LAB0152
Utah	TN00003
Vermont	VT2006
Virginia	460132
Washington	C847
West Virginia	233
Wisconsin	9980939910
Wyoming	A2LA

#### Third Party Federal Accreditations

A2LA – ISO 17025	1461.01
A2LA - ISO 17025 5	1461.02
Canada	1461.01
EPA-Crypto	TN00003

AIHA-LAP,LLC EMLAP	100789
DOD	1461.01
USDA	P330-15-00234

<sup>&</sup>lt;sup>1</sup> Drinking Water <sup>2</sup> Underground Storage Tanks <sup>3</sup> Aquatic Toxicity <sup>4</sup> Chemical/Microbiological <sup>5</sup> Mold <sup>6</sup> Wastewater n/a Accreditation not applicable

#### Our Locations

Pace National has sixty-four client support centers that provide sample pickup and/or the delivery of sampling supplies. If you would like assistance from one of our support offices, please contact our main office. Pace National performs all testing at our central laboratory.



















			Billing Info	rmation:						Analysis	/ Conta	iner / Preser	vative		Chain o	Custody	Page 1 of
EarthCon Consultants, GA 1880 West Oak Pkwy.	Inc - Mari				1880 West Oak Pkwy, Bld 100, Suite106										-/2	Pace Analytical National Center for Testing & Innovation	
Report to:			Email To:													ebanon Rd	回機器回
Doug Seely			dseely@ea	arthcon.com	n;dadkins	@earthcon	.com	es							Phone: 6	uliet, TN 371 515-758-585	3 (A)
Project Description:		City/State Collected:	Lina	ac va	4	Please Ci		NoPre	F							300-767-585 758-5859	可控制
P Wiggins	Client Projec		w lygn i	Lab Proje	ct #	SAMS.		N	N-S						SDG #	412	31742
hone: 770-973-2100		www.	20	PREMO	MGA-V	WIGGINSA	AP9	I Amb	oPre	72 72					take	H22	9
Collected by (print):  14mherly Barfield	Site/Facility			P.O.#				100ml	N-dmi								MOMGA
Collected by (signature):  Thimbly Boufull  mmediately		(Lab MUST Be Day Five Day 5 Day		(Rad Only) Date		e Results Needed		8270PCP-long list	PAHSIMLVI 40mlAmb-NoPres-WT						Prelog	Template: <b>T168702</b> Prelogin: <b>P776524</b> PM: <b>526</b> - Chris McCord	
Packed on Ice N Y X	Three		iy (Nau Only)				No. of	PCP	M						-	PB: C& Le 3 2020 Shipped Via: FedEX Ground	
Sample ID	Comp/Grab	Matrix *	Depth	Dat	te	Time	Cntrs	1270	AHS	5	圖				-	emarks	Sample # (lab only)
WP-1	Grab	GW		6-17-	20	10:30	4	X	X								-c1
WP-2		GW				16:28	4	X	Х								
DUP-02		GW				16:35	4	X	Х	7.4						400	ng
WC-8A		GW				15:26	4	X	X			7 7					-cy
WC-43		GW	14.15			11:20	4	X	X	200 m - 100							-05
WCP-8		GW				12:07	4	X	Х	1							-c6
mcb-8 melmen		GW				12:07	4	X	Х								-4
EB-2		GW		1 1		11:43	4	X	Х							## J	-07
WG56		GW		6-18-	20	08:44	4	X	X	Sec.							-el
PUP-03	V	GW	-2	1		08:47	4	X	Х						200	,	-4
Matrix: SS - Soil AIR - Air F - Filter SW - Groundwater B - Bioassay WW - WasteWater	Remarks:									pH Flov	in trade	Temp Other		COC Seal COC Sign Bottles Correct	Sample Recoll Present/ ned/Accura arrive in bottles u	Intact: te: tact: sed:	
DW - Drinking Water OT - Other	Samples returned via:UPSK FedExCourier					Tracking # 1790 3033 3168								Sufficient volume sent:  If Applicable  VOA Zero Headspace:			
Relinquished by: (Signature)  Numberly By Loulo  (0-18-2020 17:00			Received	d by: (Signat	ture)			Trip Bla	nk Rec	eived: Yes HCI TBR	No // MeoH		Preservation Correct/Checked: _Y_N RAD Screen <0.5 mR/hr:N				
Relinquished by: (Signature)				Received	d by: (Signat	ture)		χ.	Temp!	412	°C Bottles Received		If preservation required by Logi			in: Date/Time	
Relinquished by : (Signature)	C	Date:	Time	e: 4	Received	d for lab by:	(Signat	ure	101	Date:	0-2	Time:	345	Hold:			Condition:

ForthCon Consultants L	nc - Mari	ietta	Billing Infor		X	Pres			Analysis	/ Conta	iner / Pres	servative			Chain of Custoo	dy Page <u>Z</u> of <u>Z</u>	
EarthCon Consultants, Inc - Marietta, GA  1880 West Oak Pkwy.			ACCOUNTS FAVABLE												National Center for Testing & Innoversity  12065 Lebanon Rd Mount Juliet, TN 37122 Phone: 615-758-5858		
eport to: Email To: dseely@earthcon.com					kins@earthco	on.com	es										
Project Description:	14-1	City/State Collected: (	Wida:	ns, ms	Please O		NoPres	TW							Phone: 800-767-5859 Fax: 615-758-5859		
Phone: 770-973-2100	Client Projec		VV	Lab Project # PREMOMGA-WIGGINSAPS		CA DO	Amb 1	res-1							SDG# L1771742		
	02.700	W06.2	0	PREIVIOIVIG	A-Widdill.	30, 3	A In	NoP							Table #		
ollected by (print): Camperly Barfield	Site/Facility	ID#	ober 1	P.O. #			t 100n	-qmy						Acctnum: PREMOMGA Template: T168702			
nmediately Packed on Ice N Y X	Same	(Lab MUST Be Day Five Day 5 Day ay 10 Day	Day (Rad Only)	(Rad Only) Date Results Needed		No.	8270PCP-long list 100ml	PAHSIMLVI 40mlAmb-NoPres-WT		Non Add				Prelogin: P7 PM: 526 - Ch	76524 ris McCord Le[3 2000		
Sample ID	Comp/Grab	Matrix *	Depth	Date	Time	Cntrs	8270F	PAHSI							Shipped Via: Remarks	FeďEX Ground Sample # (lab only)	
WC-57	Grab	GW	1. 2. 5	6-18-1	09:20	4	X	Х		4						-10	
pup-04	7	GW		17	09:25	4	X	X								-(1	
						1											
1 17 17 17 17 17 17 17 17 17 17 17 17 17				27 7.17		2 6											
																ė.	
						. "		2									
Matrix: SS - Soil AIR - Air F - Filter SW - Groundwater B - Bioassay NW - WasteWater	emarks:		1						pl- Flo	H	Temp			COC Signe Bottles a	mple Receipt Present/Intac ed/Accurate: arrive intact: cottles used:	-7_N	
OT - Other	amples returne UPS <u>X</u> FedE	x _ Courier			king # 179	STATE OF THE PERSON NAMED IN	33 3	3168			and Pro			Sufficient volume sent:  If Applicable  VOA Zero Headspace:  Preservation Correct/Checked:			
Relinquished by : (Signature) Munululy Balcill		Date: 6-18-WT		7:00	eived by: (Sign		7 3		V Inb 81	th.M	(	HCL MeoH		RAD Scree	en <0.5 mR/hr:	_Y _N	
Relinquished by : (Signature)		Date:	Time	e: Rec	eived by: (Sign	ature)		X	Temp:	711	°C Bott	les Received		ir preservat	tion required by t	ogin: Date/Time	
Relinquished by : (Signature)		Date:	Time	e: Rec	eived for lab b	y: (Signa	ture)	13	Date:	07.0	Tim	e: 0546	1	Hold:		Condition: NCF NOK	



EarthCon Consultants, Inc.

401 Fontaine Place Suite 102 Ridgeland, Mississippi 39110

> P: 601-853-2134 F: 770-973-7395 www.earthcon.com

#### Memorandum

Date: July 29, 2020

To: Darrell Adkins, EarthCon Consultants

From: Carol Cummins, Project Scientist

Subject: Quality Assurance Review

Project: Groundwater Monitoring, International Paper Wiggins,

Mississippi

Sampling Dates: June 15-18, 2020 Project Number: 02.20000006.20

SDG Number: L1231742 and L1231761

#### 1.0 Introduction

This memorandum presents the cursory validation of the sample analyses listed in Table 1. The samples were analyzed for selected volatile organic compounds (VOCs), semivolatile organic compounds (SVOCs) and polycyclic aromatic hydrocarbons (PAHs) by Pace Analytical Services located in St. Rose, Louisiana.

The criteria used to qualify data are from the *Contract Laboratory Program National Functional Guidelines for Organic Data Review* (USEPA 2008), the Wiggins *Groundwater Monitoring Plan/Sampling and Analysis Plan* (SAP; Premier 2010), the analytical methods, or the professional judgment of the validation chemist. The following laboratory deliverables were reviewed during the validation process:

- Chain-of-custody (COC) documentation to assess holding times and verify report completeness
- Laboratory quality control (QC) sample results, including method blanks, surrogate spikes, laboratory control samples (LCSs), laboratory control sample duplicates (LCSDs), and matrix spike/matrix spike duplicates (MS/MSDs)
- Analytical results to verify reporting limits
- Field QC samples to assess field blank contamination and field duplicate precision

The field duplicate precision is presented in Table 2 and the qualified data are summarized in Section 5. Data qualifier flags have been added to the sample results in the hardcopy laboratory report used for validation.

**Table 1—Sample Data Reviewed** 

	1 abic 1	Sumpre Bu	ta iteviewea	
Sample ID	Laboratory ID	VOCs a	SVOCs (Full Scan) <sup>b</sup>	PAHs (SIM) <sup>c</sup>
WP-1	L1231742-01	X	X	X
WP-2	L1231742-02	X	X	X
DUP-02	L1231742-03	X	X	X
WC-8A	L1231742-04	X	X	X
WC-43	L1231742-05	X	X	X
WCP-8	L1231742-06	X	X	X
EB-2	L1231742-07	X	X	X
WC-56	L1231742-08	X	X	X
DUP-03	L1231742-09	X	X	X
WC-57	L1231742-10	X	X	X
DUP-04	L1231742-11	X	X	X
WC-8	L1231761-01		X	
WC-39	L1231761-02		X	
WC-41	L1231761-03		X	
WC-44	L1231761-04		X	
EB-1	L1231761-05		X	
WC-11	L1231761-06		X	
DUP-01	L1231761-07		X	
WC-26	L1231761-08		X	

<sup>&</sup>lt;sup>a</sup> Volatile organic compounds (ethylbenzene and total xylenes) by Method 8260B (USEPA 1996)

#### 2.0 Data Validation Findings

#### 2.1 Custody, Preservation, and Completeness

Sample custody was maintained as required from sample collection to receipt at the laboratory. The samples were received intact and were properly preserved. The report is complete and contains results for the samples and tests requested on the COC forms.

#### 2.2 Volatile Organic Analyses

Selected samples were analyzed for ethylbenzene and total xylenes by Method 8260B.

#### 2.2.1 Holding Times

The samples were analyzed within the required holding time of 14 days from collection for preserved water samples.

b Semivolatile organic compounds (carbazole, dibenzofuran, 2,4-dichlorophenol, 2,4-dimethylphenol, 2-methylphenol, 3&4-methylphenol, phenol, pentachlorophenol, 2,4,6-trichlorophenol, and 2,3,4,6-tetrachlorophenol) by Method 3510C/8270 full scan (USEPA 1996)

Polycyclic aromatic hydrocarbons (anthracene, acenaphthene, acenaphthylene, benzo(b)fluoranthene, benzo(k)fluoranthene, chrysene, fluoranthene, fluorene, naphthalene, phenanthrene, pyrene, and 2-methylnapthlene) by Method 3510C/8270 selected ion monitoring (SIM) (USEPA 1996)

#### 2.2.2 Blank Analyses

#### 2.2.2.1 Method Blanks

A method blank was analyzed at the required frequency. Target VOCs were not detected above the method detection limits (MDLs) in the method blank.

#### 2.2.2.2 Equipment Rinse Blanks

An equipment rinse blank (EB-2) was collected with the samples. Target VOCs were not detected above the MDLs in the rinse blank.

#### 2.2.2.3 Trip Blanks

A trip blank was not collected with the samples.

#### 2.2.3 Surrogate Analyses

Surrogate compounds were added to the sample, blanks, and QC samples as required. The recovery values are within the laboratory QC limits.

#### 2.2.4 Matrix Spike/Matrix Spike Duplicate Analyses

A MS/MSD was not reported with the VOC analyses. The acceptable LCS recovery values indicate the accuracy of the analytical system is in control. Data qualifiers are not required due to the lack of QC results.

#### 2.2.5 Laboratory Control Sample Analyses

LCSs were analyzed as required. The recovery values are within the laboratory QC limits.

#### 2.2.6 Laboratory Reporting Limits

The permit-required reporting limits for ethylbenzene and total xylenes (SAP Table 4) were met by the reporting detection limits (RDLs).

#### 2.2.7 Field Duplicates

Three field duplicate pairs were collected for VOC analyses: DUP-02/WP-2, DUP-03/WC-56, and DUP-04/WC-57. RPD values could not be calculated because no target VOCs were detected in the samples or their duplicates.

#### 2.2.8 Overall Assessment of Data Usability

The usability of the data is based on the EPA guidance documents noted previously. Upon consideration of the information presented here, the data are acceptable for their intended use.

#### 2.3 Semivolatile Organic Analyses (Full Scan and SIM)

The samples were analyzed for selected SVOCs compounds by Method 3510C/8270 full scan and selected samples were analyzed for polycyclic aromatic hyrdocarbons (PAHs) by Method 3510C/8270 SIM.

#### 2.3.1 Holding Times

The samples were extracted within the required holding time of seven days from collection. The sample extracts were analyzed within the required holding time of 40 days from extraction.

#### 2.3.2 Blank Analyses

#### 2.3.2.1 Method Blanks

Method blanks were analyzed at the required frequency of one per extraction batch for full scan and SIM analyses. Semivolatile organic compounds were not detected above the MDLs in the method blanks.

#### 2.3.2.2 Equipment Rinse Blanks

Two equipment rinse blanks (EB-1 and EB-2) were collected with the samples. SVOCs were not detected above the MDLs in the equipment rinse blanks, except as noted below.

• Pentachlorophenol was detected in EB-2 at 0.00182 mg/L. Pace re-extracted and re-analyzed the sample and verified the initial result, which should be reported. Functional Guidelines prescribes three qualifications schemes for organic blank contamination reported to the MDL: associated sample concentrations greater than the action level (five times the blank concentration) are not qualified; associated sample concentrations less than the action limit and less than the RDL are qualified as not detected at the RDL and associated sample concentrations less than the action level and above the RDL are qualified as undetected (U) at the reported value. Two samples required qualification as shown below and in Section 5.

Sample ID	Analyte	Qualifier	Quality Control Exceedance
WP-1	Pentachlorophenol	U	Result < 5X EB-2 concentration
WC-8A	Pentachlorophenol	U @ RL	Result < 5X EB-2 concentration and < RL

#### 2.3.3 Surrogate Analyses

Surrogate compounds were added to the samples, blanks, and QC samples as required. The recovery values are within the laboratory QC limits, with two exceptions.

• The surrogate recovery values of 2-fluorobiphenyl and p-terphenyl-d<sub>14</sub> for the SIM analysis of sample SP-1 were below the laboratory control limits with values of 22.7 and 17.0, indicating a potential low bias. Positive SIM results

are qualified as estimated (J) and undetected results are qualified as estimated detection limit (UJ), as shown below and in Section 5.

Sample ID	Analyte	Qualifier	Quality Control Exceedance
WP-1	PAHs (SIM)	J – Positive results	Surrogate recovery <
		UJ – Undetected results	Laboratory control limits

#### 2.3.4 Matrix Spike/Matrix Spike Duplicate Analyses

MS/MSD results for sample WCP-8 were reported for the full scan and SIM SVOCs as required in the SAP. The recovery and RPD values are within the laboratory control limits.

#### 2.3.5 Laboratory Control Sample Analyses

LCS or LCS/LCSD results were reported as required for the full scan and SIM analyses. The recovery values are within the laboratory QC limits.

#### 2.3.6 Laboratory Reporting Limits

The project-required limits were met by the reporting detection limit (RDL) or MDL for monitoring constituents in undiluted samples.

#### 2.3.7 Field Duplicates

Four field duplicate pairs were collected with the samples: DUP-01/WC-11, DUP-02/WP-2, DUP-03/WC-56, and DUP-04/WC-57. RPD values less than or equal to 35 are considered acceptable precision for water samples. RPD values were not calculated for the field duplicate analysis for WC-11 and WP-2 because no semivolatile compounds were detected in either the sample or its duplicate. RPD values for the other samples are acceptable, with one exception.

- The fluoranthene RPD value for the field duplicate analysis of sample WC-56 is above the RPD criterion at 41 as shown in Table 2. The fluoranthene result for WC-56 and DUP-03 is qualified as estimated (J) due to the poor precision of the duplicate analysis, as shown below and in Section 5.
- The 2-methylnaphthalene RPD value for the field duplicate analysis of sample WC-57 is above the RPD criterion at 47 as shown in Table 2. The 2-methylnaphthalene result for WC-57 and DUP-04 is qualified as estimated (J) due to the poor precision of the duplicate analysis, as shown below and in Section 5.

Sample ID	Analyte	Qualifier	Quality Control Exceedance
WC-56	Fluoranthene	J	RPD value > QC criterion
DUP-03	Fluoranthene	J	RPD value > QC criterion
WC-57	2-methylnaphthalene	J	RPD value > QC criterion

Sample ID	Analyte	Qualifier	<b>Quality Control Exceedance</b>
DUP-04	2-methylnaphthalene	J	RPD value > QC criterion

#### 2.3.8 Overall Assessment of Data Usability

Upon consideration of the information presented here, the data are acceptable as qualified for their intended use.

#### 3.0 Data Qualifier Definitions

The following data validation qualifiers were used in the review of this data set. These qualifiers are from the *Contract Laboratory Program National Functional Guidelines for Organic Data Review*.

- U The analyte was analyzed for but not detected above the reported sample quantitation limit.
- J The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
- UJ The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
- N The analysis indicates the presence of an analyte for which there is presumptive evidence to make a "tentative identification".
- NJ The analysis indicates the presence of an analyte that has been "tentatively identified" and the associated numerical value represents its approximate concentration.
- R The sample results are rejected due to serious deficiencies in the ability to analyze the samples and meet quality control criteria. The presence or absence of the analyte cannot be verified.

#### 4.0 References

Premier. 2010. Groundwater Monitoring Plan/Sampling and Analysis Plan, Wiggins Treated Wood Products Facility. Prepared for International Paper. Prepared by Premier Environmental Services. January 2010.

USEPA. 1996. Test Methods for Evaluating Solid Waste, Physical/Chemical Methods (SW-846) Third Edition, Updates I, II, IIA, IIB, and III. United States Environmental Protection Agency. Office of Solid Waste. December 1996.

USEPA. 2008. Contract Laboratory Program National Functional Guidelines for Organic Data Review. U.S. Environmental Protection Agency Office of Emergency and Remedial Response. EPA540/R-99/008. June 2008.

## 5.0 Summary of Qualified Data

Listed below are the data qualified during the quality assurance review of this data set.

Sample ID	Analyte	Qualifier	<b>Quality Control Exceedance</b>	
WP-1	Pentachlorophenol	U	Result < 5X EB-2 concentration	
WC-8A	Pentachlorophenol	U @ RL	Result < 5X EB-2 concentration and < RL	
WP-1	PAHs (SIM)	J – Positive results UJ – Undetected results	Surrogate recovery < Laboratory control limits	
WC-56	Fluoranthene	J	RPD value > QC criterion	
DUP-03	Fluoranthene	J	RPD value > QC criterion	
WC-57	2-methylnaphthalene	J	RPD value > QC criterion	
DUP-04	2-methylnaphthalene	J	RPD value > QC criterion	

**Table 2. Field Duplicate Precision** 

Table 2. Field Duplicate Precision			
	WC-56	DUP-03	
Analyte	Result	Result	RPD
Fluoranthene	0.0000213	0.0000324	41
Phenanthrene	0.0000184	< 0.0000180	NC
	WC-57	DUP-04	
Analyte	Result	Result	RPD
Carbazole	< 0.000111	0.000144	NC
Dibenzofuran	0.00116	0.00152	27
Acenaphthene	0.00199	0.00165	19
Acenaphthylene	0.0000256	0.0000206	22
Benzo(b)fluoranthene	< 0.0000168	0.0000170	NC
Fluoranthene	0.0000340	0.0000371	8.7
Fluorene	0.00105	0.000888	17
Naphthalene	0.0591	0.0417	35
Phenanthrene	0.000566	0.00040	34
Pyrene	< 0.000169	0.0000397	NC
2-methylnaphthalene	0.00521	0.00323	47

Units – mg/L


RPD – Relative percent difference

NC - not calculated

Text and tables reviewed by: KJG 7/29/20



Environmental Challenges
BUSINESS SOLUTIONS ®



# **Groundwater Plume Analytics<sup>®</sup> Services**




The material contained in this presentation, including text, graphic representations and the oral description thereof, is the sole and exclusive property of EarthCon Consultants, Inc. and is considered Proprietary and Confidential. This material, or any copy, facsimile, photograph or other reproduction of whatever kind, may not be disseminated to any third party without the express written consent of EarthCon Consultants, Inc.

# **Groundwater Plume Analytics® Services**




Naphthalene

Pentachlorophenol



Naphthalene 1991

#### Concentration (µg/L)



Monitoring Well Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics

Plume Area: 42.5 acres


Plume Average Concentration: 577 µg/L

Plume Mass Indicator: 400 lbs


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior



Environmental Challenges © EarthCon 2020 BUSINESS SOLUTIONS



### Concentration (µg/L)



### LEGEND Monitoring Well

Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 43.7 acres

Plume Average Concentration: 740 µg/L


Plume Mass Indicator: 528 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)







49 Concentration (µg/L)

Well Not Sampled (Assigned Value Shown)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 46.9 acres

Plume Average Concentration: 500 µg/L


Plume Mass Indicator: 383 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but ratiner is meant to show conceptual behavior





### Concentration (µg/L)





Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 38.9 acres

Plume Average Concentration: 242 µg/L


Plume Mass Indicator: 153 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



### LEGEND Monitoring Well



Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 38.7 acres

Plume Average Concentration: 223 µg/L


Plume Mass Indicator: 141 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



Concentration (µg/L)

Monitoring Well

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 35.3 acres

Plume Average Concentration: 112 µg/L


Plume Mass Indicator: 64.4 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



# Monitoring Well

Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 32.9 acres

Plume Average Concentration: 91.6 µg/L


Plume Mass Indicator: 49.2 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)





Monitoring Well

Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 25.1 acres

Plume Average Concentration: 75.8 µg/L


Plume Mass Indicator: 31.0 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



### LEGEND

WC-B Monitoring Well

Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 19.9 acres

Plume Average Concentration: 28.1 µg/L


Plume Mass Indicator: 9.1 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



### LEGEND



WC-8 Monitoring Well

49 Concentration (µg/L)

Well Not Sampled (Assigned Value Shown)

Plume Center of Mass

▲ 2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 19.4 acres

Plume Average Concentration: 82.2 µg/L


Plume Mass Indicator: 26.1 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual purpose but rather is meant to show conceptual behavior of the afformation marker, our time are the properties.





### Concentration (µg/L)



### LEGEND

WC-B Monitoring Well

Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 16.8 acres

Plume Average Concentration: 53.0 µg/L


Plume Mass Indicator: 14.5 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



### LEGEND

WC-B Monitoring Well

NS (146)

Concentration (µg/L)

Well Not Sampled (Assigned Value Shown)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 14.7 acres

Plume Average Concentration: 47.6 µg/L


Plume Mass Indicator: 11.4 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



### LEGEND

Monitoring Well

Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 34.7 acres

Plume Average Concentration: 129 µg/L


Plume Mass Indicator: 73.1 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





Concentration (µg/L)





Monitoring Well

Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 20.7 acres

Plume Average Concentration: 187 µg/L


Plume Mass Indicator: 63.1 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





Concentration (µg/L)







Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 21.5 acres

Plume Average Concentration: 137 µg/L


Plume Mass Indicator: 48.0 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



### LEGEND Monitoring Well

Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 18.0 acres

Plume Average Concentration: 137 µg/L


Plume Mass Indicator: 40.1 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



### LEGEND Monitoring Well

¥

40 Concentration (µg/L)

Well Not Sampled (Assigned Value Shown)

Plume Center of Mass

2007 ISCO Injection Point

△ 2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 21.4 acres

Plume Average Concentration: 164 µg/L


Plume Mass Indicator: 57.3 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



### LEGEND Monitoring Well

Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 22.1 acres

Plume Average Concentration: 112 µg/L


Plume Mass Indicator: 40.3 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)





Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 22.5 acres

Plume Average Concentration: 98.2 µg/L


Plume Mass Indicator: 36.0 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)





Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 21.7 acres

Plume Average Concentration: 120 µg/L


Plume Mass Indicator: 42.6 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





Concentration (µg/L)





¥

49 Concentration (µg/L)

Well Not Sampled (Assigned Value Shown)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 17.9 acres

Plume Average Concentration: 389 µg/L


Plume Mass Indicator: 113 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopistin maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior of the actual metrics up the constitution.





### Concentration (µg/L)



Concentration (µg/L)

Monitoring Well

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 21.0 acres

Plume Average Concentration: 290 µg/L


Plume Mass Indicator: 99.3 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior






### Concentration (µg/L)









Well Not Sampled (Assigned Value Shown)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 15.9 acres

Plume Average Concentration: 293 µg/L


Plume Mass Indicator: 76.3 lbs


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual pume but rather is meant to show conceptual behavior





Concentration (µg/L)





2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 15.5 acres

Plume Average Concentration: 247 µg/L


Plume Mass Indicator: 62.6 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual pume but rather is meant to show conceptual behavior.





Concentration (µg/L)





Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 14.6 acres

Plume Average Concentration: 221 µg/L


Plume Mass Indicator: 52.8 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



### LEGEND Monitoring Well

Concentration (µg/L)

WC-B

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 11.3 acres

Plume Average Concentration: 190 µg/L


Plume Mass Indicator: 35.1 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





Concentration (µg/L)





¥

40 Concentration (µg/L)

Well Not Sampled (Assigned Value Shown)

Plume Center of Mass

▲ 2007 ISCO Injection Point

△ 2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 16.8 acres

Plume Average Concentration: 209 µg/L


Plume Mass Indicator: 57.4 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



### LEGEND

Monitoring Well

Concentration (µg/L)

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 14.3 acres

Plume Average Concentration: 192 µg/L


Plume Mass Indicator: 44.9 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)





¥

Concentration (µg/L)

Well Not Sampled (Assigned Value Shown)

Plume Center of Mass

▲ 2007 ISCO Injection Point

△ 2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 12.2 acres

Plume Average Concentration: 105 µg/L

Plume Mass Indicator: 21.0 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior.






#### 2002 to 2010

No Trend

Mann-Kendall: 87% Confidence Regression: 15% Confidence

#### 2011 to 2019

Decreasing Trend Mann-Kendall: 99% Confidence Regression: 97% Confidence




#### 2002 to 2010

No Trend

Mann-Kendall: 62% Confidence Regression: 46% Confidence

#### 2011 to 2019

Decreasing Trend Mann-Kendall: >99% Confidence Regression: >99% Confidence



#### 2002 to 2010

No Trend


Mann-Kendall: 76% Confidence Regression: 40% Confidence

#### 2011 to 2019

Decreasing Trend Mann-Kendall: >99% Confidence Regression: >99% Confidence








#### 2002 to 2010

No Trend

Mann-Kendall: 87% Confidence Regression: 15% Confidence

#### 2011 to 2019

Decreasing Trend Mann-Kendall: 99% Confidence Regression: 97% Confidence




#### 2002 to 2010

No Trend

Mann-Kendall: 62% Confidence Regression: 46% Confidence

#### 2011 to 2019

Decreasing Trend Mann-Kendall: >99% Confidence Regression: >99% Confidence



#### 2002 to 2010

No Trend


Mann-Kendall: 76% Confidence Regression: 40% Confidence


#### 2011 to 2019


Decreasing Trend Mann-Kendall: >99% Confidence Regression: >99% Confidence












Plume Differences 2011 vs 2012



2012 Plume Boundary

### **Plume Characteristics**

Naphthalene

Area: 18% Increase

Average Concentration: 26% Decrease


Mass Indicator: 13% Decrease Mass Increase: 15.0 lbs Increase Mass Decrease: 29.1 lbs Decrease


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior of the afforment/orang metrics over time.

Decrease




Increase





Plume Differences 2011 vs 2013



2011 Plume Boundary

2013 Plume Boundary

## **Plume Characteristics**

Naphthalene


Area: 11% Decrease


Average Concentration: 25% Decrease

Mass Indicator: 33% Decrease Mass Increase: 6.07 lbs Increase Mass Decrease: 43.3 lbs Decrease


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are plume but rather is meant to show conceptual behavior







Plume Differences 2011 vs 2014



### **Plume Characteristics**

Naphthalene


Area: 13% Decrease


Average Concentration: 37% Decrease


Mass Indicator: 45% Decrease
Mass Increase: 3.69 lbs Increase
Mass Decrease: 54.6 lbs Decrease

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior of the afforment/orang metrics questions.









2015 Plume Boundary

## Plume Characteristics

Area: 18% Decrease

Average Concentration: 43% Decrease


Mass Indicator: 54% Decrease Mass Increase: 2.48 lbs Increase Mass Decrease: 63.2 lbs Decrease


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior.

Decrease



Increase





### 

2016 Plume Boundary

## Plume Characteristics

Area: 37% Decrease

Average Concentration: 51% Decrease


Mass Indicator: 69% Decrease
Mass Increase: 2.34 lbs Increase
Mass Decrease: 80.8 lbs Decrease


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior of the affixement/need metrics quer time.


Decrease



Increase







2011 Plume Boundary

2017 Plume Boundary

## **Plume Characteristics**

Area: 6% Decrease

Average Concentration: 46% Decrease

Mass Indicator: 49% Decrease
Mass Increase: 2.81 lbs Increase
Mass Decrease: 58.9 lbs Decrease


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior of the afforment/insert metrics upto time.


Decrease




Increase

© EarthCon 2020 BUSINESS SOLUTIONS





Plume Differences 2011 vs 2018



2011 Plume Boundary

2018 Plume Boundary

Plume Characteristics

Area: 20% Decrease

Average Concentration: 51% Decrease


Mass Indicator: 60% Decrease Mass Increase: 2.32 lbs Increase Mass Decrease: 70.9 lbs Decrease


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior

Decrease




Increase





Plume Differences 2011 vs 2019



## **Plume Characteristics**


Area: 32% Decrease

Average Concentration: 73% Decrease

Mass Indicator: 81% Decrease Mass Increase: 0.27 lbs Increase Mass Decrease: 92.7 lbs Decrease

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior








Area: 32% Decrease

Average Concentration: 73% Decrease

Mass Indicator: 81% Decrease Mass Increase: 0.27 lbs Increase Mass Decrease: 92.7 lbs Decrease


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual penavior






O - hollow symbol indicates non-detect





## Concentration (µg/L)





Concentration (µg/L) 123

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 45.5 acres

Plume Average Concentration: 157 µg/L


Plume Mass Indicator: 117 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





## Concentration (µg/L)



### LEGEND Monitoring Well



Concentration (µg/L) 123

WC-8

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 42.2 acres

Plume Average Concentration: 66.0 µg/L


Plume Mass Indicator: 45.4 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



Concentration (µg/L) 123

Monitoring Well

MC-8

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 42.1 acres

Plume Average Concentration: 59.3 µg/L


Plume Mass Indicator: 40.8 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)





Concentration (µg/L) 123

WC-8

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 43.1 acres

Plume Average Concentration: 69.3 µg/L


Plume Mass Indicator: 48.7 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)









Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 42.2 acres

Plume Average Concentration: 92.8 µg/L


Plume Mass Indicator: 63.9 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)





Concentration (µg/L) 123

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 42.7 acres

Plume Average Concentration: 75.9 µg/L


Plume Mass Indicator: 52.9 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)





Concentration (µg/L) 123

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 42.4 acres

Plume Average Concentration: 66.8 µg/L


Plume Mass Indicator: 46.3 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



Concentration (µg/L) 123

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 44.6 acres

Plume Average Concentration: 96.2 µg/L


Plume Mass Indicator: 70.1 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



Concentration (µg/L) 123

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 43.1 acres

Plume Average Concentration: 37.8 µg/L


Plume Mass Indicator: 26.6 lbs


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





Concentration (µg/L)





2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 41.9 acres

Plume Average Concentration: 83.0 µg/L


Plume Mass Indicator: 56.7 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



### LEGEND Monitoring Well

Concentration (µg/L) 123

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 36.7 acres

Plume Average Concentration: 75.1 µg/L


Plume Mass Indicator: 44.9 lbs


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





Concentration (µg/L)





2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 37.3 acres

Plume Average Concentration: 95.3 µg/L


Plume Mass Indicator: 58.0 lbs


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





Concentration (µg/L)





Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 39.0 acres

Plume Average Concentration: 62.8 µg/L


Plume Mass Indicator: 39.9 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





## Concentration (µg/L)



### LEGEND Monitoring Well

Concentration (µg/L) 123

MC-8

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 25.0 acres

Plume Average Concentration: 86.5 µg/L


Plume Mass Indicator: 35.3 lbs


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





Concentration (µg/L)





2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 25.1 acres

Plume Average Concentration: 55.7 µg/L


Plume Mass Indicator: 22.8 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





Concentration (µg/L)





# Plume Characteristics

Plume Area: 22.2 acres


Plume Average Concentration: 63.5 µg/L

Plume Mass Indicator: 23.0 lbs


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual pume but rather is meant to show conceptual behavior of the actual pulmer.



© EarthCon 2020 BUSINESS SOLUTIONS




### Concentration (µg/L)









Concentration (µg/L) 123

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 22.9 acres

Plume Average Concentration: 182 µg/L


Plume Mass Indicator: 68.0 lbs


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





Concentration (µg/L)





## Plume Characteristics


Plume Area: 21.7 acres

Plume Average Concentration: 103 µg/L


Plume Mass Indicator: 36.3 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





## Concentration (µg/L)



Concentration (µg/L) 123

Well Not Sampled (Assigned Value Shown) NS (146)

Monitoring Well

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 30.6 acres

Plume Average Concentration: 68.7 µg/L


Plume Mass Indicator: 34.2 lbs


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual penavior





Concentration (µg/L)





# Plume Characteristics

Plume Area: 20.4 acres

Plume Average Concentration: 33.3 µg/L


Plume Mass Indicator: 11.1 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior




Environmental Challenges

© EarthCon 2020 BUSINESS SOLUTIONS



### Concentration (µg/L)





WC-B Concentration (µg/L) 123

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 20.6 acres

Plume Average Concentration: 19.8 µg/L


Plume Mass Indicator: 6.6 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





## Concentration (µg/L)



### LEGEND Monitoring Well

Ÿ

123 Concentration (µg/L)

MC-8

Well Not Sampled (Assigned Value Shown)

Plume Center of Mass

△ 2007 ISCO Injection Point

△ 2011 ISCO Injection Point

## Plume Characteristics

Plume Area: 33.4 acres


Plume Average Concentration: 16.1 µg/L

Plume Mass Indicator: 8.8 lbs


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual pume but rather is meant to show conceptual behavior



© EarthCon 2020 BUSINESS SOLUTIONS



### Concentration (µg/L)





Concentration (µg/L) 123

MC-8

Well Not Sampled (Assigned Value Shown) NS (140)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 27.0 acres

Plume Average Concentration: 13.0 µg/L


Plume Mass Indicator: 5.7 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





## Concentration (µg/L)





♠

123 Concentration (µg/L)

Well Not Sampled (Assigned Value Shown)

Plume Center of Mass

2007 ISCO Injection Point

△ 2011 ISCO Injection Point

# Plume Characteristics

Plume Area: 26.9 acres


Plume Average Concentration: 10.0 µg/L

Plume Mass Indicator: 4.4 lbs


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual pume but rather is meant to show conceptual behavior.



© EarthCon 2020 BUSINESS SOLUTIONS



### Concentration (µg/L)



# Monitoring Well

Concentration (µg/L) 123

WC-B

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 17.2 acres

Plume Average Concentration: 9.0 µg/L


Plume Mass Indicator: 2.5 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



### LEGEND Monitoring Well



Concentration (µg/L) 123

WC-B

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

# Plume Characteristics


Plume Area: 17.5 acres

Plume Average Concentration: 6.6 µg/L


Plume Mass Indicator: 1.9 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





## Concentration (µg/L)



### LEGEND Monitoring Well



123 Concentration (µg/L)

WC-B

Well Not Sampled (Assigned Value Shown)

Plume Center of Mass

2007 ISCO Injection Point

△ 2011 ISCO Injection Point

# Plume Characteristics

Plume Area: 19.0 acres


Plume Average Concentration: 7.6 µg/L

Plume Mass Indicator: 2.3 lbs


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior




© EarthCon 2020 BUSINESS SOLUTIONS



Concentration (µg/L)





## Plume Characteristics


Plume Area: 15.7 acres

Plume Average Concentration: 6.8 µg/L


Plume Mass Indicator: 1.7 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior





### Concentration (µg/L)



### LEGEND Monitoring Well



Concentration (µg/L) 123

WC-B

Well Not Sampled (Assigned Value Shown) NS (146)

Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point

## Plume Characteristics


Plume Area: 15.7 acres

Plume Average Concentration: 11.3 µg/L

Plume Mass Indicator: 2.9 lbs

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior






### 2002 to 2010

Decreasing Trend Mann-Kendall: 98% Confidence Regression: 95% Confidence

### 2011 to 2019

Decreasing Trend Mann-Kendall: 99% Confidence Regression: 98% Confidence




### 2002 to 2010

No Trend Mann-Kendall: 62% Confidence

### 2011 to 2019

Regression: 45% Confidence

Decreasing Trend Mann-Kendall: 99% Confidence Regression: 99% Confidence




#### 2002 to 2010


No Trend/Decreasing Trend Mann-Kendall: 91% Confidence Regression: 83% Confidence

### 2011 to 2019

Decreasing Trend Mann-Kendall: 99% Confidence Regression: >99% Confidence








### 2002 to 2010

Decreasing Trend Mann-Kendall: 98% Confidence Regression: 95% Confidence

#### 2011 to 2019

Decreasing Trend Mann-Kendall: 99% Confidence Regression: 98% Confidence




### 2002 to 2010

No Trend Mann-Kendall: 62% Confidence

Regression: 45% Confidence

### 2011 to 2019

Decreasing Trend Mann-Kendall: 99% Confidence Regression: 99% Confidence




### 2002 to 2010

No Trend/Decreasing Trend Mann-Kendall: 91% Confidence Regression: 83% Confidence


#### 2011 to 2019


Decreasing Trend Mann-Kendall: 99% Confidence Regression: >99% Confidence







**BUSINESS SOLUTIONS** 







#### Plume Differences 2011 vs 2012



# Spatial Change Indicator™

Decrease Increase

# LEGEND Monitoring Well Plume Center of Mass 2007 ISCO Injection Point 2011 ISCO Injection Point 2011 Plume Boundary

2012 Plume Boundary

# **Plume Characteristics**

Area: 62% Increase


Average Concentration: 19% Decrease

Mass Indicator: 32% Increase Mass Increase: 4.13 lbs Increase


Mass Decrease: 2.01 lbs Decrease

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are plume but rather is meant to show conceptual penavior





#### Plume Differences 2011 vs 2013



#### Spatial Change Indicator™

Decrease Increase

# LEGEND Monitoring Well Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point
 2011 Plume Boundary

2013 Plume Boundary

# Plume Characteristics

Area: 31% Increase


Average Concentration: 34% Decrease

Mass Indicator: 14% Decrease
Mass Increase: 2.66 lbs Increase
Mass Decrease: 3.59 lbs Decrease


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual pume but rather is meant to show conceptual behavior of the afterpretional motific quiet time and actual pume.



© EarthCon 2020 BUSINESS SOLUTIONS



#### Plume Differences 2011 vs 2014



#### Spatial Change Indicator™

Decrease Increase

# LEGEND Monitoring Well Plume Center of Mass 2007 ISCO Injection Point 2011 ISCO Injection Point 2011 Plume Boundary

2014 Plume Boundary

# **Plume Characteristics**


Area: 31% Increase

Average Concentration: 49% Decrease


Mass Indicator: 34% Decrease Mass Increase: 1.96 lbs Increase Mass Decrease: 4.21 lbs Decrease

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are plume but rather is meant to show conceptual penavior






#### Plume Differences 2011 vs 2015



#### Spatial Change Indicator™

Decrease Increase



2011 Plume Boundary 2015 Plume Boundary

# Plume Characteristics


Area: 17% Decrease

Average Concentration: 54% Decrease


Mass Indicator: 62% Decrease Mass Increase: 0.43 lbs Increase Mass Decrease: 4.55 lbs Decrease

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are plume but rather is meant to show conceptual behavior





#### Plume Differences 2011 vs 2016



#### Spatial Change Indicator™

Decrease Increase

# WC-8 Monitoring Well → Plume Center of Mass △ 2007 ISCO Injection Point △ 2011 ISCO Injection Point

2011 Plume Boundary

2016 Plume Boundary

# **Plume Characteristics**

Area: 15% Decrease


Average Concentration: 67% Decrease


Mass Indicator: 72% Decrease
Mass Increase: 0.52 lbs Increase
Mass Decrease: 5.29 lbs Decrease

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior of the advergent/inject metrics quiet time.




© EarthCon 2020 BUSINESS SOLUTIONS





#### Plume Differences 2011 vs 2017



#### Spatial Change Indicator™

Decrease Increase

# LEGEND

Monitoring Well



2007 ISCO Injection Point

2011 ISCO Injection Point 2011 Plume Boundary

2017 Plume Boundary


Area: 8% Decrease Average Concentration: 62% Decrease

**Plume Characteristics** 


Mass Indicator: 65% Decrease Mass Increase: 0.82 lbs Increase Mass Decrease: 5.12 lbs Decrease


This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are plume but rather is meant to show conceptual behavior





Plume Differences 2011 vs 2018





Decrease Increase



Plume Center of Mass

2007 ISCO Injection Point

2011 ISCO Injection Point 2011 Plume Boundary

2018 Plume Boundary

# Plume Characteristics


Area: 24% Decrease

Average Concentration: 65% Decrease


Mass Indicator: 74% Decrease Mass Increase: 0.60 lbs Increase Mass Decrease: 5.50 lbs Decrease

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are plume but rather is meant to show conceptual penavior






Plume Differences 2011 vs 2019



#### Spatial Change Indicator<sup>TM</sup>

Decrease Increase



2011 ISCO Injection Point 2011 Plume Boundary

2019 Plume Boundary

# **Plume Characteristics**

Area: 24% Decrease


Average Concentration: 43% Decrease


Mass Indicator: 56% Decrease
Mass Increase: 0.66 lbs Increase
Mass Decrease: 4.41 lbs Decrease

This analysis requires fixed data points within a fixed area for the purposes of assessing relative changes of area, average concentration, and mass indicator over time. Therefore, any created isopleth maps are not intended to be a depiction or model of the actual plume but rather is meant to show conceptual behavior of the afterpretional motific quiet them.




© EarthCon 2020 BUSINESS SOLUTIONS











O - hollow symbol indicates non-detect





O - hollow symbol indicates non-detect





O - hollow symbol indicates non-detect

